

THE STEAM TURBINE

LIST OF BOOKS ON STEAM, OIL, AND GAS ENGINES

- A HAND-BOOK FOR STEAM USERS :** being Rules for Engine Drivers and Boiler Attendants, with Notes on Steam Engine and Boiler Management and Steam Boiler Explosions. By M. POWIS BALE, M.I.M.E., A.M.I.C.E. Fcap. 8vo, 2s. 6d.
- THE GAS AND OIL ENGINE.** By DUGALD CLERK, Member of the Institution of Civil Engineers, Fellow of the Chemical Society, Member of the Royal Institution, Fellow of the Institute of Patent Agents. With 228 Illustrations. 8vo, 15s.
- THE STEAM ENGINE.** By GEORGE C. V. HOLMES, Chairman of the Board of Works, Ireland. With 212 Woodcuts. Fcap. 8vo, 6s.
- A PRACTICAL TREATISE ON THE "OTTO" CYCLE GAS ENGINE.** By WILLIAM NORRIS, M.I.Mech.E. With 207 Illustrations. 8vo, 10s. 6d.
- STEAM.** By WILLIAM RIPPER, Professor of Mechanical Engineering in the Sheffield Technical School. With 142 Illustrations. Crown 8vo, 2s. 6d.
- STEAM ENGINE THEORY AND PRACTICE.** By WILLIAM RIPPER, Professor of Mechanical Engineering in the Sheffield Technical School. With 438 Illustrations. 8vo, 9s.
- THE MARINE STEAM ENGINE: A Treatise** for Engineering Students, Young Engineers and Officers of the Royal Navy and Mercantile Marine. By the late RICHARD SENNETT, Engineer-in-Chief of the Navy, etc.; and HENRY J. ORAM, Senior Engineer Inspector at the Admiralty, Inspector of Machinery in H.M. Fleet, etc. With 414 Diagrams. 8vo, 21s.
- MARINE BOILER MANAGEMENT AND CONSTRUCTION.** Being a Treatise on Boiler Troubles and Repairs, Corrosion, Fuels, and Heat, on the properties of Iron and Steel, on Boiler Mechanics, Workshop Practices, and Boiler Design. By C. E. STROMEYER, Chief Engineer of the Manchester Steam Users' Association, Member of Council of the Institution of Naval Architects, etc. With 452 Diagrams, etc. 8vo, 12s. net.

LONGMANS, GREEN, AND CO.
LONDON, NEW YORK, AND BOMBAY






PLATE I.—1000-KILOWATT PARSONS TURBIDO-ALTERNATOR FOR EBERFELD CORPORATION, AS ERECTED FOR THE TRIALS AT THE
HEATON WORKS, NEWCASTLE-ON-TYNE.

THE STEAM TURBINE

BY

ROBERT M. NEILSON

WHITWORTH EXHIBITIONER; ASSOCIATE MEMBER OF THE INSTITUTION OF MECHANICAL
ENGINEERS; MEMBER OF THE MANCHESTER ASSOCIATION OF ENGINEERS;
FELLOW OF THE CHARTERED INSTITUTE OF PATENT AGENTS;
LECTURER ON STEAM AND THE STEAM ENGINE AT THE HEGINBOTTOM TECHNICAL
SCHOOL, ASHTON-UNDER-LYNE



WITH NUMEROUS ILLUSTRATIONS



LONGMANS, GREEN, AND CO.

39 PATERNOSTER ROW, LONDON

NEW YORK AND BOMBAY

1902

All rights reserved

TJ735
N4

HALLIDIE

P R E F A C E

THAT the steam turbine is likely to be extensively used in the future is admitted by most engineers; but, although a good deal has lately been written about this type of engine, this literature has mostly consisted of descriptions of the principal features only, or of accounts of the results of tests.

The author has endeavoured in this book to describe, not only the principal parts of the leading types of steam turbine, but also the small details which, in the case of this motor, have such a preponderating influence in determining success or failure. The theory of the action of the steam turbine is also treated of, and the subject is likewise dealt with historically.

Comparisons have necessarily been made with the hydraulic turbine and with the reciprocating engine; but, with a view to extending the usefulness of the book, the author has assumed on the part of the reader no prior knowledge of the hydraulic turbine, and only an elementary knowledge of the reciprocating engine and of the laws of thermo-dynamics.

With a like object in view the author has tried to make the mathematical reasoning as simple as possible.

As entropy-temperature diagrams are not yet widely understood, a chapter on this subject has been given; but the matter has been treated as briefly as possible.

The results of tests of steam turbines given throughout the book have been carefully selected with a view to obtaining the strictest accuracy.

The author takes this opportunity of thanking the various individuals and firms who have given him information and assistance, and of expressing his indebtedness to Messrs. C. A. Parsons and Co., Newcastle-on-Tyne, and the Société de Laval of France for the loan of several blocks.

R. M. N.

30, CROSS STREET, MANCHESTER,
June, 1902.

CONTENTS

CHAPTER	PAGE
I. GENERAL REMARKS ON TURBINES	1
II. HISTORY OF THE STEAM TURBINE	7
III. HISTORY OF THE PARSONS STEAM TURBINE	38
IV. POINTS OF RESEMBLANCE AND DIFFERENCE BETWEEN THE STEAM TURBINE AND OTHER MOTORS	50
V. VANES AND VELOCITIES	57
VI. ENTROPY AND ENTROPY-TEMPERATURE DIAGRAMS	70
VII. THEORETICAL CONSIDERATION OF DIFFERENT TREATMENTS OF STEAM IN A HEAT-ENGINE	75
VIII. THE DE LAVAL STEAM TURBINE	90
IX. THE RATEAU STEAM TURBINE	106
X. FURTHER REMARKS ON THE PARSONS TURBINE	115
XI. SOME RECENT TESTS OF PARSONS TURBINES	126
XII. THE STEAM TURBINE APPLIED TO THE PROPULSION OF VESSELS	137
APPENDIX.—BRITISH PATENTS FOR OR RELATING TO STEAM TURBINES	
FROM THE EARLIEST RECORDS UP TO THE END OF 1899 .	149
INDEX	157



LIST OF ILLUSTRATIONS

PLATES.

PLATE	FACING PAGE
I. 1000-KILOWATT PARSONS TURBO-ALTERNATOR . . .	<i>Frontispiece</i>
II. PARSONS STEAM TURBINE COUPLED TO ALTERNATOR	48
III. 100-B.H.P. DE LAVAL TURBINE DYNAMO	100
IV. METROPOLITAN ELECTRIC SUPPLY COMPANY'S STATION	120
V. VICTORIAN RAILWAYS LIGHTING STATION	124
VI. PARSONS TURBINE COUPLED TO CENTRIFUGAL PUMP	126
VII. VENTILATING FAN DRIVEN BY PARSONS TURBINE	130
VIII. THE "TURBINIA"	138
IX. SET OF ENGINES FOR THE "VIPER"	140

ILLUSTRATIONS IN TEXT.

FIG.	PAGE
1. Diagrammatic Illustration of Turbine	1
2. Action of Steam in De Laval Turbine	3
2A. Section of Nozzle of De Laval Steam Turbine	3
3-5. Blades and Shrouds of a Parsons Parallel-flow Steam Turbine . . .	3, 4
6. Partial Axial Section of Parsons Parallel-flow Steam Turbine . . .	4
7. Cross-section of Parsons Parallel-flow Steam Turbine	4
8. Action of Steam on the Blades of a Parsons Turbine	5
9. Parsons Radial-flow Steam Turbine, Partial Axial Section	5
10. Blades and Shrouds of a Parsons Radial-flow Steam Turbine	6
11. Hero's Rotating Steam Globe	7
12. Wolfgang de Kempelen's Turbine	8
13. Details of Kempelen's Turbine	9
14-16. Watt's Turbine	11
17. Sadler's Engine	13
18. Cross-section of Sadler's Engine	14

FIG.	PAGE
19. Noble's Steam Wheel	15
20. Ericsson's Turbine	16
21, 22. Vanes and Channels of Ericsson's Turbine	17
23. Simple Turbine of Pilbrow's	18
24. Reversing Turbine of Pilbrow's	19
25. Pilbrow's Air-propeller	19
26. Combined Steam Turbine and Air-propeller	19
27. Pilbrow's Successive-expansion Turbine: Elevation	20
28. " " " Plan	21
29. " " " Nozzle and Vanes	21
30. Von Rathen's Turbine	22
31. Von Rathen's Reversing Turbine	23
32-35. Forms of Expanding Cone or Nozzle for Von Rathen's Turbine	24
36. Wilson's Radial-flow Turbine with Single Ring of Moving Blades: Sectional side elevation	25
37. Wilson's Radial-flow Turbine with Single Ring of Moving Blades: Half section and half front elevation	26
38. Path of the Steam through Wilson's Turbine	27
39. Wilson's Radial-flow Turbine with a series of Rings of Moving Blades	28
40. Wilson's Parallel-flow Turbine	29
41-46. Steam Turbine Details	31-33
47. Concentric Cylinders and Nozzles of Outward-flow Turbine of Morton's	33
48. Steam Duct and Nozzle of Outward-flow Turbine of Morton's	34
49. Steam Passages for Inward-flow Turbine of Morton's	34
50. Inward and Outward-flow Turbine of Morton's	34
51. Arrangement of Vanes and Channels in Morton's Turbine	35
52. Screw Type of Steam Turbine	36
53. Admission Plate	37
58. Early Parsons Turbine	39
59. Escaped-Steam Ejector	40
60. Bearing for Spindle in Early Parsons Turbine	40
61. Double-ended Parsons Turbine of Increasing Diameter	41
62, 63. Steam or Water-packing for Spindle of Parsons Turbine	42
64. Section of Parsons Radial-flow Turbine	43
65. Section of Balance Piston of same	44
66, 67. Bearing for Spindle of Parsons Turbine	45
68, 69. Elastic Bearing for Parsons Turbine	46
70. Thrust-block of Parsons Turbine	46
71. Slotted Ring for Thrust-block	46
72. Section of Parsons Parallel-flow Turbine	47
72A. Fixed and Moving Blades of Parsons Turbine	48
73. Relative Volumes of Steam and Water	52
74-78. Diagrams regarding Vane Velocities	58-62
78A. Diagram for proof regarding Effect of Centrifugal Force	64
79. Diagram showing Velocities of Fluid in a Compound Turbine, the volume of fluid being constant or increasing proportionately to increase of section of passages	66

FIG.	PAGE
80. Diagram showing Velocities of Fluid in a Compound Turbine, the volume of fluid increasing at a greater rate than section of passages	67
81. Passage of Steam through a Parsons Turbine	68
82. Entropy-temperature Diagram	72
83. Entropy-temperature Diagram for Water and Steam	72
84. Case I.: Adiabatic Expansion; isothermal compression; range of temperature, 85° F.—382° F.	76
85. Case II.: Expansion along Line of Dry Saturated Steam; isothermal compression; range of temperature, 85° F.—382° F.	77
86. Case III.: Expansion with Leakage of Heat; isothermal compression; range of temperature, 85° F.—382° F.	78
87. Case IV.: Superheating; Adiabatic Expansion; isothermal compression; range of temperature, 85° F.—540° F.	79
88. Case IV.A.: Superheating; Adiabatic Expansion; isothermal compression; range of temperature, 85° F.—382° F.	81
89. Case V.: Superheating; Expansion with Leakage of Heat; isothermal compression; range of temperature, 85° F.—540° F.	82
90. Case VI.: Expansion, partly adiabatic and partly unresisted; isothermal compression; range of temperature, 85° F.—382° F.	84
91. Case VII.: Adiabatic Expansion; heat rejected at constant volume, followed by isothermal compression; range of temperature, 85° F.—382° F.	85
92. Case VIII.: Superheating; Adiabatic Expansion; heat rejected at constant volume, followed by isothermal compression; range of temperature, 85° F.—540° F.	87
93, 94. Early Turbine of Dr. De Laval's	90
95. Friction Gearing	91
96. De Laval Nozzle	91
97. Flexible Shaft Support	91
98. Flexibility given by Rubber Rings	92
99. Flexibility given by Spring	92
100. Flexibility given by Diaphragm	92
101-103. Flexibility given by Transverse Pivots	93
104, 105. Flexibility given by Rubber Ring	93
106. Flexibility given by Spherical End Pieces	93
107. De Laval Turbine-dynamo	94
108. Component Parts of De Laval Turbine	95
109. Nozzle and Vanes of a De Laval Turbine	96
110. Section of Governor	97
111. Parts of Governor	97
112. Half Cylinders of Governor in Position	98
113. Connection of Governor with Steam Admission Valve	98
114. De Laval Turbine (Parallel) Centrifugal Pump	101
115. De Laval Turbine (Series) Centrifugal Pump	103
116. De Laval Turbine Blower	103
118. Rateau Steam Turbine: Longitudinal section	108
119, 120. Transverse Sections of Rateau Steam Turbine	109

FIG.	PAGE
121. Method of riveting the Rotating Blades of Rateau Turbine . . .	110
122. Diaphragm and Distribution Vane of Rateau Turbine . . .	111
123. Parsons Combined Turbine and Condenser: Vertical section . . .	116
124. " " " Plan . . .	117
125. " " " Partial vertical section on line AA of Fig. 123 . . .	117
126. Parsons Arrangement of Main and Reversing Turbines in One Casing	118
127. Parsons Arrangement of Telescoping Reversing Turbine within Main Turbine . . .	119
128. Form of Blades adopted for Rotating in Either Direction . . .	120
129. Electrical Governor for Parsons Turbine . . .	122
130. Electrical Governor for Parsons Turbine: Sectional elevation . .	124
131. " " " Plan . . .	124
132. Steam Consumption of 500-Kilowatt Parsons Turbo-alternator at Cambridge . . .	128
133. Steam Consumption of 500-Kilowatt Parsons Turbo-alternator at Cambridge . . .	129
134. 1000-Kilowatt Parsons Turbo-alternator. Diagram of total steam consumption per hour . . .	131
135. Variation in Speed with Centrifugal Governor: Increasing Load . .	133
136. " " " Decreasing Load . .	133
137. Variation in Speed with Electrical Governor: Increasing Load . .	136
138. " " " Decreasing Load . .	136
139. Propeller-shaft Support of Parsons and Wass: Sectional end elevation	144
140. " " " Side elevation . . .	145
141. " " " Sectional plan . . .	145
142. " " " Rear support of centre shaft . . .	146
143. Support for Four Propeller Shafts . . .	146
144. Parsons' Construction of Propeller Boss to diminish Cavitation . .	147
145. Cross-section of Boss . . .	147

THE STEAM TURBINE

CHAPTER I.

GENERAL REMARKS ON TURBINES.

A TURBINE is a machine in which a rotary motion is obtained by the gradual change of momentum of a fluid.

Fig. 1 shows a turbine diagrammatically. The partitions B between the passages A are called vanes, or blades, or buckets.

Now, it is obvious that, if a fluid enters the space between two vanes in the direction shown by the arrow 1, and leaves in the direction shown by the arrow 2, the component of its velocity perpendicular to the radius will gradually change in its passage. The component might not change during the whole of the passage of




FIG. 1.—Diagrammatic Illustration of Turbine.

the fluid owing to the vanes themselves having a velocity; but it will have a gradual change during at least some part of this passage. The fluid, therefore, has its momentum gradually changed, and it is this change of momentum which causes the vanes to rotate. The turbine wheel in the figure would rotate in the direction of the arrow 3. The action of the fluid on the

turbine will be discussed more fully later on ; it is only desired at present to give a general idea of a turbine.

Turbines may be classified in several ways. Firstly, they may be classified according to the actuating fluid. The fluids most commonly used are water and steam, and the turbines actuated thereby are called respectively hydraulic turbines and steam turbines.

Turbines may be classified according to the direction of flow of the fluid into three classes : (1) In **radial-flow turbines** the fluid travels from the centre to the circumference of the wheel, or from the circumference to the centre. This class is subdivided into **outward-flow** and **inward-flow** turbines, according as the fluid passes from the centre to the circumference, or from the circumference towards the centre. (2) In **parallel-flow** or **axial-flow turbines** the direction of the flow of the fluid is parallel to the axis of the wheel, or in a spiral co-axial with the wheel. (3) In **mixed-flow turbines** the fluid flows both as in a radial-flow and as in a parallel-flow turbine.

Turbines are classified in other ways besides these ; but as the other ways are not of importance, or do not hold good with steam turbines, we shall not refer to them.

Fig. 2 illustrates the principle of a **parallel-flow De Laval** steam turbine. The steam reaches the wheel by way of the divergent nozzles, where it expands and attains a great velocity. With this velocity it impinges on the vanes of the wheel, and causes the latter to rotate at a high speed. The wheel is enclosed loosely in a box or case, from which the steam escapes to the atmosphere or to a condenser. A section of one of the nozzles is shown at Fig. 2A drawn to an enlarged scale. In this figure the dotted line indicates the axis of rotation of the

wheel. The De Laval turbine will be more fully described later on.




FIG. 2.—Action of Steam in De Laval Turbine.




FIG. 2A.—Section of Nozzle of De Laval Steam Turbine.

Figs. 3, 4, 5, 6, 7, and 8 illustrate parts of a **Parsons parallel-flow** steam turbine. In this turbine the steam acts successively on a number of rings of blades. Part of one of these is shown in perspective view in Fig. 3, in elevation in




FIG. 3.—Blades and Shrouds of Parsons Parallel-flow Steam Turbine.

Fig. 4, and in plan in Fig. 5. Each ring of blades in this example is formed of blades, *c*, gripped in suitable recesses in shrouds, A and B. The rings thus formed are fixed alternately to the inside of the fixed cylindrical casing of the turbine, and to a revolving drum mounted inside the casing. Figs. 6

and 7 show parts of the casing and drum, the casing being lettered I and the drum H. Fig. 6 is a section taken through




FIG. 4.




FIG. 5.

Blades and Shrouds of a Parsons Parallel-flow Steam Turbine.

the axis of the casing, while Fig. 7 is a cross-section on the line CD of Fig. 6. Power is obtained from the spindle G,





FIG. 6.—Partial Axial Section.

FIG. 7.—Cross-section.
Parsons Parallel-flow Steam Turbine.

on which the drum H is keyed. It will be seen that the larger shroud A of each ring is secured to the casing or drum, while the smaller shroud B is free. The steam passing in the direction of the arrows in Fig. 6 acts on the moving blades so as to rotate them, and with them the drum and spindle. The fixed blades serve as guides to cause the steam




FIG. 8.—Action of Steam on the Blades of a Parsons Turbine.

after leaving one ring of moving blades to impinge in the right direction on the next ring of moving blades. The action of the steam on the blades can be clearly seen in Fig. 8, where the horizontal arrows show the direction of motion of the moving blades and the vertical arrows the direction of flow of the steam. It should be pointed out that the clearance between the fixed and the moving blades is very small—not nearly so great as is shown for the sake of clearness on the drawings.




FIG. 9.—Parsons Radial-flow Steam Turbine, Partial Axial Section.

Fig. 9 is a partial axial section through a **Parsons radial-flow**

turbine, and Fig. 10 illustrates a ring of blades for the same drawn to an enlarged scale. The blades *c*, both fixed and moving, are held in shrouds, *a* and *b*, of a similar nature to the shrouds A and B of the parallel-flow turbine. The cylindrical casing *i* carries internal annular flanges, *i'*, to which are attached the larger shrouds *a* of the fixed rings of blades; while the similar shrouds of the moving rings of blades are supported on annular flanges, *h'*, carried by the spindle *g*. The smaller shrouds *b* of




FIG. 10.—Blades and Shrouds of a Parsons Radial-flow Steam Turbine.

both fixed and moving rings are left free. The path of the steam is indicated by the arrows in Fig. 9, and it will be seen that the steam acts on the moving blades while flowing radially outwards in several stages.

The Parsons turbine in its several forms will be more fully described afterwards. The short description just made will, however, give a general idea of its nature.

CHAPTER II.

HISTORY OF THE STEAM TURBINE.

GOING back long before the days of Watt and Newcomen, we find a reaction steam-engine mentioned by the Egyptian philosopher **Hero** in his book on "Pneumatics," written in the second century B.C. This engine consisted of a hollow sphere rotating on two trunnions, through one of which it received steam from a generator situated below the sphere. The sphere was provided with two opposite projecting arms at right angles to the axis of the trunnions, the arms being furnished each with a nozzle at right angles to the arms and to the plane containing the arms and the trunnions. The nozzles were pointed in opposite directions, and the steam which escaped by them from the sphere caused the rotation of the latter about the trunnions.




FIG. 11.—Hero's Rotating Steam Globe.

In A.D. 1577 a German mechanic is said to have used Hero's engine to rotate a broach in place of a turnspit.

In 1629 an Italian architect named **Branca** described a steam wheel or turbine in which a jet of steam was projected against a series of vanes on a rotating wheel.

In 1642 a Jesuit named **Kircher** used Branca's wheel, but with two jets of vapour acting on its circumference instead of only one.

In 1784 **Wolfgang de Kempelen** was granted a British patent for "Obtaining and transmitting motive power." The patentee thus describes his invention—

"When the machine acts by boiling water, or rather the vapour proceeding therefrom, a boiler is to be constructed (A, Fig. 12) furnished with a valve of security (B), the weight




FIG. 12.—Wolfgang de Kempelen's Turbine.

of which is to be proportioned to the strength of the machine. At the upper extremity of the boiler is to be fixed a turncock (C), upon which the cylinder (DD) is to be screwed, the form of which cylinder appears in Fig. 13, where DD is a hollow cylinder or tube, in the centre of which E is an aperture to contain the worm of the screw. FF is a tube of cast iron, having at the lower extremity a circular projection or plate, which, when this tube is pushed into the other

tube, GG, fills up the cavity therein marked (*aa*), so that the screw (*bb*) extends beyond the utmost length of the tube GG. Upon this screw the cylinder DD, with its nut, is to be fixed, and upon the plate of the tube GG of brass is to be screwed another plate (HH) of equal dimensions, so that the little plate, when it is in the cavity (*aa*), may be enclosed between




FIG. 13.—Details of Kempelen's Turbine.

two plates, and the tube FF left at liberty to turn round. The plate HH has also a short tube (II) of an equal aperture with the tube GG, and at the end of it a screw is fixed, which surrounds the cock C, and is fastened within. Near each extremity of the cylinder DD, but on the contrary sides, is a small aperture, the size of which must be commensurate to the extent of the superficies of the boiling water, as, for instance, when the boiler measures within six feet in diameter,

requiring a valve of security weighing five pounds, the aperture near each end of the moving cylinder must be one inch in diameter. To put the machine in motion when the vapour of the boiling water is found strong enough to lift up the valve, the cock (C) is to be opened; the vapour instantly rushes through, and fills the cylinder DD, and finding a vent through the small apertures near its extremities on different sides, drives the cylinder round by reaction with exceeding great velocity. Having accomplished this first moving power which constitutes the principle of the machine, any kind of machine or engine may very easily be put into motion by it by means of a handle crown-wheel pinion, or other connection adapted to it, as is done with respect to a double pump by the excentric trunnion, *k*, Fig. 12."

The patentee then describes in his specification how his engine can be worked by water conveyed from a height, or by water acted on by steam pressure. The last-mentioned method is not illustrated, but the patentee states that two receivers of iron or copper must be provided between the boiler and the turning cylinder, and connected with both. The steam from the boiler is admitted alternately to the two receivers, and, pressing on the surface of the water, forces this into the turning cylinder, and rotates the latter by its reactive force when issuing from the apertures at its ends. The water is returned to the receivers.

In the same year Watt was granted letters patent for certain improvements relating to steam-engines. Most of the improvements relate to reciprocating engines, but one improvement relates to a rotary engine or turbine. This engine, or turbine, is described and illustrated in one of its "most commodious" forms by Watt in his specification. A vessel, ABDEC,

is rotatable on a pivot resting on the support J (Fig. 14), and is also supported by a collar, K, at its upper end. The vessel has a vertical partition, which divides it into two chambers, and each chamber has an aperture, R, at its upper end, which can communicate with a pipe, L (Figs. 14 and 15), conveying steam from a boiler. The rotating vessel is enclosed in a containing tank or vessel, MN, which is nearly filled with mercury, water, oil, or other liquid; and valves, F, G, are provided to allow




FIG. 14.

Watt's Turbine.



FIG. 15.




FIG. 16.

this liquid to enter the two chambers of the rotating vessel. Fig. 16 is a sectional plan of the rotating vessel and the enclosing tank. Openings, H (Figs. 14 and 16), are provided in the sides of the rotating vessel near the bottom.

Steam enters one of the chambers of the rotating vessel through its aperture R, and forces the liquid out of the chamber into the tank by way of the hole H, the valve F or G, as the case may be, being kept closed by the pressure of the steam. The reactive force of the jet issuing from H

rotates the vessel. While the steam is entering one chamber of the rotating vessel, the steam from the other chamber is exhausting by its aperture R into the atmosphere, or into the tank to be conveyed by the pipe O to a condenser. The escape of the steam from either chamber allows the liquid in the tank to enter that chamber by the foot-valve F or G. Power for driving machinery is got from axle P. In Watt's specification drawing the rotating vessel is shown as being about 12 inches in diameter by about 30 inches high, measured to the top of the steam-pipe.

It will be seen that this turbine is the same in principle as the last-mentioned form of De Kempelen's turbine, but as Watt's specification was signed and sealed by him only about a month after De Kempelen's, and as he had been granted his patent a few months previously, it seems probable that he devised his turbine quite independently of De Kempelen.

Since the days of James Watt, a great number of patents have been granted for inventions relating to steam turbines. A selection has been made of those which the author considers most interesting and most important, but only a very small proportion of those of recent years can of course be noticed.

In 1791 **James Sadler**, an engineer of the city of Oxford, was granted a patent for an invention entitled, "An engine for lessening the Consumption of steam and fuel, in steam or fire engines, and gaining a considerable Effect in Time and Force." The drawings enrolled with the specification are here reproduced, and the inventor's "Explanation" is also given in full. The latter is as follows: "Fig. 1st (Fig. 17). The Steam generated in the Boiler A is convey'd by y^e. Steam pipe B into y^e. spindle of y^e. rotative Cylinder C which is left

hollow for that purpose & connected with y^e pipe B by means of a stuffing Box at N which admits of the rotative motion of y^e spindle without loss of Steam, it there passes along y^e Arms of y^e rotative Cylinder nearly to y^e ends thereof where it meets with a jet of cold Water whereby it




FIG. 17.—Sadler's Engine.

is condensed this jet is introduced by y^e small pipes OO which communicates with y^e spindle M which is hollow and receives y^e Water by a hole at L, the Water falls thro' y^e bottom of y^e case DD into y^e pipe E and is together with y^e air admitted into y^e pipe G thro' y^e Cock F and descending when y^e valve H is open into y^e pipe I which has a

rotative motion round y^e end of y^e pipe G, it is thereby ejected thro' y^e valves KK the air which is left in y^e upper end of y^e pipe G is by turning y^e cock F suffer'd to escape whilst an equal portion of Water takes its place out




FIG. 18.—Cross-section of Sadler's Engine.

of the Reservoir P, Other-ways y^e steam is admitted into y^e Case DD, and rushing into the Arms of y^e rotative Cylinder is therein Condensed whilst y^e external steam by its action on y^e Arm causes a rotative motion—these Arms may also be included in y^e Boiler A which will prevent the necessity of a Case. Fig. 2nd (Fig. 18) Is a Section of y^e Machine across y^e spindle of y^e rotative Cylinder before described & AA are two small pipes which convey the Cold water for injection into y^e ends of y^e Cylinder Arms at BB.

which as described before passes down y^e pipe E thro' y^e Cock F and valve H into y^e rotative arms II it is ejected from them by y^e valves KK as before described."

Noble's Patent, No. 3289 of 1809. A drawing from the specification relating to this patent is here reproduced (Fig. 19). The accompanying description is not very good, but it

is gathered that steam proceeding from the boiler A by the pipe B impinges on the “catches and ratchets” of the wheel C, and forces the wheel to rotate in the direction of the arrow. The ratchet wheel E and pawl F prevent the possibility of a contrary rotation.

Trevithick's Patent, No. 3922 of 1815. One part of this invention consists in “causing steam of a high temperature to spout out against the atmosphere, and by its recoiling force to pro-




FIG. 19.—Noble's Steam Wheel.

duce motion in a direction contrary to the issuing steam similar to the motion produced in a rocket or to the recoil of a gun.” The patentee, who seems fond of firearms as similes, states that the mode of carrying this part of his invention into effect will be readily understood “by supposing a gun-barrel to be bent at about a quarter of its length from the muzzle, so that the axes of the two limbs shall be at right angles to each other, and the axis of the touch-hole at right angles to the axis of the short limb, or the limb containing the muzzle. . . . Then in the top of a boiler suitable to the raising [of] steam of a high temperature, make a hole and insert the muzzle of the gun-barrel into that hole, so that the gun-barrel may revolve in the hole steam-tight, and let the short bend of the gun-barrel be supported in a vertical position by a collar which will permit the breech of the gun-barrel to describe a horizontal circle, the touch-hole being at the side of the barrel. If steam of a high pressure be then

raised in the boiler, it will evidently pass through the gun-barrel and spout out from the touch-hole against the atmosphere with a force greater or less according to the strength of the steam, and as the steam is also exerting a contrary force against that part of the breech which is opposite to the touch-hole, the barrel will recoil, and because the other end is confined to a centre the breech end will go round in a circle with a speed proportionate to the pressure given, and may be readily made to communicate motion to machinery in general." The patentee gives this explanation "merely to

convey to the mind a clear idea" of his invention. In practice, he says, he uses more than one revolving arm, and he makes the aperture through which the steam is projected capable of being increased or decreased by means of a sliding piece worked by a screw. Several other variations may also, he states, be adopted.

The specification of **Ericsson's** Patent, No. 5961 of 1830, describes a steam turbine, a section of which is given in Fig. 20. A is a fixed casing in which revolves the shaft F carrying the "fly-drum" H. This drum is attached to the shaft by means of the boss I and the plate L. Channels r are provided in the plate L, which channels open at s into the fly-drum. Vanes J are situated inside the fly-drum, but are not connected to it, being attached only to the fixed collar a. One of the channels




FIG. 20.—Ericsson's Turbine.

One of the channels

r is shown separately in Fig. 21. The channels are also shown in Fig. 22, which is a view at right angles to Fig. 20, and exhibits also the fixed vanes J .



FIG. 21.

In Fig. 22, however, besides the channels r in the face of the fly-drum, channels r' are also shown in the periphery of the same. The steam enters the casing by the pipe D , and

its action in passing into the fly-drum through the channels r causes the drum to rotate, while the fixed vanes J prevent the rotation of the steam which leaves the casing at e and passes away by the exit pipe E . The inventor states, towards the end of his specification,




FIG. 22.—Vanes and Channels of Ericsson's Turbine.

that the object of his invention would be equally well obtained if the steam were to travel in a reverse manner—that is, to enter the fly-drum at e and leave it by the channels r .

Perkins' Patent, No. 7242 of 1836. The patentee states that in previous rotary steam-engines of the kind in which motion has been obtained by the reaction of steam-jets issuing from a rotating apparatus, the steam has been allowed to freely escape from the orifices into the atmosphere or into a steam chamber. In the patentee's engine, however, a series of

abutments, like the teeth of a ratchet wheel, are arranged in a ring for the steam-jets to impinge on.

The specification of **Pilbrow's** Patent, No. 9658 of 1843, is very interesting. The inventor seems to have experimented and theorized on the expansion and impulsive force of steam to a considerable extent. He found out, among other things, that, with a nozzle having an orifice three-eighths of an inch in diameter (the form of the nozzle is unfortunately not stated), the impulsive force of the steam issuing into the atmosphere was nearly proportional to the gauge pressure forcing the steam out. The pressures experimented with varied from 10 to 60 lbs. above atmosphere, and the impulsive force was measured "at the best distance from the orifice of the nozzle (about three-quarters of an inch)." With a gauge pressure of 60 lbs., the experimenter found that the total impulsive force (not the impulsive force per square inch) was about 14 lbs. Pilbrow calculated from this that the best velocity for the vanes of his turbine, using steam at 60 lbs. above

atmosphere, would be about 1250 feet per second. He admitted that this was a very high velocity, but hoped to be able to utilize it.




FIG. 23.—Simple Turbine of Pilbrow's.

Fig. 23 shows a simple turbine wheel as proposed by Pilbrow. The steam nozzle *b* is situated inside the wheel, and projects steam against the vanes *a*, where its motion

is reversed. The fixed vanes *c* lead the steam away. The change of momentum of the steam causes the wheel to rotate.

Fig. 24 shows in side elevation two such wheels mounted on the same shaft and enclosed in the same case. The vanes are set opposite ways on the two wheels, one wheel being intended for giving a reverse motion to the shaft. The pipes




FIG. 24.—Reversing Turbine of Pilbrow's.




FIG. 25.—Pilbrow's Air-propeller.




FIG. 26.—Combined Steam Turbine and Air-propeller.

conducting the steam to the two nozzles are shown in dotted lines and lettered *d* and *g*. Of course only one wheel and one nozzle are used at a time.

For purposes of land locomotion the inventor proposes to use an air-propeller, as shown in Fig. 25, fixed to the shaft of the steam turbine. Fig. 26 shows in section a combined steam turbine wheel and air-propeller. *mm* are the propeller blades, such as those seen in Fig. 25, and *f, g* is the axle on which the blades are mounted. A rim, *c*, is attached to the tips of the blades, and revolves close to the edges of the annular plates *d*, which, with the hoop *b*, form




FIG. 27.—Pilbrow's Successive-expansion Turbine: Elevation.

an annular gutter. Inside this gutter, and attached to the rim *c*, are the vanes *a*, which are acted on by the steam issuing from the nozzle *e*. An eduction pipe may be provided to lead the exhaust steam away from the gutter, or this steam may be allowed to escape only at the annular openings between the fixed plates *d* and the revolving rim *c*.

In order to get a steam turbine to work efficiently at a lower speed, the inventor proposes the arrangement shown in Figs. 27 and 28. A number of wheels are placed to

rotate on two parallel axes, the rims of the wheels overlapping, as shown in elevation in Fig. 27 and in part plan in Fig. 28. The wheels are arranged as parallel-flow turbines, and the steam entering the first wheel from the nozzle *a*, passes in succession through the vanes of all the wheels.




FIG. 28.—Pilbrow's Successive-expansion Turbine: Plan.

This is illustrated as regards two of the wheels by Fig. 29, which is drawn to a large scale. It will be seen that, at the parts adjacent to the nozzle, the vanes of the two sets of wheels move in opposite directions—that is, the two sets of




FIG. 29.—Pilbrow's Successive-expansion Turbine: Nozzle and Vanes.

wheels have similar angular velocities. The two axes may be connected by cranks and coupling-rods.

The inventor also apparently conceived the idea of reducing the vane velocity without the necessity of a second shaft by using fixed vanes or guides, for he says, "I also claim the exclusive use of curves or cavities in a stationary case to

reflect the steam back upon the wheel for a second or other number of impulses."

The inventor further describes how the power of one of his turbine wheels may be communicated to machinery by friction gearing.

The most important part of this specification is, in the




FIG. 30.—Von Rathen's Turbine.

author's opinion, the description of the method of reducing the vane velocity without losing efficiency by passing the steam through a number of rings of vanes in series. The adoption of this principle in the Parsons turbine has contributed much to make the latter so serviceable.

Von Rathen's specification, No. 11,800 of 1847, contains descriptions of several varieties of rotary steam or air engines, some at least of which may be classified as turbines. Fig. 30

shows in section one variety. A is a fixed casing in which rotates the boss B, carrying the radial pipes P. At the end of each pipe P is a cone, C, whose smaller end communicates with the interior of the pipe by means of a small orifice, D. Steam is supplied to the pipes P through the hollow boss L, and escapes, after expansion in the cones, by the pipe Q, to the atmosphere or the condenser. The boss B is mounted




FIG. 31.—Von Rathen's Reversing Turbine.

on an axle, which passes through the flat sides or ends of the casing. To render these parts steam-tight, the inventor proposes to use metallic bushes or packings, "and rings of gutta-percha, sulphurized caoutchouc, or similar substances." Fig. 31 shows a modification of the type of engine just mentioned intended for reversing. The pipes P are here made double. One chamber of each pipe communicates with a cone,

C, while the other chamber communicates with a pipe, C'. Steam can be admitted either to the cones C or the cones C', and the engine can, therefore, rotate in either direction. The




FIG. 32.




FIG. 33.




FIG. 34.




FIG. 35.

inventor describes and illustrates various constructions of expanding cones or their equivalents. Some of these are illustrated in Figs. 32, 33, 34, and 35. Several other varieties

Forms of Expanding Cone or Nozzle for
Von Rathen's Turbine.

of engine are described, in some of which the casing revolves as well as the boss.

In 1848 **Robert Wilson**, of Greenock, was granted a patent for improvements relating to rotatory engines. His improvements are chiefly with regard to the successive expansion of the steam. Wilson states in his specification that he is aware that, previous to his invention, steam has been employed in reciprocating engines to act successively in two cylinders, but that rotatory reacting engines have hitherto been worked only

so as to utilize the force of the steam at a single operation. The last part of the statement is not correct. Wilson seems to have been unaware of Pilbrow's compound steam turbine. But although Wilson's invention does not contain all the novelty that he attributed to it, it is nevertheless very interesting, and the specification shows that the inventor had carefully considered all the details of his engines. Some of his forms




FIG. 36.—Wilson's Radial-flow Turbine with Single Ring of Moving Blades: Sectional side elevation.

and methods of construction have just recently been put in practice very much as he proposed.

One form of Wilson's turbine is shown in Fig. 36, in sectional side elevation; while Fig. 37 shows the same, half in front elevation and half in section. On a base plate, A, are mounted two discs, B and D, which are united at their circumferences by the ring H. Each of the discs has a stuffing-

box through which passes a shaft, *F*, adapted to rotate on conical pins, *a*. On the shaft, and between the discs *B* and *D*, is keyed a disc, *G*, and this disc carries a number of curved vanes, *g*, which are best seen in Fig. 37. The disc *D* carries a number of vanes, r^1, r^2, r^3 , etc., and also (presumably) a number of blocks, *M*, separating chambers m^2, m^3, m^4 , etc.




FIG. 37.—Wilson's Radial-flow Turbine with Single Ring of Moving Blades: Half section and half front elevation.

(lettered *m* in Fig. 36). The disc *D* also carries a number of vanes, s^1, s^2, s^3 , etc., and (presumably) a number of blocks, *N*, separating chambers n^1, n^2, n^3 , etc. (lettered *n* in Fig. 36). All the vanes are arranged in three concentric rings so that steam can pass (for example) through between the vanes r^1 and *g*, or (for example) from the chamber m^2 , through between

the vanes s^1 and g to the chamber n^2 , without any movement parallel to the axis of revolution of the shaft F. This is shown clearly in Fig. 36. The steam passes through the ring H at I, and between the vanes r^1 which guide it to strike the vanes g nearly tangentially to these. The steam passes through between the vanes g , enters the chamber n^1 , sweeps round this chamber, and re-enters the spaces between the vanes g by way of the fixed vanes s^1 . The steam then enters the chamber m^2 , sweeps round it, and again enters the spaces between the rotating blades by way of the fixed blades r^2 . The steam thus proceeds round the casing with a serpentine course, and eventually leaves the casing at K. The actual path of the steam will be somewhat as indicated in Fig. 38, where the solid line represents the path of the steam, and the dotted lines




FIG. 38.

the internal and external peripheries of the ring of moving vanes. The stream of fluid will of course spread out in its path. The disc G, with its vanes g , presumably moves at a much lower speed than the velocity of rotation of the steam round the axis of rotation of the disc. The multiple action of the steam thus allows nearly all the energy of the steam to be conveniently used, and allows of the rotation of the

moving vanes at a speed which is small compared with the absolute velocity of the steam.

Fig. 39 shows another form of Wilson's turbine, in which the rings of blades *v*, *t*, and *s* are attached to a disc keyed on a revolving shaft, while the vanes *w*, *u*, and *g* are attached to a disc which is either stationary or is keyed




FIG. 39.—Wilson's Radial-flow Turbine with a series of Rings of Moving Blades.

to a shaft revolving in the opposite direction to the first-mentioned shaft. Steam is supplied from the boiler to the space *nn*, enters at several points the spaces between the blades, and works its way outwards through all the rings of blades. Fig. 40 shows a third form of Wilson's turbine, in which the blades *g*, *u*, and *w* are attached to and revolve with the shaft *F*, while the blades *v*, *t*, and *s* are fixed to the casing *H*, and do not move. The last two forms of Wilson's turbine are improvements on Pilbrow's device for obtaining

multiple action of the steam, and are the same in principle as successful turbines of the present day. Wilson's turbines were not intended to be mere toys. One of them is shown in the specification drawings as over 9 feet in diameter.




FIG. 40.—Wilson's Parallel-flow Turbine.

Fernihough's Patent, No. 13,281 of 1850. The patentee describes an apparatus in which the products of combustion from a furnace mingled with steam or water-spray are used to drive a turbine.

In 1853 the French mining engineer **Tournaire** pointed out very clearly the requisites of a successful steam turbine. Tournaire explained that elastic fluids like steam acquire enormous velocities, and that in order to properly utilize these velocities in a simple wheel, the latter would require to have an extraordinary great speed. He further explained that the difficulty of excessive speed of rotation could be avoided by causing the steam or gas to lose its pressure in a gradual manner, or by successive fractions, and by making it act in series on a number of turbine blades. Tournaire described a machine in which there were several shafts, all of which carried pinions which geared with a common shaft

from which power could be taken. Each shaft carried a number of wheels with blades, which wheels alternated with a number of rings of blades fixed to an enclosing cylinder. The steam, after passing in series through the fixed and moving rings of blades in one cylinder, was led to the cylinder enclosing the second shaft, and so on. Tournaire recognized that very good workmanship would be required to prevent serious loss of power through leakage between the fixed and moving blades. He also recognized the difficulty with toothed wheels rotating at the necessary speeds, and suggested the use of helicoidal gearing.

The good workmanship referred to by Tournaire has contributed largely to the success of the Parsons turbine, while the helicoidal gearing is an important feature of the De Laval motor.

Patent No. 3161 of 1873, **Thomas Baldwin**. This inventor, who filed no drawings with his specification, proposed to use a machine in the form of an hydraulic turbine, in which the flow of the steam might be "inward, or outward, or parallel." He mentions that a disc may be caused to rotate by the reaction of steam-jets issuing from apertures at its periphery, or by the impulse on the disc of steam-jets issuing from apertures in the casing. The inventor proposes to employ several machines in series, the steam which exhausts from the first being employed to drive the second and then the others in succession. It is proposed that the action of the steam on the last machine should be increased by leading it therefrom to an injector or ejector where the steam would be condensed, and the kinetic energy of the condensing water would then be utilized in a hydraulic turbine or water-wheel.

Patent No. 706 of 1874, **Alexander Teulon**. This inventor

proposed to utilize the axial thrust of a steam turbine to balance the axial thrust of a screw propeller.

Figs. 41 to 46 show steam turbine details which formed the subject-matter of several letters patent granted to **John S. Raworth**, about 1894.* 1, 1^a, 1^b, Fig. 41, are ports in communication with the nozzles of a turbine, and 2 is a circular valve furnished with

ports, 2^a, 2^b, 2^c, in the form of slots with circular ends.

The governor is connected to the valve,

so that, when the load on the turbine falls, the valve is turned to the right, and cuts off the steam supply, first to the port 1, and then in succession to the ports, 1^a and 1^b. When the load is increased, the valve is caused to move in the opposite direction.




FIG. 41.

Fig. 42 shows a compound nozzle, which is intended to be screwed at 3 into the main steam duct. The jet of steam flowing from the main steam-duct commences to expand at 4, and, as the steam increases in velocity, the nozzle is developed into two or more parts, 5, 6, 7.




FIG. 42.

Figs. 43 and 44 show a device or arrangement for reducing the high speed of steam turbines by gearing to a speed suitable for ordinary industrial purposes. The turbine shaft 1 is supported in a bearing, 2, and carries a small friction

* No. 25,090, dated December 30, 1893; No. 84, dated January 2, 1894; and No. 1242, dated January 19, 1894.

wheel, 3, which gears with large friction wheels 3^a and 3^b . These large wheels are mounted on shafts, 4 and 4^a , which carry toothed pinions, 9^a and 9^b , which gear with a spur-wheel, 9, mounted on a shaft, 10, from which power can be




FIG. 43.

taken. The shafts 4 and 4^a are supported in bearings in levers, 5^a and 5^b , which are pivoted at 6 and 6^a to the




FIG. 44.

base-plate 7, and are linked together at their upper ends by the rod 8, having a head, 8^a , and a nut, 8^b . A spring, 8^c , is arranged on the rod so that, by adjusting the nut 8^b , the wheels 3^a and 3^b can be pressed against the small wheel 3 with any desired pressure.




FIG. 45.

studs, f , attached to swing-frames, g , one of which is shown separately in Fig. 46. Each wheel, b , is lubricated by means

Fig. 45 shows another method of reducing the speed. The turbine shaft a' carries a pulley, a , which gears frictionally with three wheels, b , of which only one is shown. The wheels b rotate on

of a channel, f' , leading from an oil-chamber enclosed by the cap h screwed on the boss b^2 of the wheel. This construction prevents oil dripping on to the friction wheels. The frames g are pivoted at g' to the plate c , to which is keyed the power-shaft d . The frames may be weighted at g^2 to balance the weights of the studs and friction wheels. The latter are pressed against the small wheel a by a flexible band, e , which encircles the three wheels b , and is of such a diameter that it has to be sprung to extend around them. The band may be prevented from rotating by a band-brake, i .




FIG. 46.

Alexander Morton, of Glasgow, made several experiments with steam turbines about 1888 to 1892. In one of his engines a series of cylinders was arranged one within the other, the ends of the whole being closed by two common discs. Steam was admitted to the interior of the inner cylinder, and expanded through nozzles into the surrounding cylinder, and this action was continued till the steam reached the last cylinder, which was in communication with a condenser. This action of the steam caused the cylinders to rotate, all moving together. No guides whatever were used during the several stages of expansion, and the engine acted wholly by reaction. Parts of three of the concentric cylinders are shown diagrammatically in Fig. 47, the nozzles also being shown. The large arrow indicates the direction



FIG. 47.—Concentric Cylinders and Nozzles of Outward-flow Turbine of Morton's.

of rotation of the cylinders, and the small arrows the direction of motion of the steam relatively to the cylinders.



where it passes through divergent passages, *o*, of the nature of that shown at *b* in Fig. 48. It then has its motion changed by guides, *p*, and traverses divergent passages, *q*, somewhat similar to that shown at *y* in Fig. 49. The steam, continually expanding, has its motion then altered by guide-vanes, *r*, and impinges on rotating vanes, *s*. It then passes to the centre of the conical chamber *t*, where it escapes from the turbine, or is again similarly treated. The passages *o* and *q* and vanes *s* are arranged so as all to help to rotate the chambers *n* and *t* and the shaft *u*. The casing *v* is fixed, as is also the dished plate *w*, which supports the guide-vanes *r*.

The steam in the chamber *n* will press with equal intensity on the plate 2 as on the plate 3; but the steam in the chamber *t* will not press with equal intensity on the plate 3 as on the plate 4, if the fixed plate *w* be made solid. Further, there is no portion of the plate 2, and no portion of the plate 4, corresponding to the central portion of the plate 3; and, as this centre portion of the plate 3 has unequal pressures on its two sides (for the steam expands in passing from the chamber *n* to the chamber *t*), there will be a net axial pressure from left to right.

This axial pressure is balanced by shutting off a portion of the exterior of the plate 2 from the pressure in the casing *v* by means of the ring 7, the part of the plate within the ring being subjected to the pressure in the chamber *t* by means of the tubes 8.

Another arrangement of vanes and channels is shown




FIG. 51. — Arrangement of Vanes and Channels in Morton's Turbine.

diagrammatically in Fig. 51, the steam passing radially outwards

as indicated by the arrows, and traversing in succession diverging passages 9, 10, 11. Guide-vanes 12, 13, and 14 receive the steam after leaving the diverging passages, and redirect its course.

Fig. 52 shows in partial sectional elevation a steam turbine of the screw type, experimented on by **Professor Hewitt**. A shaft 4 is provided in a cylindrical casing, in the ends of which are stuffing-boxes. The shaft is provided with screw-threads, 5, whose pitch increases from the centre to the ends. Steam or other fluid enters the casing by way of the branch 2, and, passing through holes in the plates 6, gains access to the helical grooves between the screw-threads. The steam leaves the casing by the branches 1 at the two ends. One of the plates 6 is shown separately in Fig. 53. Professor Hewitt states that this turbine did not give good results, and that he considers that this was due to the absence of guide-




FIG. 52.—Screw Type of Steam Turbine.

plates for the steam. This is probably the case. The steam

would, no doubt, act effectively when it first struck the screw-threads; but, after it had once been deflected into a helical course, it would rush to the exhaust port, without producing much additional effect as regards rotating the shaft.




FIG. 53.—Admission Plate.

Only a small selection of inventions relating to the steam turbine could be reviewed in this chapter. Several not here referred to are described in the paper presented by Mr. Sosnowski to the International Congress on Applied Mechanics, held in Paris in the summer of 1900.

CHAPTER III.

HISTORY OF THE PARSONS STEAM TURBINE.

ON April 23, 1884, the Honourable Charles Algernon Parsons filed two applications for letters patent. These were the first patents of the great inventor relative to steam turbines, although he had previously experimented with rotary engines of another type. One of these patents is entitled "Improvements in Rotary Motors actuated by elastic fluid pressure, etc." An engineer reading this specification is at once struck with the apparent practicability of the motor therein described compared with most of its predecessors of a similar type. The motor as described and illustrated shows that an immense amount of thought and attention had been spent on details—on devices for reducing cost of construction, for preventing vibration, for drawing off leaking steam, for providing efficient lubrication, etc. This attention to details has characterized the Parsons turbine throughout its life (short as yet), and probably to this is largely due the immense success of the present-day motor.

No attempt will be here made to describe in full the first Parsons turbine, as some of the details are now obsolete, but some of its interesting features are here illustrated and explained. Fig. 58 is a plan, partly in section, of the main part of the motor. A spindle, S, is formed with a central

collar, S^1 , and reduced ends, S^3 . On S are placed a number of rings, B, B , which are held in place between the collar S^1 and nuts S^2 screwed on the spindle. The rings are provided at their circumferences with blades, b, b^1, b^2 , which are interspaced between blades, f, f^1, f^2 , fixed in the inside of the turbine casing. Steam is admitted to the annular chamber g , and passed through the rings of blades in series till it reaches the exhaust ports h, h . Any steam that leaks through to the annular chambers, o, o , is led away to a chamber, P (Fig 59), where by the action of a live steam-jet issuing from the nozzle p , it is ejected through the pipe q . As the steam passes from the centre to both ends, there can be little axial thrust on the shaft, but what little does occur is balanced by the exhaust steam at the ends of the casing, the arrangement being such that a slight movement of the shaft to either end of the casing checks the




Fig. 58.—Early Parsons Turbine.

exhaust at that end, and so increases the back pressure. In order that the shaft and rotating parts may rotate about their centre of gravity instead of about their geometric centre when the two are not coincident, arrangements are provided for allowing the shaft a little lateral play. One of these arrangements is shown in Fig. 60, where I is a light bush enclosing




FIG. 59.—Escaped-Steam Ejector.




FIG. 60.—Bearing for Spindle in Early Parsons Turbine.

the shaft. Surrounding this bush are rings, K, which touch the casing but not the bush, alternating with rings, K', which touch the bush but not the casing. The nut M compresses the spiral ring L against the end ring K'. The shaft can thus move laterally a certain extent, say, one-hundredth of an inch, but this movement is resisted by the friction of the collars on one another. A system of forced lubrication is provided, and also a fan governor.

A steam turbine dynamo was constructed in 1885 by Messrs. Clarke, Chapman, Parsons and Co. Revolving at the rate of 18,000 revolutions per minute, it gave great satisfaction, and was used for several years generating current for incandescent electric lamp manufacture.

A year or two later Parsons introduced an improved

steam turbine, of which an elevation, partly in section, is given in Fig. 61. The steam entered at *a*, and passed through the rings of blades shown diagrammatically at *c* and *c'*. The fluid then passed through the rings of blades of larger diameter indicated by the letters *e* and *e'*, and then through those of still greater diameter situated at *g* and *g'*. The exhaust ends of the parts *c* and *c'* were connected by the passage *d*, which maintained an equal pressure at the two points, and the exhaust ends of the parts *e* and *e'* were similarly united by the passage *f*. The exhaust from this compound turbine was taken away from both ends by the passage *h*. Water or steam packing was provided at the places where the spindle passed through the ends of the casing, so that water or steam might be drawn into the condenser, but no air could. An annular chamber, *i* (Figs. 62 and 63), was provided round the spindle *b*,




Fig. 61.—Double-ended Parsons Turbine of Increasing Diameter.

and kept supplied by the pipe *k* with water from the hot well or with steam, either at boiler pressure or partly expanded. Packing rings, *l*, *l*, *m*, were used, as shown in Fig. 62, or, when water was employed, the spindle was sometimes cut with right- and left-hand threads, as shown in Fig. 63, so that its rotation tended to repel the water leaking past.




FIG. 62.




FIG. 63.

Steam or Water-packing for Spindle of Parsons Turbine.

In 1891 the first Parsons condensing steam turbine was constructed for the Cambridge Electric Supply Company by the firm of C. A. Parsons and Co., just then formed (Messrs. Clarke, Chapman, Parsons and Co. having dissolved partnership in 1889). This engine was tested by Professor Ewing, and its efficiency proved to be equal to that of the best reciprocating engines of the same power.

This condensing steam turbine was followed by many others, plants being supplied to the Newcastle and District Electric Lighting Company, the Cambridge Electric Supply Company, and the Scarborough Electric Supply Company. At first the turbines had all been comparatively small, but larger machines were now made, and the increase in size,




FIG. 64.—Section of Parsons Radial-flow Turbine.

together with improvements in design, led to still higher efficiencies.

Fig. 64 shows a recent form of construction of radial-flow Parsons turbine. Steam is led into the annular chamber H, and passed therefrom through the fixed and moving rings of blades G, of which the fixed blades are attached to the casting P, and the moving ones to the disc B. The steam, in a somewhat expanded state, then doubles back along the passage Q, and works its way outwards again through the rings of blades G^1 . The fixed blades in this case are attached to the annulus M. The action is repeated through the rings of blades G^2 , G^3 , G^4 , and G^5 . The form of these rings of blades is shown in Figs. 3-10, pp. 3-6. The final expansion of the steam takes place in the rings of blades N and N^1 , and the steam then reaches the passage O and proceeds to the condenser. The method of fitting the casting P to the parts M, M^1 , M^2 , etc., by means of spigot and faucet joints, is clearly shown.

E is a balance piston used to balance the end pressure of the steam on the discs B, B^1 , B^2 , etc. This piston is provided with deep projecting flanges, a , a^1 , a^2 , a^3 (Figs. 64 and 65), which flanges are adapted to rotate in corresponding recesses provided in a ring secured to the casting P. The flanges are serrated on one side, as shown at b , b^1 , b^2 , and b^3 . The resistance to the flow of




FIG. 65.

steam through the tortuous passages between the fixed and moving flanges is very great, and leakage is thus reduced to a minimum. The piston E is mounted on a conical part of the spindle.

The turbine spindle A is constructed with a collar, c^1 , into which are screwed long studs or pins, c^2 , c^3 , which pass

through holes in the turbine discs B, B¹, B², etc., and through holes in the balance piston E. The discs and balance piston are thus firmly held on the spindle. Live steam is admitted to the annular spaces f , f^1 , f^2 , etc., to reduce the condensation of the steam passing through the rings of blades.

In order to damp vibration and to allow the spindle a little transverse movement so that it may rotate about the line containing the centre of gravity of the revolving parts, the spindle is enclosed near both ends in a sleeve, K (Figs. 64, 66, 67), provided with a flange, K², and a collar, K¹.




FIG. 66.




FIG. 67.

Bearing for Spindle of Parsons Turbine.

Surrounding the sleeve, and between the flange and collar, are placed three concentric tubes, A, B, and C. The tubes are bored so as to be an easy fit on each other and on the sleeve; and oil is supplied to the thin annular spaces so formed so that any transverse movement of the shaft is resisted by the fluid friction of the thin films of oil which have to be squeezed from the parts where the tubes are compressed against each other. Figs. 68 and 69 show an alternative construction, where two tubes, A and E, contain between them several segments, F, G, H, which are cut from a tube of smaller diameter so that the ends of the segments touch the

inner tube E, and the middle portions of the segments touch the outer tube A. Oil is supplied in this case also to the




FIG. 68.

Elastic Bearing for Parsons Turbine.




FIG. 69.

spaces between the tubes and sleeve, but the fluid friction is aided by the elasticity of the segments F, G, H. In both cases suitable means, such as projections D, are provided to prevent rotation of the sleeve K.

The end-thrust of the spindle due to the pressure of the




FIG. 70.—Thrust-block of Parsons Turbine.




FIG. 71.—Slotted Ring for Thrust-block.

steam on the discs B, B¹, B², etc., is taken up by the thrust-block L (Fig. 64), which is made in halves and provided with flanges and recesses to engage with recesses and flanges on the spindle. Sometimes the construction shown in Fig. 70 is




FIG. 72.—Section of Parsons Parallel-flow Turbine.

adopted where rings, *i, j, k, l, m*, are used, which are separate from both block and spindle, and are of sufficient diameter and thickness to possess the requisite elasticity. The elasticity may be increased by providing slots in the rings as shown in Fig. 71; or spring washers may be inserted between the rings and the recesses for them in the block L.

All these devices for taking up end-thrust and damping vibration have been patented by Parsons.

Fig. 72 shows in vertical longitudinal section a modern Parsons parallel-flow turbine. Steam passes through the




FIG. 72A.—Fixed and Moving Blades of Parsons Turbine.

equilibrium valve H and enters the annular space J, from which it proceeds through the fixed and moving blades in the high-pressure cylinder, or part A; then through those in the intermediate cylinder, or part B; and then through those in the low-pressure cylinder, or part C. The arrangement and construction of the rings of blades will be best understood by referring back to Figs. 3-8.

Instead of making the turbine cylinder of increasing




PLATE II.—PARSONS STEAM TURBINE COUPLED TO 500-KILOWATT ALTERNATOR.



diameter, the fixed rings of blades at the high-pressure end may contain only a few blades, the spaces where blades are not placed being occupied by solid or hollow segments. The number of blades on the fixed rings will then increase progressively from the high-pressure end to the low-pressure end of the turbine. All the moving rings, however, are provided with blades round their whole circumferences. A section of the fixed and moving blades is shown drawn to a large scale in Fig. 72A, where 10 represents the fixed blades, 11 the spaces between them for the passage of steam, 12 the segments occupying the remaining space of the fixed rings, and 13 the rotating blades.

Plate II. shows a Parsons steam turbine coupled direct to a 500-kilowatt alternator. It is installed in the station of the Newcastle and District Electric Lighting Company.

CHAPTER IV.

POINTS OF RESEMBLANCE AND DIFFERENCE BETWEEN THE STEAM TURBINE AND OTHER MOTORS.

THE action of the steam turbine depends on the conversion of the heat energy of the steam into kinetic energy, and then in the transference of this kinetic energy from the steam to the rotating parts of the turbine. The latter part of the action is thus in principle much the same as that of the water turbine, but the former part has no parallel in the hydraulic motor. In a water turbine the fluid is practically at constant volume and at constant temperature, and its kinetic energy is gained at the expense of potential energy due to pressure or position. On the other hand, when steam is used, this fluid varies in volume within very wide limits. Thus, 141 cubic feet of saturated steam at 200 lbs. pressure absolute produces 1647 cubic feet at atmospheric pressure, and this produces only 1 cubic foot of water when condensed. These volumes are represented respectively by the cubes A, B, and C in Fig. 73, p. 52. The temperature of the steam varies also, and care has to be taken to prevent, as far as possible, loss of heat by radiation, a point that does not call for attention with a water turbine.

Another important point of difference between the steam turbine and the water turbine is the immense velocity of

the fluid in the former compared with the latter. In a water turbine working under the large head of 150 feet, the velocity of the fluid entering the wheel is about 96 feet per second.

In steam turbines a fluid velocity of 2000 to 3000 feet per second is common. The reason for high speeds with steam can easily be seen. A cubic foot of water having a velocity of 96 feet per second has a kinetic energy of about 9000 foot-lbs.* A cubic foot of dry saturated steam at 50 lbs. pressure absolute has, however, so small a mass that, in order that it may have the same kinetic energy, it must have a velocity of about 2200 feet per second.* These differences in the physical properties of steam and water necessitate great differences in the construction of steam turbines and water turbines. It should also be noted that all friction in a water turbine means loss of energy; but that in a steam turbine the heat generated by the friction may serve to heat the fluid, and thus in great part restore the energy absorbed. This will be referred to again.

Comparing a steam turbine with a reciprocating engine, we find that, although the greatest possible efficiency, as determined by thermo-dynamic considerations, is the same in both, being represented by Carnot's formula $\frac{T_1 - T_2}{T_1}$, the causes which reduce this efficiency below this maximum are largely different in the two cases. One of the greatest losses in the reciprocating engine is due to the alternate contact of the inside of

* Kinetic energy of 1 cubic foot of water = $\frac{mv^2}{2} = \frac{62\frac{1}{2} \times 96^2}{2 \times 32.2} = 9000$ foot-lbs. approximately.

Kinetic energy of 1 cubic foot of dry saturated steam at 50 lbs. pressure absolute) = $\frac{mv^2}{2} = \frac{0.12 \times 2200^2}{2 \times 32.2} = 9000$ foot-lbs. approximately.

the cylinder with the hot steam and with the comparatively cold exhaust. The cylinder walls rob the entering steam of much of its heat energy. Some of this energy may be recovered by the steam at a later part of the stroke, but a great part is given up to the exhaust, and, unless it can after-




FIG. 73.—A, volume of steam at 200 lbs. absolute; B, volume of steam at atmospheric pressure; C, volume of water.

wards be utilized, is lost. There is no such loss with the steam turbine, as the steam passes constantly in the same direction, some surfaces of the turbine making contact with the entering steam and some with the exhaust, but none with both.

Another loss which is sometimes thought to be considerable occurs with reciprocating engines using slide-valves or their

equivalents, and consists in steam leaking past the valve to the exhaust. This, of course, cannot happen in a steam turbine where no slide-valve or its equivalent exists.

Another great source of loss with reciprocating engines is due to friction. This friction sometimes absorbs more than a quarter of the total I.H.P. of the engine. Except for the friction in the bearings of the shafts, the friction in a steam turbine is of a totally different nature from that in a reciprocating engine. It consists in the friction of the steam against itself and against the surfaces of the turbine, and the friction of the water carried by or deposited by the steam. Water deposited on the fixed parts of the turbine will cause friction by coming in contact with the rotating parts. The amount of clearance between the fixed vanes and the moving vanes of a Parsons turbine is very small, and, with a high speed of rotation, it is quite possible that the friction due to this cause may be considerable. If saturated steam be used, a certain amount must be condensed in the turbine, but, by superheating the steam and jacketing the turbine, this condensation may be very much reduced, if not entirely prevented. It is noteworthy that superheating the steam very much improves the efficiency of a Parsons turbine. Mr. Parsons considers that 55° C. superheat reduces the steam consumption about 12 per cent. It should be borne in mind, however, that a great part of the heat developed by this friction, as already stated, will probably not be lost. Slightly more radiation may take place from the outside surfaces of the turbine, and the exhaust may leave in a slightly less condensed form than would otherwise happen ; but a large portion of the heat, it is presumed, will be returned to the working fluid so as to be again utilized. With the reciprocating engine, although the friction of the piston in the cylinder

and of the slide-valve or other valve in the steam-chest may heat the steam, yet, as the exhaust steam receives part of this heat, and as there is much friction caused by other parts than the piston and valve, we may safely assert that in a reciprocating engine the greater part of the heat caused by friction is lost.

Another advantage which the steam turbine possesses over the reciprocating engine is that, with the former, there is no internal lubrication required. The fact that the steam turbine can take steam without any lubricant whatever is doubly advantageous. In the first place, the exhaust steam is absolutely free from oil, so that the water from the hot well can be directly returned to the boiler without the use of an oil filter, and without any danger of the boiler suffering from a deposit of grease in it. The second advantage arises when superheated steam is used. When this is employed in reciprocating engines, there are difficulties with regard to internal lubrication; and there is also the danger of piston and valves sticking, unless properly and carefully designed, owing to difference of expansion of different parts of the engine. With the steam turbine no lubricant is required to be added to the steam, and the danger of harm arising from unequal expansion is not as a rule great. It should be noted that, although both turbines and reciprocating engines improve in efficiency by superheating the steam, the reasons for the superheating are not altogether the same. The reciprocating engine gains chiefly (or at least largely) by the reduction or abolition of initial condensation. This cannot be the chief reason with the steam turbine; but the gain in economy in the steam turbine by superheating will be discussed later on.

The steam turbine benefits more than the reciprocating

engine from a good vacuum in the condenser. (Tables showing the effect of the state of the vacuum on the steam consumption of Parsons turbines are given in Chap. X.) Decreases of pressure below 5 lbs. absolute mean large drops of temperature in the case of saturated steam, and therefore there is a great thermo-dynamic advantage in having a low condenser pressure in a steam-engine. In the case of a reciprocating engine, however, this thermo-dynamic advantage is partly neutralized by the increased initial condensation due to the lower temperatures of the surfaces with which the steam entering the cylinder comes in contact. The increase in efficiency obtained by improving the vacuum is therefore only due to the difference of these two effects. In the case of the steam turbine, however, there is no such initial condensation, and consequently this type of engine gains largely by improvement of the condenser vacuum. Another reason for the comparatively small gain in efficiency by increase of vacuum in the reciprocating engine is the impossibility in most cases of taking full advantage of the vacuum by expanding the steam in the cylinder down to the condenser pressure without unduly increasing the bulk of the engine and diminishing its mechanical efficiency.

A source of loss with the steam turbine which does not occur with the reciprocating engine is caused at the parts where the shaft leaves the case. At high speeds of rotation difficulties obviously occur with packing such as is used in the piston-rod glands of a reciprocating engine. In the Parsons turbine no packing is used, but a special device is employed which will be described hereafter; with this device very little loss is said to occur.

It should be noted in comparing the driving of alternators by steam turbines and by reciprocating engines that, while the

same percentage variation of speed means the same percentage variation of periodicity, a drop (or rise) of, say, 5 revolutions per minute in the one case, does not mean the same variation of periodicity as in the other case; for the number of alternations per revolution in the turbine-driven alternator is, owing to the speed of rotation, less than in the alternator driven by the reciprocating engine, the mean periodicity being the same in both cases.



CHAPTER V.

VANES AND VELOCITIES.

LET us now consider the form of the vanes or blades and the speed of rotation of a steam turbine, and, in the first instance, it may be advisable to deal with turbines generally.

As we shall be using the terms "absolute velocity" and "relative velocity" with respect to the motion of the fluid, it will be better to state here that by absolute velocity is meant a velocity which would be absolute if the turbine casing or frame were at rest. A turbine may be on board a ship, and therefore have the velocity of the ship, and even when on land and what we call fixed, it nevertheless has the velocity of the earth. It is convenient, however, to neglect these velocities of the ship and the earth and such-like, and speak of the velocity of a revolving part of the turbine or of the operating fluid as *absolute*, when we mean that such a velocity would be absolute if the casing or frame, or fixed parts of the turbine, had no motion. We shall speak of velocities as *relative* only when they are relative to a "moving" part of the turbine. To illustrate what is meant, let X (Fig. 74) be part of a turbine wheel moving with an absolute velocity, W , as shown by the arrow. Let V be the absolute velocity of a jet of fluid. Then the velocity of the fluid relatively to the turbine will be obtained by making $QB = W$, and completing the

parallelogram APBQ, when PB will represent the velocity of the jet relatively to the wheel. This relative velocity PB is the velocity which the jet would have if a velocity were imparted to both the wheel and the jet of an amount sufficient to render the net velocity of the wheel equal to zero. Now, a velocity which would render the net velocity of the wheel




FIG. 74.

equal to zero would be equal and opposite to W . Therefore, combine this velocity with V , and the velocity PB is obtained. Or we may define the velocity of the jet relatively to the wheel as that velocity which, combined with the velocity of the wheel, produces the absolute velocity of the jet. Now, PB represents the velocity which, combined with the velocity of the wheel, produces the absolute velocity represented by AB . Therefore, PB represents the velocity of the jet relatively to the wheel.

In Fig. 75, let V = the absolute velocity of the fluid impinging on the blades or vanes of a turbine; let W = the velocity of the turbine vanes. Then R , the velocity of the fluid relatively to the turbine, can easily be determined. If the course of the fluid is not to be abruptly altered, it is necessary that the vanes where the fluid enters should be parallel to the line of R , and this is usually the case where possible. If the

ack , or α , will represent the angle of the vanes at the point of entrance, and the angle at dck , or β , will represent the angle of the vanes at the point of exit. By completing the parallelogram $cbcd$, we obtain ce , which represents v in magnitude and direction.

Draw ag and eh perpendicular to bk .

$$\text{Then } ce^2 = cb^2 + eb^2 - 2bc \cdot bh$$

$$\text{Now } eb = cd = ac$$

$$\begin{aligned} \text{Therefore } ce^2 &= cb^2 + ac^2 - 2bc \cdot bh \\ &= ab^2 - 2bc \cdot cg - 2bc \cdot bh \\ &= ab^2 - 2bc(cg + bh) \\ &= ab^2 - 2bc(ac \cos \alpha + eb \cos \beta) \\ &= ab^2 - 2bc(ac \cos \alpha + ac \cos \beta) \\ &= ab^2 - 2bc \cdot ac(\cos \alpha + \cos \beta) \quad \dots (1) \end{aligned}$$

$$\text{Therefore } v^2 = V^2 - 2bc \cdot ac(\cos \alpha + \cos \beta) \quad \dots (2)$$

It is therefore evident that with a given initial absolute velocity of the fluid, v^2 will be the smallest when $2bc \cdot ac(\cos \alpha + \cos \beta)$ is greatest. It can be seen that this will occur when α and β are each equal to zero, and when $bc = cg$, which in this case will equal ac . W would then equal $\frac{1}{2}V$, and the vanes would be as shown in Fig. 77.




FIG. 77.

If V = velocity at A, the velocity W of the vane should be $\frac{1}{2}V$. The velocity R of the fluid relatively to the vane at A would therefore be $\frac{1}{2}V$. Therefore the velocity r of the fluid relatively to the vane at B would also be $\frac{1}{2}V$, and therefore the absolute velocity of the fluid at this point would be zero.

Not only when the angles α and β are both equal to zero, but in any case when α and β are fixed, and V is also fixed in

magnitude, it can be seen from equation (2) that v^2 is least when $ac \cdot bc$ (Fig. 76) is a maximum. Since the area of the triangle $abc = \frac{1}{2}ac \cdot bc \sin a$, and also equals $\frac{1}{2}ab \cdot cm$ (Fig. 78), where cm is perpendicular to ab , it follows that—

$$\frac{ab \cdot cm}{\sin a} = ac \cdot bc$$

Therefore v^2 is least when $\frac{ab \cdot cm}{\sin a}$ is a maximum.

But ab and $\sin a$ are both constant.

Therefore v^2 is least when cm is a maximum.

This occurs when m is the middle point of ab .

For, draw any other triangle, abc' (Fig. 78), on base ab and with angle $ac'b = \text{angle } acb$.

Then the points a, c, c', b are on the circumference of a circle

whose centre will be on cm produced.

Let o be the centre.

Join oc' , cutting ab at n .

Draw $c'm'$ perpendicular to ab .

Then om is less than on .

Therefore $oc - om$ is greater than $oc' - on$.

Therefore cm is greater than $c'n$, and therefore greater than $c'm'$.

Therefore cm is a maximum when m is the middle point of ab .

Therefore v^2 is least when m is the middle point of ab ; that

is, when $bc = ac$, or when $bc = \frac{ab}{2 \cos \frac{a}{2}}$.




FIG. 78.

It follows, therefore, that the best value for W is never less than $\frac{1}{2}V$. When α is large, the best value for W is considerably more than $\frac{1}{2}V$.

It is usually impracticable to make α and β equal to zero, although this is very nearly obtained in the Pelton water-wheel. But even when α and β are each equal to 45° , the energy lost need not exceed about 17 per cent. of the whole; for, when $ac = bc$ (Fig. 76), the angle $abc = \frac{1}{2}$ of angle $acg = 22\frac{1}{2}^\circ$; and the angle $ecb = \frac{1}{2}$ of angle $dec = 67\frac{1}{2}^\circ$.

$$\text{Therefore } ec = \frac{eh}{\sin 67\frac{1}{2}^\circ} = \frac{ag}{\sin 67\frac{1}{2}^\circ} = \frac{ab \sin 22\frac{1}{2}^\circ}{\sin 67\frac{1}{2}^\circ}$$

$$\text{Therefore } ec^2 = \frac{ab^2 \sin^2 22\frac{1}{2}^\circ}{\sin^2 67\frac{1}{2}^\circ} = 0.17ab^2$$

With hydraulic turbines V is comparatively small; 100 feet per second is a high value. In steam turbines, however, V is immensely greater.

If steam at a high pressure is allowed to escape through a small, sharp-edged orifice in a plate into the open air or into a chamber at a lower pressure, it is found that only a small portion of its heat is converted into kinetic energy. If, however, the steam is allowed to escape through a diverging nozzle, a much larger proportion of its heat energy is converted into kinetic energy.

Suppose that a pound of dry saturated steam at 300 lbs. pressure absolute is expanded through a divergent nozzle to a chamber communicating with a condenser, and suppose that 20 per cent. of the total heat energy in the steam is converted into kinetic energy; then, as the total heat of the steam equals about 1700 thermal units—

$$\text{K.E.} = 1700 \times \frac{20}{100} \text{ thermal units} = \frac{1700 \times 20}{100} \times 778 \text{ foot-lbs.}$$

$$\text{Therefore } \frac{v^2}{2g} = 1700 \times \frac{20}{100} \times 778$$

$$\text{Therefore } v^2 = \frac{1700 \times 20 \times 778 \times 2g}{100}$$

$$\text{Therefore } v = 4116 \text{ feet per second}$$

If this steam be allowed to act on a single ring of vanes in a steam turbine, then, as we saw that for the greatest efficiency the velocity of the vanes must never, in any case, be less than half the velocity of the entering fluid, it follows that the velocity of the vanes should not be less than 2058 feet per second.

Now, it can be proved that if a ring, whose thickness measured radially is not great compared with its mean diameter, be rotated about its axis, the stress produced in the material due to centrifugal force will be approximately wv^2 ; * where w

* Let the velocity at outer circumference of the ring shown in Fig. 78A be represented by V_1 , and the radius to the outer circumference by R_1 .




FIG. 78A.

$$\text{Therefore velocity at any radius } r = \frac{V_1 \times r}{R_1}.$$

Let w = density of material.

$$\begin{aligned} \text{Therefore centrifugal force at radius } r \text{ on ring of indefinitely small breadth } dr & \left\{ \begin{aligned} &= \frac{2\pi r \cdot dr \cdot w}{r} \times \frac{V_1^2 \times r^2}{R_1^2} \\ &= \frac{2\pi \cdot dr \cdot w \cdot V_1^2 \cdot r^2}{R_1^2} \end{aligned} \right. \end{aligned}$$

$$\text{Therefore total C.F.} = \int_{R_2}^{R_1} \frac{2\pi dr \cdot w \cdot V_1^2 \cdot r^2}{R_1^2}$$

(where R_2 = interior radius of ring A)

$$\begin{aligned} &= \frac{2\pi w V_1^2}{R_1^2} \int_{R_2}^{R_1} r^2 \cdot dr \\ &= \frac{2\pi w V_1^2}{R_1^2} \times \frac{R_1^3 - R_2^3}{3} = \frac{2\pi w V_1^2 (R_1^3 - R_2^3)}{3R_1^2} \end{aligned}$$

Let v = velocity at mean radius from centre.

$$\text{Then } v = \frac{R_1 + R_2}{2} \times \frac{V_1}{R_1} \text{ or } V_1 = \frac{2vR_1}{R_1 + R_2}$$

is the density of the material (*i.e.* mass per unit volume), and v is the mean velocity, that is, the velocity at a point at the end of a mean radius. The width of the ring, measured parallel to its axis, and the mean radius do not affect the result. Even if the thickness of the ring, measured radially, is great compared with the mean diameter, the result is not greatly altered. If a steel ring, therefore, weighing 500 lbs. per cubic foot, could have a mean velocity of 2000 feet per second, the stress produced in it would be nearly 200 tons per square inch of cross-section. If the interior diameter of the ring and its velocity there be fixed, then any increase in the external diameter will increase the stress.

This shows that when high-pressure steam is expanded all at one step, the efficiency of a turbine using it is limited by the strength and weight of the materials available for its construction. This difficulty may be overcome by expanding the steam in steps, so that an efficient velocity may be obtained within the limits allowed by the material. On p. 63 it was shown that the velocity of the wheel had to be half, or more than half, of the velocity of the entering fluid, if the velocity of the fluid when leaving the wheel was to be a minimum. But the latter velocity need not be a minimum if the fluid has to act on another series of vanes. The fluid

$$\text{Therefore total C.F.} = \frac{2\pi w(R_1^3 - R_2^3)}{3R_1^2} \times \frac{4v^2 R_1^2}{(R_1 + R_2)^2} = \frac{8\pi wv^2(R_1^3 - R_2^3)}{3(R_1 + R_2)^2}$$

$$\text{Now, the force tending to break the ring across a diameter} = \frac{\text{C.F.}}{\pi}$$

$$\begin{aligned} \text{Therefore average stress of material} &= \frac{\text{C.F.}}{\pi \times 2(R_1 - R_2)} = \frac{8\pi wv^2(R_1^3 - R_2^3)}{3(R_1 + R_2)^2 \times 2\pi(R_1 - R_2)} \\ &= \frac{4wv^2(R_1^2 + R_1R_2 + R_2^2)}{3(R_1 + R_2)^2} \end{aligned}$$

$$\text{When } R_2 \text{ approaches } R_1, \text{ the stress approaches } \frac{4wv^2 \times 3R_1^2}{3 \times 4R_1^2}, \text{ which} = wv^2.$$

may act on several sets of vanes in succession, and the angle and velocities of these vanes may be so arranged that the fluid gives up a portion of its energy to each.

In Fig. 79 let ab represent the absolute velocity of the fluid




FIG. 79.—Diagram showing Velocities of Fluid in a Compound Turbine, the volume of fluid being constant or increasing proportionately to increase of section of passages.

entering the first series of vanes.

Let α and β be the angles of the vanes at the points of entrance and exit of the fluid, and let cb represent the velocity of the vanes. Then ac represents the velocity of the fluid, relatively to the vanes as it enters, and cd its velocity relatively to the vanes as it leaves. If the sectional area of the fluid while passing through between the vanes is constant, and if the fluid neither expands nor contracts in volume, then $cd = ac$; ce will represent the absolute velocity of the fluid as it leaves the first series of vanes. If the fluid be then guided so that it takes the direction ef , and if ef be made equal in length to ce , then ef

will represent the absolute velocity of the fluid as it enters the second series of vanes. If these vanes are similar to the last, and have the same velocity which is here represented by mf , the relative velocity of the fluid entering the vanes will be represented by em , and the fluid leaving this series of vanes will have a relative velocity represented by mn , which is

equal to em , and an absolute velocity represented by mo . If the fluid be now guided into the direction op , and made to act on another series of similar vanes, having a similar velocity represented by qp , the fluid will leave this series of vanes with an absolute velocity represented by qs . It will thus be seen that the energy taken from the fluid, which is proportional to $ab^2 - qs^2$, is a large proportion of the total available energy, which is proportional to ab^2 ; but the velocity of the vanes is only a small fraction of the initial velocity of the fluid. By having a greater number of series of vanes, the velocity of these could be kept still lower.

The several series of vanes can be all arranged on the same shaft. If all the series are placed the same distance from the axis of the shaft, cb , mf , and qp will be equal. Otherwise these lines will be unequal.

We have assumed that the fluid neither expands nor contracts in volume from the time it enters the first series of vanes to the time it leaves the last series. If the fluid is a gas, however, it usually will expand during the interval. If the area of section of the passages for the fluid through between the vanes be correspondingly increased, the diagram shown in Fig. 79 will be unaltered. Otherwise the diagram will be modified. Fig. 80 shows a diagram for the same vanes as shown in Fig. 79, and with these vanes having the same velocity, but with the fluid expanding both while passing




FIG. 80.—Diagram showing Velocities of Fluid in a Compound Turbine, the volume of fluid increasing at a greater rate than section of passages.

through each series of vanes, and in passing from one series to the next. cd is, therefore, greater than ac , as a greater volume of fluid leaves the first series of vanes than enters it. Similarly, ef is greater than ce , as a greater volume of fluid enters the second series of vanes than leaves the first series. Similarly, mn is greater than em , op than mo , and qr than oq . The energy taken from the fluid is in this case not proportional to $ab^2 - qs^2$, as some of the initial energy of the fluid exists as heat energy, and is converted into kinetic energy during the passage of the fluid through the apparatus.

In a Parsons steam turbine, practically the whole of the expansion of the steam takes place after the fluid has entered the first series of vanes, and, as the steam passes through a great many series of vanes, its velocity is never excessive.




FIG. 81.—Passage of Steam through a Parsons Turbine.

As, moreover, with a number of series of vanes, the velocity of the vanes need only be a small fraction of the velocity of the steam, it follows that vane-speeds can be kept comparatively low without losing the efficiency. Very good results have been obtained with Parsons turbines running at nearly as low a speed as that of fast reciprocating engines.

Fig. 81 shows the fixed and moving vanes or blades

of a parallel-flow turbine of the Parsons type, the dotted line and

small arrow-heads showing the passage of the steam. The fixed blades are for guiding the steam from one series of moving blades to the next. The relative and absolute velocities at different points are lettered to correspond with Fig. 80. The lines *ab*, *ac*, etc., are intended to represent only the directions, and not the magnitudes, of the velocities.

In order to reduce the velocity of the fluid acting on the vanes of a steam turbine, it has been proposed to cause the steam-jet, by an injector action, to draw in air, water, or other fluid at atmospheric pressure, the velocity of the combined fluid being thus made moderate. This would allow of a lower efficient vane speed ; but, as a greater mass of fluid would leave the turbine, and as this fluid must have a certain velocity, the energy thus lost would be increased without any increase in the energy entering the turbine.

CHAPTER VI.

ENTROPY AND ENTROPY-TEMPERATURE DIAGRAMS.

As we shall be dealing with entropy-temperature diagrams, and as this subject is not very well known, it may be advisable, in the first place, to explain what is meant by "entropy," and what can be determined by an entropy-temperature, or, as it is sometimes called, a theta-phi diagram. To an engineer accustomed only to diagrams in which the ordinates and abscissæ represent readily appreciable quantities, such as pressure, or volume, or steam consumption, the idea of entropy is rather difficult to grasp. This "ghostly quantity," as Professor Perry calls it, is not perceptible by the senses, and cannot be measured directly by any gauge or meter. It is, nevertheless, a very convenient term of expression, and entropy-temperature diagrams are very instructive and very useful.

In an ordinary pressure-volume or pressure-distance diagram, as, for example, an indicator diagram, the ordinates represent pressure, the abscissæ represent volume or distance travelled, and the areas represent energy received or rejected, or work done. Now, when heat is put into or taken out of a substance, any small part of the heat so dealt with is equal to the temperature at which it was put in, or taken out, multiplied by some quantity. This quantity is called change of entropy, or difference of entropy.

Temperatures are reckoned from absolute zero, which is




FIG. 82.—Entropy-temperature Diagram.

represented by the line OX. Entropy may be reckoned from any point, but it is convenient, in dealing with water and steam, to consider zero entropy to be that of water at freezing-point (32° F.). This will then be represented by OY. Quantities of heat always refer to one pound of the working substance.

In Fig. 83 AB is an entropy-temperature curve for water raised in temperature

from 100° F. to 400° F. The temperatures are indicated both on the ordinary Fahrenheit and on the absolute scale. It will be seen that the difference of entropy between water at 100° F. and water at 400° F. equals 0.437. The amount of heat required to effect this physical change




FIG. 83.—Entropy-temperature Diagram for Water and Steam.

in the water is represented by the area $aABb$. The curve AB

may be drawn by obtaining from a table the entropy of water at several temperatures, and plotting these values. If the water at 400° F. be converted into steam at that temperature, the entropy-temperature curve will be parallel to OX, as the temperature is unchanged. The change of entropy will be represented by bd , and the heat put into the substance by the area $BDdb$. The heat put into the water is obviously the latent heat of steam at 400° F. (860° abs.). This equals 830 units. The change of entropy bd is therefore equal to $\frac{830}{860}$, or 0.965, as indicated on the diagram. If, now, the steam expand adiabatically against a resistance, the temperature will fall, but as no heat is being imparted to or taken from the steam, it is obvious that the area below the curve of expansion must be zero—that is, that no change of entropy will take place. The entropy-temperature curve will therefore lie along Dd , and will be represented by DE if the temperature fall to 100° F. If heat be now abstracted from the steam and water (for some of the steam will have condensed during expansion) till all the fluid exists in the liquid state, but without lowering the temperature, the entropy-temperature curve will be EA, which is parallel to OX. The quantity of heat taken from the fluid will be represented by the area $aAE d$. The total heat supplied to the fluid is therefore proportional to the area $aABDd$, and the heat abstracted to the area $aAE d$. The heat converted into work is therefore proportional to the area ABDE, and the efficiency of a heat-engine working on this cycle = $\frac{\text{area ABDE}}{\text{area } aABDd}$

If, instead of allowing the steam to expand adiabatically, we had, during expansion, supplied just sufficient heat to it to maintain it in a dry, saturated condition, the entropy-temperature curve for expansion would be DG instead of DE. If heat had

then been taken from the steam without reducing its temperature till the whole had condensed, the drop of entropy would be represented by AG (or ag), and the quantity of heat abstracted by the area $aAGg$. This last quantity is obviously the latent heat of steam at 100° F., and it is evident that the ratio of the area $aAEd$ to the area $aAGg$ is the fraction of the latent heat available to be given up after the steam has expanded, according to the line DE . This ratio must therefore represent the amount of steam uncondensed at E . The areas are proportional to the lines AE and AG , and therefore $\frac{AE}{AG}$ represents the dryness fraction, or the fraction of the steam uncondensed after the adiabatic expansion DE has taken place, or when the point E is reached during the isothermal withdrawal of heat GA . Similarly, if any other horizontal line such as HKL be drawn, $\frac{HK}{HL}$ will represent the dryness fraction of the steam at the point K of the adiabatic expansion DE .

The curve DG may be drawn by obtaining from a table the entropy of dry, saturated steam at several temperatures, or it may be obtained in another manner. $AG \times Aa = \text{area } aAGg$. But aA represents a certain temperature, and $aAGg$ represents the latent heat of steam at that temperature. Therefore the length of AG can be obtained by dividing the latent heat by the temperature. Several horizontal lines, such as AG and HL , can thus be determined, and the curve DLG drawn through their ends.

CHAPTER VII.

THEORETICAL CONSIDERATION OF DIFFERENT TREATMENTS OF STEAM IN A HEAT-ENGINE.

It is intended in this chapter to consider the effects of treating steam in different ways on the efficiencies of heat-engines with special reference to the steam turbine.

Let us consider the transfer of heat energy into mechanical energy in a heat-engine or apparatus comprising a boiler in which water is heated to a certain temperature and then converted into steam, a turbine or other motor in which the steam is expanded and loses some of its heat, and a condenser in which more of the heat is taken from the fluid before the latter is returned to the boiler.

The different cases which will be considered have been chosen not to represent what occurs in practice, but to indicate the effects of different treatments of the steam, so that it can be ascertained what had best be done with any type of turbine, in order to prevent waste and promote efficiency, and what is likely to be gained or lost by any alteration in treatment, such, for example, as by superheating the steam.

CASE I.

Let us suppose, in the first instance, that feed water is received into a boiler at 85° F., and heated to 382° F. The

entropy-temperature curve for this heating is shown at AB, in Fig. 84.

Suppose that the water is converted into steam at this temperature, which means that the pressure is 200 lbs. absolute.




FIG. 84.—Case I.: Adiabatic Expansion; isothermal compression; range of temperature, 85° F.—382° F.

This absorption of heat is represented by BC. Let the steam now expand adiabatically, doing work, till the pressure falls to 0.6 lb. absolute. The temperature corresponding to this pressure is 85° F. This expansion is represented by the line CD on the diagram. Some of the steam will condense during this expansion, and we can find the wetness at any point in CD, by the method

described in connection with Fig. 83. Lastly, let heat be abstracted from the fluid till the whole of the steam has condensed, but without any reduction of temperature, and let the water be returned to the boiler. This action is represented by DA on the diagram (Fig. 84). It does not matter whether the heat be abstracted from the steam in the turbine or in a condenser, or in any other vessel, provided that it takes place after the expansion and the fall in temperature are completed.

The heat supplied to the fluid is then represented by the area $aABCD$, and the heat abstracted by the area $aADd$. The heat converted into work is therefore represented by the area ABCD and—

$$\text{The efficiency} = \frac{\text{area } ABCD}{\text{area } aABCd} = 0.31$$

CASE II.

Let us suppose now that the steam generated at 200 lbs. pressure, instead of expanding adiabatically, be supplied during expansion with sufficient heat to prevent any condensation. This might be approximately attained by jacketing a steam turbine with high-temperature steam. The condensation will then all take place at constant temperature, as shown by EA. The entropy - temperature diagram will then be as shown in Fig. 85.




FIG. 85.—Case II.: Expansion along Line of Dry Saturated Steam; isothermal compression; range of temperature, 85° F.—382° F.

The heat supplied to the fluid is represented by the area $aABCEe$, and the heat abstracted by the area $aAEe$. The heat converted into work is therefore represented by the area ABCE, and—

$$\text{The efficiency} = \frac{\text{area } ABCE}{\text{area } aABCEe} = 0.28$$

Compared with Case I. it will be seen that there is an increase both in the heat supplied and in that converted into work, but the latter is not increased proportionately to the former, and hence the drop in the efficiency.

by the area $fFCDd$. Of this the area CFD goes to reduce the heat converted into work, and the area $fFDD$ to reduce the work of the condenser. There is no reason why CF should be a straight line. A straight line has only been assumed for convenience. The nature of the line would depend on the construction of the engine. (In a reciprocating engine the line is usually very convex to the left, on account of the coolness of the cylinder at the beginning of the stroke.) It should therefore be noted that if the leakage of heat had been greater than that represented towards the beginning of the expansion, and less towards the end, so that the line of expansion was as shown by the dotted line $C23F$, the efficiency would have been reduced; while if, on the contrary, the leakage had been less towards the beginning of the expansion and greater towards the end, as indicated by the dotted line $C45F$, the efficiency would have been increased; the total amount of steam condensed being the same in all cases.

CASE IV.

Suppose in this case the steam is superheated before expansion takes place, from 382° F. to 540° , and that the expansion is then adiabatic.




FIG. 87.—Case IV.: Superheating; Adiabatic Expansion; isothermal compression; range of temperature, 85° F.— 540° F.

Fig. 87 is the diagram for this case,

CG being the curve for the superheating action. It will be seen that the line GK of adiabatic expansion cuts the line CE of dry, saturated steam at the point H. This indicates to us that, during the fraction of the adiabatic expansion represented by GH, the steam is superheated; while, during the remaining fraction represented by HK, it is wet—at the point H it is dry and saturated. The heat supplied to the fluid is represented by the area $aABCGg$, and the heat abstracted by the area $aAKg$. The heat converted into work is therefore represented by the area ABCGK, and—

$$\text{The efficiency} = \frac{\text{area } ABCGK}{\text{area } aABCGg} = 0.32$$

The heat supplied to the fluid during the superheating action is represented by the area $dCGg$. Of this the portion represented by the area DCGK is converted into work. The fraction of the heat supplied which is converted into work is therefore greater during this action than during the actions of heating the feed water and generating the steam, and it is this which raises the efficiency slightly above that in Case I.

To draw the curve CG we must make an assumption regarding the specific heat of steam at constant pressure. Let this specific heat be denoted by K , and let us assume that K is a constant, and equal to 0.48. Then from equation (3), p. 71—

$$\phi_2 - \phi_1 = \int_{842}^{1000} \frac{dQ}{\tau}$$

the numbers 1000 and 842 denoting the temperature on the absolute scale, and ϕ_1 and ϕ_2 , denoting the entropy respectively before and after the superheating action.

$$\text{Now } dQ = Kd\tau.$$

$$\begin{aligned}
 \text{Therefore } \phi_2 - \phi_1 &= \int_{842}^{1000} \frac{K d\tau}{\tau} = 0.48 \int_{842}^{1000} \frac{d\tau}{\tau} \\
 &= 0.48(\log_e 1000 - \log_e 842) = 0.48 \times 0.1720 \\
 &= 0.08256 \text{ ,}
 \end{aligned}$$

This is the difference of entropy between C and G, and determines the length dg . The height gG is of course determined by the temperature, namely, 540° . Any other point on the curve CG can be similarly located, and the curve thus obtained.

CASE IV_A.

In the case just described the higher limit of temperature and the range of temperature exceed that in the other cases, and therefore, in order to make a fair comparison, we must consider the case of an engine working on a cycle, as in Case IV., but with the same limits of temperature as in Cases I., II., and III.

Let us suppose, then, that steam is generated at 224° F., and superheated to 382° F., the cycle otherwise being the same as in Case IV.

The entropy-temperature diagram will then be as shown in Fig. 88, where




FIG. 88.—Case IV_A.: Superheating; Adiabatic Expansion; isothermal compression; range of temperature, 85° F.— 382° F.

the heat supplied to the fluid is represented by the area

$aAMNSs$, and the heat withdrawn by the area $aAPs$. The heat converted into work is therefore represented by the area $AMNSP$, and—

$$\text{The efficiency} = \frac{\text{area } AMNSP}{\text{area } aAMNSs} = 0.20$$

The efficiency is less than in Case I., because, although the maximum and minimum temperatures are the same as in Case I., most of the heat is absorbed by the fluid when at a lower temperature.

CASE V.

If in Case IV. (Fig. 87), the fluid, instead of expanding adiabatically, had had the same amount of heat abstracted from it during expansion as in Case III. (Fig. 86), the entropy-temperature diagram would be as shown in Fig. 89, where the total leakage of heat is represented by the area $qQJGg$, which corresponds to and equals the area $fFCDd$ in Fig. 86. The heat supplied, the heat withdrawn, and the heat converted into work are represented respectively by the areas $aABCGg$, $aAQJGg$, and $ABCGJQ$.




FIG. 89.—Case V.: Superheating; Expansion with Leakage of Heat; isothermal compression; range of temperature, 85° F.—540° F.

$$\text{The efficiency} = \frac{\text{area } ABCGJQ}{\text{area } aABCGg} = 0.26$$

The increase in efficiency in this case over Case III. is about the same as the increase in Case IV. over Case I., and for the same reason.

CASE VI.

In the cases heretofore considered the steam has expanded doing work. But the steam may expand without doing work, or against an imperfect resistance. Joule found by experiment that when a gas expands without doing work, its temperature remains constant. Joule's experiment consisted in placing in a tank of water two vessels, one containing a gas under pressure, and the other empty. On communication being established between the vessels, some of the gas rushed from one vessel to the other, and the pressure fell; but it was found, after equilibrium had been established, that the temperature was the same as at the beginning of the experiment.

The phenomenon of unresisted expansion occurs when steam is passed through a reducing-valve, when the pressure falls and the steam expands without any appreciable amount of work being done. Imperfect resistance to expansion also occurs when steam passes at a high velocity through a restricted opening, and is well known in such a case by the name of "wire-drawing." When unresisted or imperfectly resisted expansion takes place, some of the heat of the gas is converted into kinetic energy; but if the gas has its velocity arrested, the energy returns to the form of heat. Thus, in the case of a reducing-valve, when the valve opens, there is a rush of steam through it, some of the heat energy of the steam being converted into kinetic energy. The rush is, however, arrested at the other side of the valve, and the kinetic energy is returned by impact or eddies to the form of heat.

In Fig. 90 AB represents the heating of the feed water, BC the generation of steam, and CX the adiabatic expansion of the steam, as in the previous cases. Suppose that free expansion then takes place till the steam is completely dried and is superheated. The state of the steam will then be represented




FIG. 90.—Case VI.: Expansion, partly adiabatic and partly unresisted; isothermal compression; range of temperature, 85° F.—382° F.

by the point Y on the diagram. If the steam had been dried, but not superheated, the point Y would have been on the curve CZ. We cannot connect X and Y by a straight line to represent the free expansion, as this would indicate that heat had been absorbed by the steam,

which is not the case. If we want an unbroken curve, we must connect X and Y by means of the straight lines Xd, de, and eY. Ye of course equals Xd, as the temperature is unchanged. Suppose that, after the free expansion, the steam expands adiabatically, doing work, till the temperature falls to 85° F. This expansion is represented in the diagram by YE. The isothermal compression EA completes the diagram, as in the previous cases. The amount of free expansion has been so chosen that, after the last expansion, the steam is dry and saturated, as indicated, by the point E being on the curve CZ.

The heat absorbed by the fluid in this case is represented by the area $aABCd$ and the heat rejected by the area $aAEe$.

The heat converted into work is represented by the area $aABCd$ —the area $aAEc$ and

$$\text{The efficiency} = \frac{\text{area } aABCd - \text{area } aAEe}{\text{area } aABCd} = 0.08$$

CASE VII.

In this case let us suppose that the feed water is heated, the steam generated, and the adiabatic expansion commenced as in Case I.; but let the adiabatic expansion continue only till the temperature falls to 250° F., as indicated by the point V. Then let heat be abstracted from the fluid *at constant volume* till temperature 85° F. is reached, as indicated by U, Fig. 91. The isothermal compression UA completes the diagram.

FIG. 91.—Case VII.: Adiabatic Expansion; heat rejected at constant volume, followed by isothermal compression: range of temp.




FIG. 91.—Case VII.: Adiabatic Expansion; heat rejected at constant volume, followed by isothermal compression; range of temperature, 85° F.—382° F.

The curve VU is obtained as follows. Let a' be the volume of 1 lb. of saturated steam at 250° F. (the temperature at V), and let a be the volume of the same at any other temperature, τ , between V and U. Let q' be the dryness fraction of the steam at V, and q be the dryness fraction at the temperature τ . Then, neglecting the volume of the water—

$$qa = q'a'$$

because the fluid is expanding at constant volume. If l is

the point on the curve where the temperature is τ , and mln is a horizontal line drawn to meet the line of saturated steam CZ—

$$q = \frac{ml}{mn}$$

$$\text{therefore } ml = q \times mn = \frac{q'a'}{a}mn$$

q' of course equals $\frac{vV}{vp}$, and a' and a can be obtained from a table of the properties of saturated steam. Hence ml can be obtained. Similarly, any number of other points can be obtained on the curve VU.

The heat supplied to the fluid in this case is represented by the area $aABCd$, and the heat rejected by the area $aAUVd$. The heat converted into work is represented by the area ABCVU, and

$$\text{The efficiency} = \frac{\text{area ABCVU}}{\text{area } aABCd} = 0.18$$

This treatment, by which part of the heat is rejected at constant volume, and part at constant temperature, gives a reduced efficiency compared with the treatment in Case I., where all the heat rejected was given up at constant temperature. In reciprocating condensing engines the heat is commonly rejected, neither on a constant volume line nor on a constant temperature line, but on a line between the two. The nature of the rejection of heat in a steam turbine is pretty much a matter of conjecture.

CASE VIII.

Suppose in this case that the feed water is heated, and the steam generated, superheated, and expanded adiabatically, as in Case IV., till the point T (Fig. 92) is reached, where the

temperature is 250° F. Let the fluid now expand at constant volume, as in Case VII., till the point W is reached, when the temperature is the same as at A, and let the cycle be completed by the isothermal compression WA. In this case the heat supplied to the fluid is represented by the area




FIG. 92.—Case VIII.: Superheating; Adiabatic Expansion; heat rejected at constant volume, followed by isothermal compression; range of temperature, 85° F.— 540° F.

$aABCGg$, as in Case IV., and the heat rejected is represented by the area $aAWTg$. The heat converted into work is represented by the area $ABCGTW$, and

$$\text{The efficiency} = \frac{\text{area } ABCGTW}{\text{area } aABCGg} = 0.19$$

Many more cases might be studied, but sufficient have been considered to show the effect of different treatments of the steam. The results are here tabulated in Table I.




TABLE I.

Case.	Method of treatment.	Max. temp. F.	Min. temp. F.	Efficiency.
I.	{ Adiabatic expansion. Isothermal compression }	382	85	0.31
II.	{ Expansion along line of dry saturated steam. Isothermal compression }	382	85	0.28
III.	{ Expansion with leakage of heat. Isothermal compression }	382	85	0.25
IV.	{ Superheating. Adiabatic expansion. Isothermal compression }	540	85	0.32
IVa.	{ Superheating. Adiabatic expansion. Isothermal compression }	382	85	0.20
V.	{ Superheating. Expansion with leakage of heat. Isothermal compression }	540	85	0.26
VI.	{ Expansion, partly adiabatic and partly unresisted. Isothermal compression }	382	85	0.08
VII.	{ Adiabatic expansion. Heat rejected at constant volume, followed by isothermal compression }	382	85	0.18
VIII.	{ Superheating. Adiabatic expansion. Heat rejected at constant volume, followed by isothermal compression }	540	85	0.19

It should be borne in mind, however, that a change in the range of temperature will alter the relative efficiencies. It should also be remembered that arbitrary quantities have, as a rule, been chosen for the amount of superheating, amount of free expansion, etc.; and that, if these are altered, the results may be considerably modified. And it must not, above all things, be forgotten that there are practical considerations which affect the efficiency. For example, there is the fluid friction in a turbine. It is probable that the diminution of this fluid friction by superheating the steam accounts in part for the increased economy obtained by superheating; for the results obtained by the tests of Parsons turbines show a greater percentage increase in efficiency with superheating than is due to thermo-dynamic reasons. Table II. shows the effect of superheating on the steam consumption of a Parsons turbine.

TABLE II.

TEST OF 500-KILOWATT TURBO-ALTERNATOR CONSTRUCTED BY MESSRS. C. A. PARSONS AND CO. FOR THE CORPORATION OF BLACKPOOL.

Pressure of steam above atmosphere at stop-valve.	Superheat at stop-valve.	Vacuum in the turbine cylinder. (Bar. = 30".)	Revolutions per minute.	Load.	Steam used.	
lbs. per sq. in.	degrees F.	ins. of mercury.		kilowatts.	lbs. per hr.	lbs. per kw. hr.
146	70	27.1	2500	515	11,000	21.35
150	0	27.0	2500	502	11,600	23.1
135	0	27.3	2500	497	11,953	24.0
133	66	27.3	2500	507	10,693	21.1

CHAPTER VIII.

THE DE LAVAL STEAM TURBINE.

ABOUT 1882, Dr. Gustaf de Laval invented a turbine on the principle of Hero's engine. This turbine is illustrated diagram-




FIG. 93.




FIG. 94.

Early Turbine of Dr. De Laval's.

matically in Figs. 93 and 94. Steam (or other fluid) entered the casing *a* by the nozzle *b*, and passed along the curved hollow arms *c, c*. These arms were formed like the buckets of an outward-flow hydraulic turbine, and the passage of the steam along them caused them to revolve and to rotate the shaft *d*. This shaft drove another shaft at a slower speed by means of friction wheels. The requisite pressure between the surfaces of these wheels was obtained by utilizing the axial thrust of the turbine wheel. The turbine shaft *d* was supported in bearings which allowed it an axial movement. This shaft (see Fig. 95) carried a bevel friction wheel *e*, and the axial thrust of the turbine wheel forced this bevel wheel against the bevel wheel *f* carried by the power shaft *g*.

In 1889 Dr. De Laval applied for a British patent* for

* No. 7143 of 1889.

a steam turbine wheel combined with a diverging nozzle for the steam supply. The nozzle shown in the specification of this patent was shaped as illustrated in Fig. 96. The steam expands in passing from the smaller section *m* to the larger section *n*, and its velocity increases while its pressure falls. The object is of course to obtain a great kinetic energy with which to act on



FIG. 95.—Friction Gearing.




FIG. 96.—De Laval Nozzle.




FIG. 97.—Flexible Shaft Support.

the turbine vanes. The manner in which the steam is directed on to the vanes can be seen by referring back to Figs. 2 and 2A.

Another patent of De Laval's of the same year,* refers to the flexible support of steam turbines or other bodies intended to rotate at high velocities. Figs. 97 to 106 illustrate diagrammatically several devices covered by the patent for allowing a certain amount of lateral movement to the rotating mass, to enable it to compensate for slight want of balance.

In Fig. 97, the rotating body *a* is carried on a flexible shaft, *b*, whose ends are placed in the shoes *c, c*, which rotate in the bearings *d, d*.

In Fig. 98, the rotating body *a* is flexibly connected to the shaft *b*, by providing the latter with a flange, *e*, and inserting

* No. 12,509 of 1889.

rubber rings f, f , as shown. The body is of course also supported by another shaft at the other side.




FIG. 98.—Flexibility given by Rubber Rings.

In Fig. 99, spiral springs g, g , are substituted for the rubber rings.




FIG. 99.—Flexibility given by Spring.

In Fig. 100, the shaft b is connected to the rotating body by




FIG. 100.—Flexibility given by Diaphragm.

means of the flexible diaphragm h , held in place by the gland k .

In the device shown by Figs. 101, 102, 103, in end elevation, side elevation, and section respectively, the shaft b is

supported at each end in bushes *m*, which, by means of the transverse pins *n*, *n*, can swing in the standards *o*.




FIG. 101.

FIG. 102.

FIG. 103.

Flexibility given by Transverse Pivots.

In Figs. 104 and 105, the bearing bush *p* (one of these is




FIG. 104.

FIG. 105.

Flexibility given by Rubber Ring.

provided at each end of the shaft) is supported in the cylindrical top of the standard *o*, by means of the rubber ring *q*.

In Fig. 106 the shaft is provided with spherical end pieces, *r*.




FIG. 106.—Flexibility given by Spherical End Pieces.

British patent, No. 20,603 of 1891, granted to Dr. De Laval, has reference to the exhaust passage from the turbine, which is constructed of a divergent shape in order to produce an ejector action. The velocity of the fluid at the outer end of the nozzle is less than at the inner end, owing to the increase in the section of the passage, and consequently the pressure at the inner end is less than at the

outer end. If, therefore, the pressure at the outer end is atmospheric, a partial vacuum will exist at the inner end of the passage and around the wheel, thus diminishing friction.

Fig. 107 shows a De Laval turbine-dynamo, as constructed




FIG. 107.—De Laval Turbine-dynamo.

by the Société de Laval (France), for horse powers from 5 to 30. The cylinder to the right contains the turbine wheel, and the intermediate cylinder is the gear box in which the high rotary motion of the wheel is geared down to a speed suitable for driving the dynamo, which is shown at the left of the figure.

Fig. 108 shows the principal parts of a turbine such as that shown in Fig. 107, but fitted with a pulley instead of being connected with a dynamo. A is the turbine shaft on which is mounted the disc or wheel B, furnished with a series of vanes. These vanes can also be seen in Fig. 109, where they are lettered W. C is a double helical pinion which gears with the toothed wheel M, the teeth on the wheel and pinion being formed at an angle of 45° , as is shown in the figure. Great




FIG. 108.—Component Parts of De Laval Turbine.

(The block for this has been prepared from an illustration kindly supplied by Messrs. Greenwood and Bailey, of Leeds.)

strength is not required in these teeth, as the forces exerted on them are not excessive, owing to the high speed of rotation of the shaft A, and the small diameter of the pinion. It can be seen by a small calculation that, if the diameter of the pinion C be, say, one inch, and the speed of rotation 24,000 revolutions per minute, the force exerted on the teeth will be very small, even if the motor be of considerable power. D is the end bush of the turbine shaft, and F the middle bush, made in




FIG. 109.—Nozzle and Vanes of a De Laval Turbine.

two parts. T is a tightening bush, also made in two parts. O, O, are the gear-wheel shaft bushes which support the power shaft N, which carries the gear wheel M, and the driving pulley R. S is a stop nut for the power shaft, and H a ball bush with adjusting spring for the turbine shaft. U is an adjusting nut, and V a friction gland. I is a steam nozzle, of which several are usually provided, distributed round the wheel. K is the stuffing-box for the spindle stop-valve, which can be actuated by the hand-wheel L. P is a lubricating ring, and Q is the governor which is mounted on the power shaft.

A section of a De Laval governor as constructed by the

Société de Laval (France) is shown in Fig. 110, and the parts are shown separately in Fig. 111. The half cylinders 8, 8, are




FIG. 110.—Section of Governor.

pivoted in the case 10 by the knife-edges 14, and have projecting lugs which press on the spindle 11 through the agency of pins 13.




FIG. 111.—Parts of Governor.

Fig. 112 shows the half cylinders in their correct positions, but removed from the other parts. The spindle 11 acts by means of a lever on the steam admission valve. The centrifugal force is balanced by a spring, 9, which can be adjusted by means of the nut 12.

The connection of the governor with the steam admission or throttle valve, is shown in Fig. 113, where A is the spindle

which was marked 11 in Figs. 110 and 111. C is a lever pivoted near its centre, and arranged so that the spindle A can act on its lower end, while its upper end is connected to the lever G by means of a link which is adjustable by means of the nuts EF. The lever G operates the valve.




FIG. 112.—Half Cylinders of Governor in Position.

The characteristic feature of the De Laval steam turbine is the fact that the steam is completely, or nearly completely, expanded before it reaches the wheel.

This expansion is accomplished by means of the divergent nozzle, which is best seen in Fig. 109. It will be seen from




FIG. 113.—Connection of Governor with Steam Admission Valve.

this figure that any nozzle may be closed by screwing down the spindle, and thereby preventing the entry of steam into the nozzle from the distribution conduit Y. This distribution conduit is cast in one of the parts of the casing in which works the turbine wheel, the conduit being closed by a ring, Z.

The form of the nozzle I is most important. The sectional area of the smaller end has to be large enough to allow of the passage of the requisite amount of steam, while a sufficient section is required at the larger end

for the complete expansion of the steam. The length of the nozzle must also exceed a certain amount, or the steam will take an eddying or irregular course through it. Too long a nozzle is objectionable, on account of friction.

This expansion of the steam before it enters the vanes is of great practical importance, for it allows of a considerable amount of clearance being permitted all round the turbine wheel in the case. In turbines constructed by the Société de Laval of France, a clearance of 2 to 5 millimetres is allowed all round the wheel. This permits of a very flexible shaft being used as a slight displacement of the wheel may take place without any injurious consequences. The pressure in the wheel-box or case is practically that of the exhaust exit from the case, and the turbine works like an impulse hydraulic turbine. The flexibility of the shaft is conducive to steadiness of motion at high speeds. To utilize a large proportion of the kinetic energy of the steam, as is done, the vane speed has to be enormous. Even the speed of the second motion or power shaft is usually very high. The great velocity and absence of pressure, however, allow of great lightness.

Table III. gives the total weights of steam turbines of various sizes as made by the Société de Laval, with the angular velocities of the second motion or power shafts. The first five sizes have each one power shaft; the others have two.

TABLE III.

WEIGHTS AND SPEEDS OF ROTATION OF DE LAVAL TURBINE MOTORS.

B.H.P. of turbine motor.	Total weight in kilograms.	Revolutions per min. of power shaft.
5	150	3000
10	225	2400
15	260	2400
20	420	2000
30	580	2000
50	1570	1500
75	1870	1500
100	2650	1250
150	3140	1040
200	4900	910
300	7650	775

The diameter of the turbine wheel is only 12 centimetres for a motor of 10 B.H.P., where the wheel revolves at the rate of 24,000 revolutions per minute, and 30 centimetres for a turbine of 100 B.H.P., with a wheel velocity of 15,000 revolutions per minute, while the turbine wheel, with an angular velocity of 7500 revolutions per minute, belonging to a 300 B.H.P. motor, has a diameter of 70 centimetres.

Plate III. shows 100 B.H.P. De Laval steam turbine dynamo made by Messrs. Greenwood and Batley, of Leeds. This machine has been delivered to, and is now at the works of, the Morris Aiming Tube and Ammunition Co., Ltd., Essex. It will be seen that there are two armatures. These are mounted on shafts which carry inside the gear-box helical-toothed wheels, which gear one on each side with a pinion mounted on the turbine shaft. The turbine wheel case is seen at the right of the figure, with the wheels for controlling the supply of steam to the several nozzles. The flange for connection to the steam supply is seen over the turbine case, and the exhaust outlet is shown at the bottom of the case. The weight of this machine complete is 6 tons, and the designed speed of rotation of the armature-spindles is 1050 revolutions per minute. A machine of the same power as this, but of earlier design, has been in constant use for several years at the Albion Works of Messrs. Greenwood and Batley.

Fig. 114 shows a De Laval turbine centrifugal pump as supplied by the same firm. T is the turbine-wheel casing, surrounding which can be seen the wheels W for controlling the steam jets. G is the gear-wheel casing, emerging from which can be seen the two pump shafts, which are driven like the armature shafts of the turbine dynamo just described.




PLATE III.—100-B.H.P. DE LAVAL TURBINE DYNAMO MADE BY MESSRS. GREENWOOD AND
BATLEY, LEEDS.



Centrifugal pumps A and B are arranged one on each shaft, the two pumps working in parallel.




FIG. 114.—De Laval Turbine (Parallel) Centrifugal Pump.

Fig. 115 shows a turbine pump constructed by the Société de Laval, but in which the pumps are arranged in series as regards delivery of water. The pumps are arranged on parallel shafts as in the pump just mentioned, but in the series pump the delivery end of the one pump is connected to the suction end of the other, so that the pressure and not the amount of water is doubled.

The constant turning moment on the pump shaft causes

these pumps to work very quietly, and the high speed of rotation allows the water to be raised to considerable heights.

Fig. 116 shows a turbine blower as constructed by the French company.

Table IV. gives particulars of tests made by Messrs. Erik Andersson, Karl Wallin, and Axel Estelle, at the works of the Aktiebolaget de Laval's Angturbin in Sweden in 1895, on a 50 H.P. turbine dynamo. Steam was generated at 118 lbs. per square inch, and reduced by a throttle valve. The turbine had 6 induction nozzles.

TABLE IV.
TEST OF DE LAVAL TURBINE DYNAMO.

Date of trial.	E.H.P. volts \times amp. 736	Steam pressure; lbs. per square inch.	Vacuum; lbs. per square inch.	Number of nozzles used.	Lbs. of steam per E.H.P. per hour.
Feb. 15	49.92	114	13	6	24.5
Mar. 4	50.05	114	—	6	24.2
"	40.79	114	—	5	24.76
"	21.72	114	—	3	27.9
"	25.34	93.8	13.27	4	27.49
"	12.87	74	13.5	3	32.0

It should be noted that the electrical horse-power unit is obtained by dividing the product of volts and ampères by 736 instead of by 745, as is done in this country. The steam consumption was obtained on March 4, by inserting one of the steam nozzles into a pipe leading to a vessel containing a quantity of water where the steam was condensed. The amount of steam passing through this nozzle was thus ascertained, and it was assumed that the amount passing through each of the other (acting) nozzles was the same, the design and cross-sections of the nozzles being identical. The amounts probably




FIG. 115.—De Laval Turbine (Series) Centrifugal Pump.




FIG. 116.—De Laval Turbine Blower.

were nearly the same, as was shown by a check test, but it cannot, of course, be assumed that this will be so in every case.

Table V. shows the results of tests on a De Laval turbine made by Professor Cederholm, of Stockholm, in November, 1897. The power was measured by a brake.

TABLE V.
DE LAVAL TURBINE OF 150 BRAKE HORSE-POWER.

No. of nozzles used.	Brake horse- power.	Steam pressure.		Vacuum.		Revolutions.	Consumption of steam per B.H.P. per hour.	
		Kilos per sq. centim.	Lbs. per square inch.	Millim. of mercury.	Inches of mercury.		Kilos.	Lbs.
7	165·3	8·00	113	670	26·4	1057	7·87	17·3
5	116·1	8·00	113	666	26·2	1057	8·01	17·6
3	65·0	7·90	112	685	27 0	1060	8·49	18·7

In 1896 tests were made of the steam consumption of one of the turbine dynamos supplied by the Société de Laval to the Edison Electric Illuminating Company of New York. The tests were made at the works of the Illuminating Company in New York.

The following is a summary of the trial, the report on which is signed by Messrs. Smith, Van Vleck, and De Kermel representing the Edison Electric Illuminating Company, and Mr. Paré, who represented the Société de Laval.

Duration of trial 6 hours.
Mean steam pressure 10 kilos. per square
centimetre, or 143
lbs. per square inch.
Mean vacuum in condenser 65 centimetres, or 25½
inches.
Dynamo No 1, mean volts 127·25, mean ampères 708·56.
Dynamo No. 2, mean volts 128·26, mean ampères 727·47.

The total power generated was therefore about 183 kilowatts.

A surface condenser was used, and was tested to prove that no leakage took place. The amount of water condensed in the six hours was 12,493·35 kilograms, or 2082·22 kilograms per hour.

The steam consumption per kilowatt hour was therefore $\frac{2082\cdot22}{183}$, or 11·38 kilograms (*i.e.* 25·1 lbs.).

Seven hundred and thirty-six watts were taken as an electrical horse-power, and the efficiency of the dynamo was assumed to be 90 per cent. The brake horse-power of the turbine under these assumptions was therefore about 276·7, and the consumption of steam per B.H.P. per hour $\frac{2082\cdot22}{276\cdot7}$, or 7·52 kilograms (*i.e.* 16·6 lbs.).

CHAPTER IX.

THE RATEAU STEAM TURBINE.

It has already been pointed out that in the Parsons turbine the steam is expanded gradually in passing alternately through fixed and moving rings of blades, while in the De Laval type of turbine, the steam is expanded in a divergent nozzle before it reaches the vanes of a single rotating wheel. It has also been pointed out that the De Laval type of motor has an advantage over the Parsons type in so far that the amount of clearance round the wheel does not need to be small. In a Parsons turbine, the amount of clearance spaces between the fixed and moving rings of blades have to be most minute to prevent excessive leakage of steam, especially at the high-pressure end of the turbine. It is true that the leakage of steam round the rings of blades, instead of through between the blades, does not represent the same loss of power as the leakage of steam past the piston of a reciprocating engine, for the steam that leaks past one ring of blades reserves its energy for the next ring, or gives up its saved heat to the rest of the steam. It will, however, be obvious on a little consideration that this leakage of steam must entail a lengthening of the turbine cylinder, and an increase in the number of rings of blades, in order to expand the steam to the desired extent. This involves increase in bulk, weight, cost, and radiation.

To minimize the leakage of steam, great accuracy and good workmanship are required; and, although these requisites can be commanded by Messrs. C. A. Parsons and Co., they might not be obtained in less well-equipped or less well-managed works.

The disadvantage of the De Laval type of steam turbine is the excessive velocity which the blades must have, necessitating the use of gearing to obtain speeds of rotation which can be utilized for industrial purposes. In the more powerful De Laval motors, the larger turbine wheels employed allow somewhat smaller angular velocities to be obtained without reducing the velocity of the vanes; but in all cases the number of revolutions per minute of the turbine wheel is very high. Apart from the objectionable feature of gearing, the velocity of the vanes is limited by the strength of the materials of construction. As has already been pointed out in Chapter V., the stress due to centrifugal force in a rotating ring becomes enormous at high velocities. The vane-speed in a De Laval turbine is thus limited by the strength of material obtainable. Increasing the diameter of the wheel makes approximately no difference if the vane-speed remains constant. By arranging the vanes on the periphery of a disc which increases in thickness from the circumference to the centre, a somewhat higher speed may be obtained, the inner parts of the disc supporting the outer, but still a limit is reached to the safe speed before the best velocity is obtained for utilizing the energy of high-pressure steam.

The Rateau steam turbine, as now constructed by Messrs. Sautter, Harlé and Co., of Paris, and by the Maschinenfabrik Oerlikon of Switzerland, has been devised with the object of obtaining the advantages of the De Laval motor while adopting




FIG. 118.—Rateau Steam Turbine: Longitudinal section.

the plan of expansion in steps and action on a series of wheels in order to obtain a more moderate speed of rotation.

This type of steam turbine is somewhat like the Parsons parallel flow-motor, but differs from the latter in this respect, that each rotating ring of blades revolves, as it were, in a compartment by itself. If we can imagine a number of De Laval turbines placed side by side with the wheels in parallel planes, and if we imagine a large number of nozzles extending from the exhaust side of one wheel, through the casings to the steam side of the next wheel, we have in principle a Rateau turbine as now constructed at Oerlikon and by Messrs. Sautter, Harlé and Co., of Paris.

Fig. 118 is a longitudinal section through a marine steam turbine of this type, and Figs. 119 and 120 are transverse




FIG. 119.

FIG. 120.

Transverse Sections of Rateau Steam Turbine.

sections of the same. The plane of section of the left-hand half of Fig. 119 is represented by the line X^1X^1 on Fig. 118, and the plane of section of the right-hand half by the line X^2X^2 .

The planes of section of the left and right-hand parts of Fig. 120 are represented on Fig. 118 by the lines X^3X^3 and X^4X^4 respectively.

The cast-iron or cast-steel cylinder D^1, D^2, D^3 is made in several parts and is strengthened by circumferential ribs. The high-pressure end of the cylinder is closed by the dished plate F to a flange on which is attached the steam-pipe A . Steam passages, a^1, a^1 , are provided to allow of the steam reaching the first distributor or guide ring B^1 . This distributor consists of a series of blades which occupy a portion of the inner circumference of the casing. These blades guide the steam in the proper direction on to the blades C^1 of the first rotating disc c^1 . This disc is of thin steel slightly dished and is attached to an annular flange formed on a hub mounted on the turbine shaft H . The disc is formed with a circumferential flange to which the blades are attached. Fig. 121 shows a method of riveting




FIG. 121.

the rotating blades C to the flanged periphery P of the disc, two consecutive blades being shown. The pieces U are cast on to the blades at their flanged ends to stiffen them. It will be seen from the figures that the arrangement is very light. The steam on passing the rotating blades C^1 enters a chamber enclosed between the disc c^1 and a diaphragm m^2 . This diaphragm extends from a hub, b^2 , which surrounds the shaft without touching it to the distributing blades B^2 . These blades are fixed to a casting which is attached steam-tight to the inside of the cylinder. The construction is such that the steam can enter the chamber only by way of the rotating blades C^1 , and can leave the chamber only by way of the distributing blades B^2 . These distributing blades direct the steam on to the second set of rotating blades C^2 , after passing

through which the steam enters another chamber enclosed between the disc c^2 and diaphragm m^3 , which is attached to the distributing blades B^3 and to the hub b^3 , the diaphragm, distributing blades, and hub being similar to the preceding, except that the area allowed for the passage of steam is greater. The construction is continued in a similar manner to the end of the cylinder. The diameter of the cylinder is increased at D^2 to afford greater area to the steam. Any steam that may leak out between any set of distributing blades and the succeeding rotating blades is in a closed chamber between the diaphragm of this set of distributing blades on the left hand and the diaphragm of the next set of distributing blades on the right hand. Each revolving disc, therefore, rotates in a closed chamber just like a De Laval turbine, the pressure on both sides of the rotating disc being approximately the same. There is, of course, a slight leakage of steam between the hubs b^2 , b^3 , etc., and the shaft; but a clearance of a few millimetres here does not allow a large area for the escape of steam, and any distortion of the machine is not so likely to cause rubbing at this point as at the circumference of the rotating discs.

Fig. 122 shows one of the diaphragms attached to the distributing blades of a slightly different design to that shown in Fig. 118. The bush 2 inserted in the hub

is just clear of the shaft. The part 3 fits into a groove in the surrounding cylinder. One of the distributing vanes is




FIG. 122. — Diaphragm and Distributing Vane of Rateau Turbine.

shown at B, these vanes being usually fitted only on a small part of the circumference at the high-pressure end of the turbine and increasing in number towards the low-pressure end; 4 is a plate riveted on the front of the diaphragm in order to present a smooth surface to the steam and so reduce friction.

The last five rings of rotating blades C^{21} to C^{25} are not mounted like the others, but are attached to the exterior of a drum which is connected to the shaft H by the discs c^{21} and c^{25} . The distributing blades B^{21} to B^{25} are connected only to the enclosing cylinder. K is the exhaust passage, and it will therefore be seen that the back of the plate c^{25} is exposed to the pressure of the exhaust, while the front of the plate c^{21} is exposed to the pressure of the steam which acts on the blades C^{21} . An axial thrust is thus exerted on the rotating parts of the turbine, and this axial thrust is used to wholly or partially balance the thrust of the screw propeller. In a turbine used for driving a dynamo or otherwise where no axial thrust is required, this arrangement of blades which is the same as that in a Parsons parallel-flow turbine may be dispensed with. The arrangement has the disadvantage, mentioned at the beginning of this chapter, that leakage of steam will take place between the inner periphery of the distributing rings of blades and the exterior of the drum carrying the rotating blades.

For rotating the turbine in a reverse direction (when this is required) a number of vanes, N, are provided, the curvature of which is opposite to that of the other moving vanes. Steam is guided on to these vanes by nozzles, M, leading from a supply conduit L. The rotating vanes, N, are carried by the disc c^{25} , and the steam exhausting from these vanes is guided by the annular trough n to the exhaust passage K.

The shaft K is supported in three bearings G^1 , G^2 , G^3 . These bearings are supplied with oil under pressure conveyed to the respective bearings by the pipes g^1 , g^2 , g^3 . The pressure of oil in the bearing G^3 is used to prevent air leaking into the exhaust end of the turbine when the latter is connected to a condenser.

M. Rateau has also experimented, in conjunction with Messrs. Sautter, Harlé and Co., with other types of steam turbines having one, two, or more discs. Some account of these experiments is given in M. Rateau's interesting paper presented to the International Congress on Applied Mechanics held at Paris in the summer of 1900. In a one-disc turbine described in the paper, the disc was formed from a single piece of special forged steel in the periphery of which the vanes were milled. These vanes were of the double type like those of a Pelton water-wheel. The disc increased in thickness from the periphery to the centre, this design being adopted for the sake of strength to resist centrifugal force. The stress produced in a ring due to the centrifugal force caused by its own weight, has already been discussed in Chapter V. M. Rateau has calculated that, by substituting a disc of uniform thickness for a ring, the allowable speed of rotation is only increased by 7 per cent. In this case the dangerous part is at the centre of the disc. By increasing the thickness progressively towards the centre, M. Rateau has found that considerably higher speeds can be attained. In fact, with special hard steel he has obtained, without rupture, peripheral velocities of 400 metres per second.

The steam was projected on to the disc by several nozzles, and the jets of steam were divided in two by the central ridges of the buckets, as in the Pelton water-wheel. The nozzles

were arranged to project the steam on to the lower part of the disc so that the impact of the steam helped to balance the weight of the disc. One or more of the nozzles could be put out of action to decrease the power of the motor. The best results were obtained by supporting the disc shaft in one bearing only. The disc had thus a slight play owing to the flexibility of the shaft, and was able to choose its own centre of rotation. Gearing was employed to reduce the speed of the disc, the gear-wheels being of double helicoidal form and enclosed in a dust-proof box. The best form of packing tried at the place where the shaft passed through the side of the casing containing the disc consisted of a ring split into three pieces along three diametrical planes. This split disc was pressed against the side of the casing by means of springs. When the shaft did not vibrate, the ring worked as if solid, whilst, when the shaft did vibrate, the three pieces moved apart to give it freedom. This packing was found to be tight as long as the vibrations of the shaft were not considerable.

CHAPTER X.

FURTHER REMARKS ON THE PARSONS TURBINE.

THE efficiency of a condensing steam turbine depends largely on the pressure at the exhaust end, or, in other words, the number of inches of vacuum at this end. Tables VI. and VII. show the effect on a Parsons turbine of altering the vacuum in the condenser. It will be seen that every additional inch of vacuum reduces the steam consumption about 4 per cent.

TABLE VI.

CONSUMPTION OF 500-KILOWATT PARSONS TURBO-ALTERNATOR RUNNING AT 2500
REVOLUTIONS WITH 140 LBS. STEAM PRESSURE AT THE STOP-VALVE AND
NO SUPERHEAT. (Based on results of tests.)

Vacuum constant from full load to no load.	Consumption of steam per kilowatt-hour.			Consumption per hour.
	full load.	half load.	quarter load.	
inches of mercury.				no load,
29	—	—	—	1500
28	22·2	25·6	32·4	1700
27	23·1	26·9	34·5	1900
26	24·0	28·2	36·6	2100
25	25·1	29·7	39·0	2300
24	26·2	31·2	41·2	2500
23	27·5	32·9	44·8	2700
22	28·9	34·7	46·3	2900

Barometer = 30 ins.

TABLE VII.

CONSUMPTION OF 1000-KILOWATT TURBO-ALTERNATOR CONSTRUCTED BY MESSRS.
C. A. PARSONS AND CO. FOR ELBERFELD CORPORATION. NO SUPERHEAT.

Pressure stop-valve.	Vacuum. Barometer = 30 ins.	Kilowatts.	Steam per kilowatt-hour.
lbs. per sq. in.	inches of mercury.		lbs.
157.5	26.97	1010	23.08
153.0	24.45	1041	25.25
125.0	27.10	1022	20.47

But even with a good vacuum in the condenser, the efficiency may be spoilt by the throttling of the exhaust by narrow pipes or passages between the turbine and the condenser. To prevent any possibility of this, Mr. Parsons has invented




FIG. 123.—Vertical section.

Parsons Combined Turbine and Condenser.

and patented a combined turbine and condenser, which is illustrated in Figs. 123, 124, and 125, the turbine being of the parallel-flow type. Fig. 123 shows the combination in

vertical section, and Fig. 124 in plan; while Fig. 125 is a partial vertical section on the line AA of Fig. 123. The casing *c* of the turbine is bolted at *d* to the end *e* of the condenser.




FIG. 124.—Plan.
Parsons Combined Turbine and Condenser.

The turbine spindle *f* passes through the turbine and condenser, and is supported in bearings at *g* and *h*. The turbine and condenser casings are supported on feet, *k*, *k*. The steam enters the turbine casing at *l*, and, after going through the fixed and moving rings of blades *a*, passes directly out of the large end of the turbine casing into the condenser. The turbine and condenser casings act as if made in one piece, and are, in fact, only made in separate castings for constructional reasons. The




FIG. 125.—Partial vertical section on line AA of Fig. 123.
Parsons Combined Turbine and Condenser.

outlet from the condenser to the air-pump is shown at *n*. The circulating water enters the condenser at *o*, and passes into compartment *p*. It then passes up through the tubes *q* to the

top chamber *r*, whence it descends through the tubes *s* to the compartment *t*, and leaves the condenser at *u*.

When it is desired to cause the shaft of a turbine to revolve in a reversed direction, this is usually accomplished by placing a reversing turbine on the same shaft as the main turbine. The main and reversing turbines are usually in separate casings, and steam is admitted to one or the other according to the direction of rotation desired. Both have their exhaust ends permanently connected to the condenser, so that the one not working rotates in the condenser vacuum; and, as there are no rubbing parts within the casing of a turbine, the drag of the inoperative turbine is almost inappreciable.

The main and reversing turbines may, however, with advantage be placed within the same casing. Fig. 126 shows




FIG. 126.—Parsons Arrangement of Main and Reversing Turbines in One Casing.

an example of this. The main turbine *a* is enclosed chiefly in the casing *c*, which is bolted at *e* to the casing *d*. The casings *c* and *d* are cast with feet, A and B, and the casing *d* also carries an internal cylinder, *l*, which encloses the reversing turbine *b*. Both turbines are of the parallel-flow type, and both have their

moving rings of blades attached to the spindle *f*. The low-pressure ends *g* and *h* of the two turbines open into the passage *k*, leading to or forming a part of the condenser. The steam supply for the main turbine enters by the passage *n*, while that for the reversing turbine is admitted through the casing *d* at *m*. The turbines shown in Fig. 126 are intended for marine purposes, and the reversing turbine is therefore smaller than the main turbine, as the astern speed of a vessel is not usually required to be so great as the ahead speed.

Fig. 127 shows another example of main and reversing




FIG. 127.—Parsons Arrangement of Telescoping Reversing Turbine within Main Turbine.

turbines in one casing. The reversing turbine *b* is here telescoped within the main turbine to save longitudinal space. The stationary rings of vanes of the main turbine are fixed, as is usual, to the casing *c*, the moving rings being attached to the drum *o*, which is fixed to the shaft *f*. The reversing turbine has its fixed rings of blades attached to the exterior of the cylinder *p*, which is fixed to the casing *d*, while its moving rings are carried by the casing *7*, which is rigid with the drum *o*. The steam enters the main turbine at *n*, while

it gains access to the reversing turbine by the pipe *r*. The exhaust ends, *g* and *h*, of both turbines open directly into the condenser passage *k*.

A Parsons turbine can be reversed by interchanging its steam and exhaust connections so that the steam passes through the turbine in the reverse direction, but the efficiency is not as great. If the blades are designed for maximum efficiency in one direction, the efficiency when rotating in the other direction is much reduced. The usual construction of blades has been already shown in Figs. 3, 4, 5, 8, 10, and 72A. It will be seen that both in the fixed and in the moving blades the space between two adjacent blades converges from the side at which the steam enters to the side at which it leaves. The concave face of the blade at the side at which the steam enters is almost at right angles to the direction of motion of the moving blades. When the flow of steam is reversed, the blades are much less efficient. Mr. Parsons has patented the form of blade illustrated in Fig. 128 for use in turbines intended to run in




FIG. 128.—Form of Blades adapted for Rotating in Either Direction.

both directions. Here the blades are straight for the greater part, but each blade is hollowed out at both ends, at *g* and *h*, so that, whichever way the steam flows, it impinges on a concavity. The fixed blades are lettered *f*, and the revolving




PLATE IV.—METROPOLITAN ELECTRIC SUPPLY COMPANY'S SARDINIA STREET STATION WITH PARSONS STEAM TURBINES COUPLED TO ALTERNATORS.



blades r . The latter move in the direction of the arrow 3 when the steam passes as indicated by the arrow 1, and in the direction of the arrow 4 when the steam flows as indicated by the arrow 2. Messrs. C. A. Parsons and Co. have a very ingenious machine for constructing the rings of blades used in their turbines. Shrouds of suitable metal, preferably brass, are formed into a circle, or segment of a circle. On one edge of the strip, teeth of special shape are cut by means of a circular cutter. The form of the teeth is such that, when the blades are laid in the grooves and the teeth turned over them, the teeth and blades fit each other closely, and form a secure fastening. This will be clear by referring back to Figs. 3, 4, and 5. In Fig. 3 some of the teeth of the shrouds are shown before they are bent down over the blades. The bending down of the teeth is performed by a punch which acts about three or four teeth behind the cutting-tool, so as to give the attendant time to insert the blades. The rings of blades are usually constructed with a heavy shroud at one end and a light shroud at the other, the heavy shroud being inserted and caulked into a groove in the turbine casing or revolving drum.

The governing of a Parsons turbine is usually effected by varying the duration of puffs or blasts of steam admitted to the turbine. Fig. 129 shows an electrical governor arranged for this purpose. The solenoid U is energized by electric current (from the electric generator driven by the turbine), so that increase or decrease of speed of the turbine causes the lever U^2 to overcome the resistance of the spring U^1 , or to be overcome by it. This lever, by means of the projection U^3 , moves a cam sleeve, V , on the second-motion shaft Q^1 . The sleeve, although free to slide along the shaft, rotates

with it, and the cam surface cut on the sleeve acts on a roller so as to depress the steam-valve spindle R against the spring R^1 . The cam surface is so arranged that in one position of the sleeve V , the steam-valve is held open during the whole revolution of the shaft Q^1 —that is, steam is admitted continuously by the steam valve to the turbine. When, however,




FIG. 129.—Electrical Governor for Parsons Turbine.

the solenoid gets more strongly energized, it pulls the sleeve V to such a position that steam is admitted to the turbine only for a portion of a revolution of the shaft Q^1 ; and, the greater the energizing current, the further the sleeve moves along, so that steam is admitted to the turbine for a smaller and smaller fraction of a revolution of the shaft Q^1 . The shaft Q^1 is driven by the frictional contact of a wheel or disc carried by it with the end of the turbine spindle, the speed of revolution of the shaft Q^1 being much less than that of the turbine spindle.

Figs. 130 and 131 show another arrangement of electric governor. Steam is admitted to the turbine by the double-beat valve A from the steam space A¹. Steam which leaks past the neck-bush C acts on the piston B¹ so as to force it upwards against the action of the spring B². This occurs when the valve D is closing the passages B³ and B⁴, but, when these passages are opened, the steam escapes from the lower end of the cylinder faster than it can enter by the leak; and so the piston B¹ descends, and, by means of the rod B, closes the main valve A. For intermediate positions of the valve D, the main valve assumes positions of partial opening. The eccentric G¹ is driven from the turbine spindle H by means of a worm and worm-wheel, and gives a rocking motion to the lever G. This is pivoted at G², and, consequently, its end E¹ has an up-and-down motion. This end, E¹, is connected to a lever, E, one end, E², of which is attached to the valve D. The lever E can turn about the point E³, and the valve D will, therefore, be reciprocated up and down by the action of the eccentric G¹. This will allow regular puffs or blasts of steam to pass through the valve A.

The other end of the lever E is pivoted to the core F¹ of the solenoid F, which tends to draw it down against the action of a spring at E³; so that an increase or diminution in the strength of the current energizing the solenoid will cause the lever E to turn about the point E¹ and actuate the valve D. The effect of the combined action of eccentric and solenoid is to prolong or shorten the duration of the puffs, and the turbine is thus governed.

Centrifugal governors may be employed to control the admission of steam equally as well as electrical governors. For example, in Fig. 129 the sleeve V might have been actuated




FIG. 130.—Sectional elevation.

FIG. 131.—Plan.
Electrical Governor for Parsons Turbine.




PLATE V.—VICTORIAN RAILWAYS LIGHTING STATION EQUIPPED WITH FOUR 150-KILO-WATT PARSONS TURBINE ALTERNATORS WITH EXCITERS.



by a centrifugal governor mounted on and rotating with the second-motion shaft Q¹. The electrical governor has the advantage in cases where constant voltage is required, as it can control the voltage independently of the speed.

Plate IV. shows an installation of steam turbine alternators supplied by Messrs. C. A. Parsons and Co. to the Metropolitan Electric Supply Co. An injunction was obtained against this company to cease running at their Manchester Square Station unless the vibration was prevented. The company satisfied the plaintiffs by removing the reciprocating engines then installed, and replacing them by steam turbines.

In Plate V. is seen the interior of the Victorian Railways Lighting Station. Four turbine alternators, each of 150 kilowatts capacity, and provided with exciters, are there installed and run in parallel. Ferranti rectifiers are used, and the current employed for both arc and incandescent lighting.

Plate VI. shows a steam turbine driving a centrifugal pump. This was supplied by Messrs. C. A. Parsons and Co. to Messrs. Storey Bros., Lancaster, and is said to be capable of delivering 53,000 gallons per hour against a head of 165 feet.

Parsons turbines are also used for directly driving fans and air-propellers. Plate VII. shows a turbine-driven fan installed at the Clara pit in Durham. It is 5 feet in diameter, and said to be able to deliver 120 cubic feet of air per minute at a pressure equal to 2 inches of water.

CHAPTER XI.

SOME RECENT TESTS OF PARSONS TURBINES.

THIS chapter will be devoted to giving the results of some recent tests of Parsons turbines.

TABLE VIII.

TEST OF 24-KILOWATT TURBO-DYNAMO FOR MESSRS. SPILLERS AND BAKERS,
NEWCASTLE-ON-TYNE, CONSTRUCTED BY MESSRS. C. A. PARSONS AND CO.

Pressure of steam above atmosphere at stop-valve.	Superheat at stop-valve.	Vacuum in the turbine cylinder. Bar.=30".	Revolutions per minute.	Load.	Steam used.	
lbs. per sq. in.	degrees F.	ins. of mercury.		kilowatts.	lbs. per hr.	lbs. per kw.-hr.
80	0	28·8	4990	24·7	712	28·8
77	0	29·0	4630	11·8	400	33·9
74	0	29·1	4570	5·15	235	45·6
78	0	26·0	4900	23·8	798	33·5
79	0	0	4780	19·7	1350	68·5

This shows that good efficiencies can be obtained even with steam turbines of comparatively small size. It also shows the effect of better vacuum and higher load on the steam consumption. The former was also shown by Tables VI. and VII., pp. 115 and 116.

TABLE IX.

50-KILOWATT STEAM ALTERNATOR SUPPLIED BY MESSRS. C. A. PARSONS AND CO.
TO THE BLACKPOOL CORPORATION.

Pressure of steam above atmosphere at stop-valve.	Superheat at stop-valve.	Vacuum in the turbine cylinder. Bar.=30".	Revolutions per minute.	Load.	Steam used.	
lbs. per sq. in.	degrees F.	ins. of mercury.		kilowatts.	lbs. per hr.	lbs. per kw.-hr.
126	0	28·0	5044	52·7	1480	28·0
132	0	28·5	4880	0	320	—




PLATE VI.—PARSONS STEAM TURBINE COUPLED TO CENTRIFUGAL PUMP.



With a larger power and higher steam-pressure the efficiency here is slightly greater.

TABLE X.

TWO 100-KILOWATT CONTINUOUS-CURRENT TURBO-DYNAMOS FOR WEST BROMWICH ELECTRIC LIGHTING STATION, MADE BY MESSRS. C. A. PARSONS AND CO.

Pressure of steam above atmosphere at stop-valve.	Superheat at stop-valve.	Vacuum in the turbine cylinder. Bar.=30".	Revolutions per minute.	Load.	Steam used.	
lbs. per sq. in.	degrees F.	ins. of mercury.		kilowatts.	lbs. per hr.	lbs. per kw.-hr.
129	54	27·8	3500	123	3144	25·5
134	64	27·7	3520	122	2913	23·8

With a greater power and moderate superheat the efficiency is again improved.

In January, 1901, a series of trials were made by Professor Ewing of a 500-kilowatt steam turbo-alternator at the works of the Cambridge Electric Supply Co.

The machine was constructed by Messrs. C. A. Parsons and Co., and erected at the Cambridge Electric Co.'s station in January, 1900, and ran at times daily, and at times intermittently, according to requirements, up to the time it was tested.

The turbine is of the parallel-flow type, with its shaft as usual directly coupled to the armature of the alternator, which is of the four-pole type, and designed to give 250 ampères at 2000 volts, running at 2700 revolutions a minute. The turbine is governed electrically, and is furnished with a surface condenser, and drives its own air-pump and circulating pump by means of a shaft carrying a screw-wheel driven by a worm on the main turbine shaft.

Table XI. shows the collected results of the trials, and Figs.

132 and 133 show the steam consumption graphically. The straightness of the line in Fig. 133 will be noticed.

TABLE XI.

TESTS OF 500-KILOWATT PARSONS TURBO-ALTERNATOR AT CAMBRIDGE.

Trial number.	Effective electrical output in kilowatts.	Consumption of steam.	
		lbs. per hour.	lbs. per kw.-hour.
Trials of Jan. 9 	(1) 518	12,970	25.0
	(2) 586	14,320	24.4
	(3) 273½	7,730	28.3
	(4) 160½	5,320	33.1
	(5) 0	1,850	—
Preliminary trials of Jan. 8	{A. 535	13,350	25.0
	{B. 300	8,270	27.6




FIG. 132.—Steam Consumption of 500-Kilowatt Parsons Turbo-alternator at Cambridge.




FIG. 133.—Steam Consumption of 500-Kilowatt Parsons Turbo-alternator at Cambridge.

Table XII. supplies particulars of the pressures, temperatures, speeds, etc.

TABLE XII.

TESTS OF 500-KILOWATT PARSONS TURBO-ALTERNATOR AT CAMBRIDGE.

Number of trial.	1.	2.	3.	4.	5.	A.	B.
Electrical output in kws.	518	586	273½	160½	—	535	300
Volts at terminals of generator	2,100	2,150	2,250	2,290	2,280	2,120	2,110
Speed in revolutions per minute	2,670	2,740	2,630	2,590	2,580	2,880	2,800
Air-pump discharge, lbs. per hour	12,970	14,320	7,730	5,320	1,850	13,350	8,270
Air-pump discharge, lbs. per kws. per hour	25.0	24.4	28.3	33.1	—	25.0	27.6
Pressure at stop-valve, lbs. per sq. in.	148	145	151	151	121	145	150
Vacuum in condenser, inches	27.8	27.9	28.2	28.3	28.3	26.6	27.6
Vacuum in turbine cylinder, inches	25.7	25.4	27.2	27.8	28.1	25.1	26.2
Temperature of air-pump discharge, ° F.	74	76	57.5	56	54	90	68
Temperature of circulating water, inlet, ° F.	40	40	38	39	36	41	39
Temperature of circulating water, outlet, ° F.	71	72.5	60	57	46	91	71
Barometer, inches ...	29.93					29.99	

In January, 1900, tests were made at the works of Messrs. C. A. Parsons and Co., Newcastle-on-Tyne, of a 1000-kilowatt

turbine-generator, constructed by that firm for the electric station of the city of Elberfeld. This machine is shown in Plate I. The tests were conducted by W. H. Lindley, Esq., M.Inst.C.E., and Professors Schröter and Weber of the Polytechnicum, Zurich. Steam was supplied by one Babcock and Wilcox boiler, two marine boilers, and a locomotive boiler. A Babcock and Wilcox superheater with independent firing was introduced into the main steam-pipe. The machine was loaded with a water resistance consisting of four electrodes immersed in four iron vessels fitted with water coolers, while an auxiliary adjustable water resistance was employed to regulate the load.

The tests extended over three days, exclusive of a preliminary trial, and the results as regards steam consumption are given in Table XIII.

TABLE XIII.

TESTS OF 1000-KILOWATT PARSONS STEAM TURBO-ALTERNATOR FOR ELBERFELD CORPORATION.

Number of series.	Amount of load.	Exact value in output in kws.	Steam consumption per kw.-hour.		Steam consumption in one hour.
			lbs.	kgs.	kgs.
A.	Preliminary trial	1172.7	18.22	8.26	9,689
II.	Overload	1190.1	19.43	8.81	10,485
I.	Normal load	994.8	20.15	9.14	9,092
III.	Three-quarter load	745.3	22.31	10.12	7,542
IV.	Half load	498.7	25.20	11.42	5,695
V.	Quarter load	246.5	33.76	15.31	3,774
VI.	No load with alternator excited	0	—	—	1,844
VII.	No load without excitation ...	0	—	—	1,183

The same steam-pressure and the same amount of superheat were not used in all the trials. The steam consumption was, therefore, calculated by the experts conducting the tests for a steam temperature of 197.3° C., this being a superheat of





PLATE VII.—VENTILATING FAN DRIVEN BY A PARSONS STEAM TURBINE AT CLARA PIT, DURHAM.



14.3° C.; and, to enable a comparison to be made with the steam consumptions of engines working with saturated steam, the equivalent consumptions for saturated steam at eleven atmospheres were calculated. The results are given in Table XIV.

Fig. 134 shows the steam consumption graphically.




FIG. 134.—1000-Kilowatt Parsons Turbo-alternator. Diagram of total steam consumption per hour.

Table XV. shows the variation in the speed between no load and full load. The number of revolutions per minute was obtained by noting the time occupied by 200 revolutions of the driving-wheel of the valve-gear and air-pump, this driving-wheel rotating at one-eighth of the speed of the turbine.

TABLE XIV.
TESTS OF 1000-KILOWATT PARSONS TURBO-ALTERNATOR.

Number of series.	Load in kilowatts.	Average observed steam pressure in $\frac{\text{kgs.}}{\text{cm.}^2}$ absolute.	Corresponding temperature of saturated steam.	Average observed temperature of superheated steam at inlet valve.	Superheating (Col. 5 - Col. 4).	Observed steam consumption per kw.-hour.	Total heat contained in 1 kg. of steam at observed steam pressure.		Measured consumption of heat per kw.-hour (Col. 9 \times Col. 7).	Corresponding consumption of saturated steam per kw.-hour (Col. 10 \div Col. 8).	Corresponding consumption of steam at 11 kgs. absolute and at 14.3° superheating (1 kg. of steam = 669.2 cal.).	Corresponding consumption of saturated steam at 11 kgs. absolute (1 kg. of steam = 662.3 cal.).
							In saturated condition.	In super-heated condition.				
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)
	kilowatts.	kgs. $\frac{\text{cm.}^2}{\text{kg.}}$	° C.	° C.	° C.	kgs.	calories.	calories.	calories.	kgs.	kgs.	kgs.
II.	1190.1	10.11	179.3	189.5	10.2	8.81	661.1	666.0	5,867	8.87	8.76	8.86
I.	994.8	10.47	180.9	192.0	11.1	9.14	661.7	667.0	6,096	9.21	9.11	9.20
III.	745.3	10.76	182.0	190.0	8.0	10.12	662.0	665.8	6,738	10.18	10.07	10.17
IV.	498.7	10.40	180.6	209.7	29.1	11.42	661.6	675.6	7,715	11.66	11.53	11.66
V.	246.5	10.14	179.4	196.4	17.0	15.31	661.2	669.4	10,248	15.50	15.31	15.47
VI.	No load with excitation.	10.34	180.3	193.0	13.3	per hour, 1844	661.5	667.8	per hour, 1,231,423	per hour, 1861	1840	per hour, 1859
		10.49	181.0	194.5	13.5	1183	661.7	668.2	790,481	1194	1181	1194
VII.	No load without excitation.											

TABLE XV.

1000-KILOWATT PARSONS TURBO-ALTERNATOR. VARIATION IN SPEED BETWEEN
NO LOAD AND FULL LOAD.

Time.	Load.	Steam pressure.	Vacuum in condenser.	Potential of alternator.	No. of revolutions as counted.		Variation in the number of revolutions.	Variation per cent.
					No load.	Full load.		
h. m.	kws.	lbs.	mm.	volts.				
10 44-45	0	150	—	3705	1482	—	—	—
11 16-17	1020	140	693	3960	—	(1433)	(-49)	(3.3)
0 19-20	1035	140	691	3950	—	1424	-58	3.9
11 28-30	0	150	712	3900	1486	—	+62	4.3
11 35-36	1040	145	696	4060	—	1429	-57	3.8
11 44	0	140	712	3880	1472	—	+43	3.0
0 48	960	140	698	4045	—	(1433)	(-39)	(2.6)
0 52	1058	140	693	4040	—	1429	-43	2.9
—	—	—	—	Average	1480	1427	53	3.6

Fig. 135 shows the effect on the speed of governing with a centrifugal governor with an increasing load, while Fig. 136




FIG. 135.—Increasing Load.




FIG. 136.—Decreasing Load.

Variation in speed with centrifugal governor.

shows the same with a decreasing load. Table XVI. gives a summary of the results, the numbers in the fifth, sixth, and seventh columns referring to the distances marked on the diagrams (Figs. 135 and 136).

TABLE XVI.

Test.	Average of all values of load.	Limits : Variation in the load		Variation in speed.			Variation in potential.		Average of variations in the load. Kilowatts.
		within the limit of	in per cent.	Average.			In per cent.	Average.	
				a	b	a-b			
IXa	kilowatts 957	kilowatts, 1086-840	max. min. 19.5 16.3	1.75	0.67	a-b 1.08	+	-	From To 1050↗864
IXb	694	790-590	26.7 16.4	1.28	0.65	0.63	1.19	1.35	766↗623
IXc	497	590-400	47.5 30.5	1.36	0.73	0.63	1.32	1.28	590↗404
IXd	405	500-306	63.4 36.0	1.62	0.86	0.75	1.35	1.41	490↗312
IXe	251	292-204	43.1 26.9	1.37	0.63	0.74	1.34	1.29	292↗210 and back.

As the average potential may be taken at 4000 volts, the actual variation of 52 volts on the average amounts to **1.3** per cent. of the initial potential.


TABLE XVII.

Test.	Average of all values of load. kilowatts.	Limits: Variation in the load within the limits of		Speed.			Variation in voltage.		Average of variations in the load. Kilowatts.
		max.	min.	Variations.			In per cent.	Volts.	
		kilowatts.		a	b	d			From To
Xa	281	336-222	51.3 27.5	—	—	—	+ 1.05 — 1.10	43	230 \rightleftharpoons 332
Xb	492	616-380	62.1 34.4	0.31	0.22	1.32	1.10	45	382 \rightleftharpoons 601
Xc	714	(900)-580	55.2 12.2	0.24	0.20	1.29	1.11	44	611 \rightleftharpoons 818
Xd	900	1016-790	30.6 19.3	0.21	0.27	1.26	1.06	45	797 \rightleftharpoons 1007 and back.

The average variation in the potential amounts to 44 volts, *i.e.* to 1.1 per cent. of the initial voltage.

Figs. 137 and 138 and Table XVII. show the effects of governing with an electrical governor.


before increasing load



after increasing load

FIG. 137.—Increasing Load.

after decreasing load



before decreasing load

FIG. 138.—Decreasing Load.

Variation in speed with electrical governor.

It will be noticed that the centrifugal governor increases the speed with diminishing load and reduces the speed with increasing load, while the action of the electrical governor is the reverse.

CHAPTER XII.

THE STEAM TURBINE APPLIED TO THE PROPULSION OF VESSELS.

THE success of the Parsons steam turbine on land led to the formation of a company in the beginning of 1894 for applying the steam turbine to marine purposes. This pioneer syndicate—the Marine Steam Turbine Co.—at once commenced experimental work, and the *Turbinia* was produced. It had often previously been proposed to use a steam turbine for the propulsion of vessels at sea; but, as far as the author is aware, no steam turbine was ever before fitted on board a vessel for this purpose. The same difficulty now arose with the marine steam turbine as had arisen with turbines previously made for use on land—namely, of running the turbine economically at a sufficiently low speed. In the driving of alternators a high speed is usually an advantage, except when it becomes so excessive as to occasion dangerous stresses due to centrifugal force. With screw propellers, however, the case is very different. The existence of cavitation with high velocities of screw propellers was not unknown at the time the *Turbinia* was built; but the importance of it with propeller-blade velocities such as those tried in the *Turbinia* was not appreciated. The trials of the *Turbinia*, however, clearly demonstrated that an ordinary propeller could not be run with any degree of efficiency above a certain velocity. Beyond this limiting

velocity (the exact value of which depends on the size and form of the propeller) an almost perfect cylindrical vacuum is formed around the propeller, causing great loss of power.

As a steam turbine could not be run economically except at a high velocity—above the limiting velocity of a propeller—the difficulty arose of getting an efficient combination. With a low velocity the steam consumption was excessive; with a high velocity the waste of power by the propeller was enormous.

The designers of the *Turbinia* and her propelling gear, however, energetically and scientifically grappled with the difficulty. Trials were made with screws of various patterns, a spring torsional dynamometer was constructed and fitted between the turbine and the propeller-shaft to measure the actual torque, and a series of experiments were carried out in a tank with model propellers, which were illuminated by the light from an arc lamp thrown on to them for a single instant in each revolution. At length, after a great amount of labour, the efforts of the experimenters were crowned with success, a combination and arrangement of turbines and screw propellers being obtained which gave excellent results—results as good as the most optimistic of well-wishers had ever hoped for.

The solution of the difficulty was found in dividing up the power into three turbines driving three propeller-shafts. Each shaft carried three propellers of a special form. As the economic speed of a turbine depends on the difference of pressure of the entering and exhausting steam, it will be obvious that, by dividing the total range of pressure into three parts—that is, in expanding the steam only about one-third in each turbine—the minimum economic speed of each machine could be very much reduced—in fact, reduced to about one-half. The propeller-shafts could thus rotate at one-half the speed. In





PLATE VIII.—THE PIONEER OF MARINE STEAM TURBINE PROPULSION.



addition to this, the employment of so large a number of propellers—nine in all—allowed each to be of small size, and therefore allowed the tips of the blades to revolve in circles of small diameters. By thus reducing both the size and the angular velocity of the propellers, and giving them a suitable design, their efficiency was brought quite up to the normal. The result was that the *Turbinia* attained a speed—33 to 34 knots—never before reached by any vessel.

The length of the *Turbinia* is 100 feet and the beam 9 feet. The displacement is $44\frac{1}{2}$ tons, which if made up as follows:—

Main engines, 3 tons 13 cwts.

Total weight of machinery and boiler, screws

and shafting, tanks, etc.	22 tons
-------------------------------	-----	-----	---------

Weight of hull complete	15 „
-----------------------------	-----	-----	------

Coal and water	$7\frac{1}{2}$ „
--------------------	-----	-----	------------------

Total displacement	$44\frac{1}{2}$ „
------------------------	-----	-------------------

Steam is supplied by a water-tube boiler, and enters the first turbine cylinder at a pressure of 170 lbs. per square inch. The heating surface of the boiler is 1100 square feet, and the grate area 42 square feet. The stoke-holds are closed, and draught is furnished by a fan coupled directly to the engine-shaft. 4200 square feet of cooling surface are provided in the condenser. The fresh-water tank and hot well contain about 250 gallons of water. The auxiliary machinery consists of main air-pump and spare air-pump, auxiliary circulating pump, main and spare feed-pumps, main and spare oil-pumps, and bilge ejectors.

The engine cylinders lie close to the bottom of the boat, and are bolted directly to small seatings on the frames. The reaction of the propellers and the axial thrust of the steam on the

rotating parts of the turbine are arranged as far as possible to balance one another; but small-thrust bearings are provided in the turbine bearings to withstand any difference or error of balance. Lignum-vitæ bearings are used for the propeller-shafts. Astern motion is given to the vessel by means of a reversing turbine situated on the central shaft.

The hull of the boat is built of mild steel plates, varying in thickness from $\frac{3}{16}$ inch at the bottom to $\frac{1}{16}$ inch at the sides near the stern. Water-tight bulkheads divide the vessel into five compartments.

The success of the *Turbinia*, which was only built for experimental and demonstrative purposes, led to the formation under the same directorate of a larger company—the Parsons Marine Steam Turbine Co., Ltd.—and the construction of the ill-fated torpedo-boat destroyers, *Viper* and *Cobra*. Of these the first was built to the order of the British Admiralty, who subsequently purchased the other after completion.

The *Viper* was 210 feet long, 21 feet beam, and 12 feet 9 inches moulded depth, the hull being constructed with the standard Admiralty scantlings for 30-knot destroyers, and further strengthened in parts for the higher speeds contemplated. The displacement was 350 tons. There were four shafts and two propellers on each shaft, the after propeller on each shaft having a slightly greater pitch than the forward one. On each side of the vessel a high-pressure turbine drove the outer and a low-pressure turbine the inner shaft. The inner shaft on each side was also fitted with a reversing turbine, the two reversing turbines being capable of driving the vessel astern at a speed of 15 knots. Plate IX., reproduced by kind permission from *Engineering*, shows one set of turbines. The cylinder on the left is the high-pressure turbine, and the one




PLATE IX.—ONE SET OF ENGINES FOR H.M. TORPEDO-BOAT DESTROYER "VIPER" SUPPLIED BY THE PARSONS MARINE STEAM TURBINE COMPANY, LIMITED.

From "Engineering," by kind permission.

to the right on the other shaft is the low-pressure turbine, which receives the steam which exhausts from the high-pressure cylinder. The small cylinder at the back is the reversing turbine. The set of engines for the other side of the vessel was similar. Steam was supplied by four Yarrow boilers, having a total heating surface of 15,000 square feet, and a total grate area of $275\frac{3}{4}$ square feet. The thrust of the propellers was arranged to balance the thrust of the turbines. The fittings were constructed to satisfy Admiralty requirements, and were much the same as those of other destroyers. The diameter of each high-pressure cylinder was 35 inches, and of each low-pressure cylinder 50 inches. The weights of boilers and machinery are as follows:—

Boiler-room weights with water in boilers ...	120 tons
Engine-room weights with auxiliary gear	
and water in condensers	65 „
Propellers, shaftings, etc.	8 „
<hr/>	
Total	193 „

Although the contract for the whole vessel was given by the Admiralty to the Parsons Marine Steam Turbine Co., Ltd., that firm, while themselves making and fitting on board the engines, sublet the contract for the hull and boilers to Messrs. Hawthorne, Leslie and Co.

On her official steam trials under the direction of the Admiralty officials, the *Viper* easily attained a speed of 33·838 knots on a three-hours' run. At this speed, the consumption of coal was 11 tons 9 cwt. 1 qr. 9 lbs., or 25,685 lbs. per hour. On a three-hours' trial at 31·118 knots, the coal burned per hour was 19,846 lbs.

At a preliminary trial instituted by her contractors, the *Viper*, with a displacement of 380 tons, attained a mean speed on two runs with and against the tide of 36·849 knots. The mean speed for an hour's run alternately with and against the tide was 36·581 knots, the mean revolutions being 1180 per minute. The steam pressure during the six-hours' run ran up to 200 lbs., and the mean air-pressure in the stoke-holds was $4\frac{1}{2}$ inches. The speed was changed from 14 knots to 36·585 knots in twenty minutes.

The *Viper* was wrecked, it will be remembered, off Alderney in a fog, during the naval manœuvres in the summer of 1901.

The *Cobra* was built by Sir W. G. Armstrong, Whitworth and Co., Ltd., and engined by the Parsons Marine Steam Turbine Co., Ltd. This boat was slightly larger than the *Viper*, although of less beam (the small beam being noticeable in many war-vessels of Elswick design). The length was 223 feet 6 inches; beam, 20 feet 6 inches; draught, 6 feet; displacement, 400 tons. The *Cobra* foundered during a gale on September 18, 1901, while being taken from the Tyne to Portsmouth Dockyard to undergo trials by the Admiralty. She was not quite so fast a vessel as the *Viper*.

The first merchant steamer to be propelled by steam turbines is the *King Edward*, which commenced running in July, 1901. This vessel was built by Messrs. William Denny and Bros., of Dumbarton, and is engined with Parsons' turbines.

The dimensions of the vessel are as follows: length, 250 feet; beam, 30 feet; moulded depth, 10 feet 6 inches to the main deck, and 17 feet 9 inches to the promenade deck. Steam is supplied by a double-ended return-tube Scotch boiler of the usual marine type, having four furnaces at each end. There are three propeller-shafts, of which the two outer ones each

carry two propellers, the central shaft being provided with only one. A high-pressure turbine is situated on the central shaft, in which turbine the steam supplied at 150 lbs. is expanded about 5-fold, and then passes to two low-pressure turbines on the wing shafts, where it is expanded about 25-fold, the total expansion, therefore, being about 125-fold. Reversing is done by two turbines situated in the exhaust ends of the casings of the main low-pressure turbines. Steam can be supplied direct to the low-pressure cylinders, and the high-pressure turbine and its shaft cut out of use in order to obtain greater manœuvring power for negotiating piers. The weight of the motors, condensers with water in them, steam-pipes, auxiliaries connected with the propelling machinery, shafting, propellers, etc., is 66 tons, which is very much less for the power developed than the propelling machinery of reciprocating-engine, paddle-propelled passenger steamers of the same type.

The *King Edward* was employed for passenger traffic between Fairlie and Campbeltown in the summer of 1901, and gave great satisfaction. The turbines produce no vibration whatever, a slight vibration aft being due to the propellers.

In the trials of the *King Edward*, on June 26, 1901, on the Clyde, a mean speed of 20·48 knots was obtained on several runs over the measured mile at Skelmorlie. The mean revolutions at this trial were 740 per minute. The steam-pressure at the boilers was 150 lbs., and the vacuum $26\frac{1}{2}$ inches. The air-pressure in the stoke-hold was equal to $1\frac{1}{2}$ inches of water.

Figs. 139-142 illustrate a propeller-shaft support, recently patented by Messrs. Parsons and Wass, as applied to a vessel with a flat bottom upwardly inclined at the stern. Fig. 139 shows the support in end elevation, partly in section. Fig. 140 is a side elevation of part of the vessel with the support and

propeller-shafts. Fig. 141 is a section on a line below the part of the vessel shown in Fig. 140. The support consists of two Y-shaped brackets of elliptical section, as shown at *a*, Fig. 141. The approaching arms of the two brackets are connected by a boss, while each of the outside arms also carries a boss. These bosses are lined with lignum-vitæ or white metal. Each bracket carries a sole, *B*, which is placed in a socket, *C*, in a sole-plate, *D*, which is machined to receive it. The sole-plates are preferably formed of cast steel, and are permanently attached to




FIG. 139.—Propeller-shaft Support of Parsons and Wass : Sectional end elevation.

the framing *E* and plates *F* of the vessel, the plates being cut away to allow of the insertion of the soles. If the brackets are formed of aluminium bronze, manganese bronze, or gun-metal, strips *H* are provided round the soles to prevent corrosion. The end support for the central shaft is shown in Fig. 142. An arrangement of brackets for four propeller-shafts is shown in Fig. 143.

It will be seen that these propeller-shaft supports will offer very little resistance to passage through the water, and will be light and easily fitted correctly to the vessel.

Mr. Parsons states that he has found that the cavitation which attends high-speed propellers occurs principally in two places, namely, at the back faces of the blades near the tips, and

around the conical tip of the propeller-boss behind the blades. To obviate or lessen cavitation at the blade-tips, Mr. Parsons




FIG. 140.—Propeller-shaft Support of Parsons and Wass: Side elevation.




FIG. 141.—Propeller-shaft Support of Parsons and Wass: Sectional plan.

prefers to form the blades with diminishing pitch near the tips.

A device for diminishing cavitation round the conical end of the boss has been patented by Mr. Parsons, and is shown applied to a propeller in Fig. 144. Vanes v are fixed on the




FIG. 142.—Propeller-shaft Support of Parsons and Wass: Rear support of centre shaft.

conical end x , the vanes being parallel, or nearly so, to the axis of the shaft y . Fig. 145 is a cross-section through the cone and vanes. The water put into rotation by the propeller-blades




FIG. 143.—Support for Four Propeller Shafts.

closes in on the cone x , but tends to retain its velocity. It therefore rotates with a greater angular velocity than the cone. The vanes v are, therefore, considered to produce two beneficial results. Firstly, some of the kinetic energy of the rotating water is given up to the shaft which it helps to rotate; and

secondly, owing to the diminution of the velocity of the water rotating round the shaft, centrifugal force is reduced, and the




FIG. 144.—Parsons' Construction of Propeller Boss to diminish Cavitation.

water closes in more readily, and, pressing on the cone *x*, imparts an additional forward thrust to the shaft.

The steam turbine possesses several advantages over the




FIG. 145.—Cross-section of Boss.

reciprocating engine for marine propulsion. In the first place, there is the absence of vibration—an important point, both as regards comfort in passenger steamers and as regards accuracy

of gun-fire in naval vessels. Then there is a distinct saving in weight. This is not so marked in vessels of the destroyer type, where the engine-room weights are cut down to an abnormally small amount, as in larger vessels, and especially in the mercantile marine. This saving in weight can, of course, be used either in increasing the engine power, and consequently the speed, of the vessel, or in adding to its carrying capacity. The low situation of the engine-room weights in a turbine-propelled vessel also tends to improve the stability, and, in the case of a war-vessel, places the engines in a more protected position.

APPENDIX

BRITISH PATENTS FOR OR RELATING TO STEAM TURBINES FROM
THE EARLIEST RECORDS UP TO THE END OF 1899.

*When inventions have been communicated from abroad, the names of the
communicators are printed within parentheses.*

1784.		1836.	
1,426	. . Kempelen.	7,242	. . Perkins.
1,432	. . Watt.		
1791.		1837.	
1,812	. . Sadler.	7,305	. . Elkington.
1805.		1838.	
2,887	. . Miller.	7,554	. . Heath.
1809.		7,797	. . Burstall.
3,289	. . Noble.	7,854	. . James.
1815.		1840.	
3,922	. . Trevithick.	8,474	. . Williams.
1823.		8,572	. . Cordes and Locke.
4,793	. . Peel.	1841.	
1830.		9,116	. . Jones.
5,910	. . Grisenthwaite.	1842.	
5,961	. . Ericsson.	9,354	. . Pilbrow.
1831.		1843.	
6,120	. . Hobday.	9,658	. . Pilbrow.
1834.		9,902	. . Walther.
6,720	. . Craig.	1844.	
		10,189	. . McIntosh.

1845.
10,765 . . Meade.

1846.
11,044 . . Taylor.
11,352 . . Bessemer.

1847.
11,800 . . Von Rathen.

1848.
12,060 . . Wilson.
12,080 . . Exall.
12,217 . . Stenson.

1850.
13,245 . . Barclay.
13,281 . . Fernihough.

1851.
13,598 . . Andrews.

1852.
14,351 . . Gorman.
149 . . Wheel.
776 . . Presson.
1,083 . . Slate.

1853.
480 . . Nicholls.
735 . . Brown.
2,768 . . Sochet.

1854.
315 . . Tournay.
944 . . Danchell.
1,706 . . Tetley.

1855.
2,747 . . Poulson.

1857.
2,076 . . Ivory.
2,598 . . Lombard.
3,061 . . Parker.

1858.
144 . . J. and E. Harthan.

1859.
805 . . Ivory.
1,041 . . Taylor.

1860.
119 . . Rutchet, Vonwiller,
and Seiler.
1,155 . . Boyman.
2,317 . . Budden (Pilkington).

1861.
770 . . Chevillard.
2,457 . . Coffey.
2,953 . . Macintosh.

1862.
552 . . Parker.
1,568 . . Brakel, Hoehl, and
Gunther.
3,252 . . Braddock.
3,283 . . Budden (Pilkington).

1863.
1,160 . . Thomson.
2,355 . . Lloyd.
2,692 . . Verran.

1864.
502 . . Southam.
2,596 . . Newton.
2,779 . . Galloway.

1865.
949 . . Brookes (Perrigault,
Farcot, Farcot, Far-
cot, Château, and
Farcot).
2,130 . . Stevenson (Venzano).

1866.

- 891 . . Wenner.
 1,206 . . Newton (Farcot and
 Perrigault).
 1,822 . . Fraser.
 2,270 . . White (Sellier and
 Hermant).
 3,289 . . Newton (Harris).

1867.

- 646 . . Clark, W. (Lemley, G.
 W.).
 984 . . Moll, J. A.

1868.

- 784 . . Parker, J.
 883 . . Beech, T. S. L.
 1,732 . . Newton, W. E. (Boor-
 man, J. M.).
 2,320 . . Brooman, C. E. (Hie-
 lakker, J. V.).
 2,680 . . Hunter, J. M.
 3,146 . . Robertson, J.
 3,307 . . Meldrum, R.
 3,933 . . Lake, W. R. (de Ame-
 zaga, F.).

1869.

- 68 . . Legg, R.
 208 . . Cook and Watson.
 1,159 . . Brooman, C. E. (Go-
 guel, E. F. A.).
 1,748 . . Clark, A. M. (Lesnard,
 F.).
 2,476 . . Mayall, J. J. E.
 2,648 . . Muller, J. A.
 2,830 . . Walker, W., and
 Davies, D.
 3,267 . . Gorman, W.
 3,642 . . Outram, J.
 3,705 . . Bourne, J.

1870.

- 1,537 . . Astrop, W.
 1,904 . . Lake, W. R. (Smith,
 J. Y.).
 2,086 . . Scott, B. C.

1871.

- 1,736 . . Griffin, G. F.

1872.

- 2,188 . . Lake, W. R. (Harris,
 J.).
 3,134 . . Robertson, J.
 3,835 . . Cotter, R. H.

1873.

- 1,493 . . Burnett, W.
 3,161 . . Baldwin, T.

1874.

- 706 . . Teulon, A.
 3,961 . . Louche, J. H.

1875.

- 51 . . Turnock, J.
 67 . . Boyman, R. B.
 1,676 . . Newton, H. E. (Bab-
 bitt, B. T.).
 1,848 . . Clark, A. M. (de Ro-
 milly, H. F. L. W.).
 2,184 . . Preiswerk, L.
 4,324 . . Preiswerk, L.

1876.

- 1,224 . . Pope, A.
 1,549 . . Cotton, Sir A.
 2,368 . . Clark, A. M. (Dufort,
 J. H.).
 3,483 . . Apperly, J.
 3,841 . . Harris, J.

1877.

- 862 . . Apperly, J.
 2,434 . . Lake, W. R. (Averseng,
 M. A. T.).
 2,864 . . Smith, T. J. (Penning,
 G. A. de).

1878.

- 1,985 . . . Brydges, E. A. (Bazin, R.).
 4,293 . . . Apperly, J.
 4,596 . . . Lumley, H. R.
 4,628 . . . Mills, B. J. B. (Gfeller, J.).
 4,682 . . . Tuckey, T.

1879.

- 409 . . . Abel, C. D. (Binzer, J. von, and Bentzen, E.).
 2,673 . . . Davies, P.
 3,521 . . . Rigg, A.
 5,022 . . . Cutler, W. H.

1880.

- 17 . . . Jensen, P. (Hahn, E. J.).
 1,222 . . . Prowett, W.
 2,496 . . . Howson, J. T., and Tate, W.
 2,609 . . . Nedden, F. zur.
 3,522 . . . Temple, G.
 3,980 . . . Jensen, P. (Hahn, E. J.).
 4,160 . . . Lake, W. R. (Cole, J. W.).

1881.

- 177 . . . Imray, J.
 255 . . . Willet, T.
 369 . . . Temple, G.
 981 . . . Willet, T.
 2,857 . . . Leverkus, K. W. A.
 5,237 . . . Newton, H. E. (Desruelles, L. A. W., and Carlier, C. F.).

1882.

- 2,166 . . . Charlton, G., and Wright, J.

1883.

- 911 . . . Capell, G. M.
 1,655 . . . Engel, F. H. F. (Laval, G. de).
 4,245 . . . Johnson, J. H. (De-laurier, E. J.).
 5,233 . . . Lake, W. R. (Emmanuel, C.).

1884.

- 5,610 . . . De Laval, G.
 6,734 . . . Parsons, Hon. C. A.
 6,735 . . . Parsons, Hon. C. A.
 12,950 . . . Dumoulin, A. J. A.

1885.

- 1,174 . . . Johnson, J. H. (Howell, J. A., and Paine, F. H.).
 3,885 . . . Last, W. I.
 4,483 . . . Curtis, N. W.
 8,773 . . . Howson, J. T.

1886.

- 1,157 . . . Neil, W.
 5,647 . . . Thévenet, J.
 13,805 . . . Tongue, J. G. (Brunner, A.).
 13,949 . . . Whittle, W.
 16,020 . . . De Laval, G.

1887.

- 5,312 . . . Parsons, C. A.
 9,591 . . . Gwynne, J. E. A.
 12,488 . . . McConnell, J.

1888.

- 8,990 . . . Thompson, W. P. (Erwin, J. B.).
 9,158 . . . Morton, A.
 10,374 . . . Kranich, F.
 14,170 . . . Hodgeman, H. D.
 16,072 . . . Haddan, R. (Dow, J. H., and Dow, H. H.).
 17,299 . . . Morton, A.

1889.

1,862 . .	Curtis, N. W., and Carey, A. E.
4,302 . .	Phillips, W. H.
5,619 . .	Garside, A. A.
7,143 . .	Laval, C. G. P. de.
8,884 . .	West, J.
9,683 . .	Howden, J., and Hunt, E.
9,684 . .	Hunt, E.
12,509 . .	De Laval.
13,593 . .	Cousens, R. L. (Frost, W.).

1890.

291 . .	Rowe, R.
1,120 . .	Parsons, C. A.
2,050 . .	Haddan, H. J. (Dow, J. H.).
2,691 . .	Brown, J. W., and Sut- cliffe, W. W.
5,768 . .	Desgoffe, A., and Giorgio, L.
9,852 . .	Sharples, P. M., and Sharples, D. T.
11,615 . .	Moore, R. T.
14,994 . .	Parsons, C. A.
15,264 . .	Cot, J. P.
21,145 . .	Allison, H. J. (Jones, J. H.).

1891.

4,596 . .	Watkinson, W. H.
4,799 . .	Thompson, W. P. (Altham, G. J.).
5,074 . .	Parsons, C. A.
5,820 . .	Morton, A.
10,940 . .	Parsons, C. A.
20,449 . .	Laval, C. G. P. de.
20,603 . .	Laval, C. G. P. de.
21,376 . .	Mossop, J.

1892.

10,370 . .	Lake, H. H. (Altham, G. J.).
13,770 . .	Laval, C. G. P. de.
15,677 . .	Parsons, C. A.
19,723 . .	Justice, P. M. (Edwards, E. A., and Doughty, C. L.).
20,550 . .	Rothery, G. W.
22,428 . .	Scott, W. H.

1893.

2,720 . .	Seeger, E.
2,881 . .	Nelson, W., and Niven, J. J.
7,807 . .	Hutchinson, W. N.
8,357 . .	Haddan, R. (Dow, J. H.).
8,854 . .	Parsons, C. A.
15,703 . .	Robinson, M. H.
17,297 . .	Thompson, J. E., and Navard, E. J.
20,148 . .	Beaumont, W. W.
22,573 . .	Smith, I.
25,086 . .	Raworth, J. S.
25,090 . .	Raworth, J. S.

1894.

84 . .	Raworth, J. S.
367 . .	Parsons, C. A.
394 . .	Parsons, C. A.
1,242 . .	Raworth, J. S.
4,611 . .	Seeger, E.
6,248 . .	Wrench, W. G.
6,822 . .	Bollmann, L.
9,759 . .	Haddan, R. (Piguet and Co.).
10,458 . .	House, H. A., House, H. A., Symon, R. R.
11,526 . .	Redfern, C. F. (Norden- felt, P., and Chris- tophe, A.).
11,880 . .	Hopkins, G. M.

- | | | | |
|--------------|--|--------------|--|
| 17,273 . . . | Lake, W. R. (Consolidated Car Heating Co.). | 19,247 . . . | Mills, C. K. (Curtis, C. G.). |
| 18,130 . . . | Larr, A. F. S. van de. | 19,248 . . . | Mills, C. K. (Curtis, C. G.). |
| 18,745 . . . | Rateau, A. C. E. | 20,514 . . . | Jensen (Aktiebolaget de Lavals Angturbin). |
| 18,807 . . . | Vojacek, L. | 22,369 . . . | Mackintosh, J. |
| 1895. | | | |
| 2,565 . . . | Ferranti, S. J. de. | 26,612 . . . | Hug, D. |
| 3,506 . . . | Raworth, J. S. | 28,196 . . . | Fischer, A., and Held, A. |
| 11,709 . . . | Hewitt, J. T. | 1897. | |
| 16,476 . . . | Grauel, H. | 901 . . . | Parsons, C. A. |
| 19,978 . . . | Jönsson, J. L. | 2,123 . . . | Martindale, M. D. |
| 1896. | | | |
| 24 . . . | Buchmüller, C. | 2,595 . . . | Ringelmann, M. |
| 180 . . . | Bollmann, L., and Kohnberger, S. | 2,817 . . . | Weichelt, C. |
| 2,680 . . . | Benze, L., and Bachmayr, E. | 6,800 . . . | Martin, H. M. |
| 6,073 . . . | Cook, D. | 6,831 . . . | Heys, W. G. (Cazin, F. M.). |
| 6,419 . . . | Capel, H. C., and Clarkson, T. | 7,979 . . . | Martindale, M. D. |
| 7,250 . . . | Bousfield, J. E. (Soc. des Provedes Desgoffe et de Georges). | 9,340 . . . | Stone, J. H. |
| 7,455 . . . | Hewson, R., Whyte, N. C., and Rome, L. de. | 10,284 . . . | Philipp, O. |
| 8,697 . . . | Parsons, C. A. | 10,609 . . . | Fiedler, L. R. |
| 8,698 . . . | Parsons, C. A. | 11,223 . . . | Parsons, C. A. |
| 8,832 . . . | House, H. A., and Symon, R. R. | 11,328 . . . | Hickson, E. (Hickson, S. A. E.). |
| 11,086 . . . | Parsons, C. A. | 12,529 . . . | Johnson, J. Y. (Sharples, P. M.). |
| 11,351 . . . | Hayward, W. | 14,885 . . . | McAllister, J. |
| 12,060 . . . | Lacavalerie, S. | 15,069 . . . | Hakansson, L. M. |
| 12,589 . . . | McAllister, J. | 15,983 . . . | Ulenhuth, E. |
| 15,502 . . . | Davidson, S. C. | 16,635 . . . | Lohmann, C. F. C. |
| 15,832 . . . | Dugard, W. H. | 17,842 . . . | Marconnet, G. A. |
| 16,079 . . . | Dominy, G., and Sturme, J. H. | 19,673 . . . | Hayot, L. |
| 17,136 . . . | Trossin, O. | 20,536 . . . | Mills, C. K. (Curtis, C. G.). |
| 17,481 . . . | Schmidt, J. | 22,226 . . . | Seger, E. |
| 18,377 . . . | Ramstedt, C. W. | 22,431 . . . | Senior, T. E. |
| 19,246 . . . | Mills, C. K. (Curtis, C. G.). | 22,842 . . . | Seger, E. |
| | | 23,832 . . . | Huggins, W., and McCallum, D. |
| | | 24,113 . . . | Grubinski, F. von. |
| | | 26,553 . . . | Parsons, C. A. |
| | | 26,650 . . . | Jourdanet, A., and Gauthier, J. P. |

- 26,669 . . Gray, T. M., and Bass,
F.
28,812 . . Boyd, F. A.
28,821 . . Thompson, W. P.
(Irgens, P., and
Brunn, G. M.).
29,508 . . Huber, C.
29,637 . . Scott, J.

1898.

- 3,068 . . Miles, R.
3,455 . . Clarke, W. H., and
Warburton, F. J.
4,102 . . Stuart, H. A.
4,714 . . Addington, A. M.
4,922 . . Thorssin, J.
4,932 . . Stone, J. H.
7,398 . . Stolze, F.
7,580 . . Groterjam, C.
8,588 . . Stone, J. H.
9,024 . . Clarke, W. H., and
Warburton, F. J.
9,044 . . Paige, J. W., and
Dixon, T. S. E.
9,220 . . Yates, J., and Bellis,
T. K.
10,503 . . Schulz, R.
11,055 . . Schulz, R.
11,159 . . Canning, A. H.
11,668 . . Petersson, F. O., and
Franc, C.
17,271 . . Johnson, C. M.
19,025 . . Thompson, W. P.
(Prall, W. E.).
19,256 . . Bök, N. S.
19,350 . . Montag, G., Hüter, F.,
and Karb, M.
19,392 . . Bäckström, C. A.
19,394 . . Lohmann, C. F. C.
20,099 . . McCollum, J. H. K.
21,079 . . Vandel, X. C. L. G.
21,478 . . Davidson, S. C.
21,698 . . Heys, W. G. (Heil-
mann, J. J.).

- 21,836 . . House, I. M., and
Overend, W. J.
24,084 . . Prall, W. E.
24,204 . . Pitt, S. (Rateau, A. C. E.,
and Sautter, Harlé,
and Co.).
24,845 . . Coard, J. B. M. A., and
Charpentier, E. A.
26,721 . . Bailly, P.
26,767 . . Thrupp, E. C.
26,801 . . Edge, H. T.

1899.

- 195 . . Schroetter, J. F.
1,031 . . Weihe, C. L.
1,149 . . Gommerat, J. F., and
Gommerat, L.
3,138 . . Niepmann, F.
4,242 . . Vijgh, G. van der.
4,638 . . Enoch, A. G., and
Enoch, D.
5,881 . . Parsons, C. A.
6,768 . . Baker, R. E., Dixon,
T. H., Coghlan, J. B.,
Foley, E., Coleman,
T., Dennehy, P. R.,
O'Brien, J., Crotty.
J., Russell, E. B.,
Noonan, J., Mouris-
sey, W., and O'Con-
nell, M.
7,183 . . Thompson, W. P.
(Brady, J. F.).
9,119 . . Jackson, J.
9,629 . . Betscher, G.
10,296 . . Lount, S.
10,980 . . Billardon, A. L.
11,179 . . Burgum, J.
11,433 . . Haddan, R. (Rahmer,
P.).
11,557 . . Weichelt, C.
11,563 . . Bruder, P.
14,476 . . Parsons, C. A.
14,915 . . Parsons, C. A., and
Carnegie, A. Q.
15,724 . . Spence, J.

15,954 . .	Richards, R. S.	18,979 . .	Zoelly, H.
16,284 . .	Parsons, C. A., Stoney, G. G., and Fullagar, H. F.	19,839 . .	Ferretti, E.
17,721 . .	Nivert, E.	21,341 . .	Thompson, W. P. (Brady, J. F.).
17,826 . .	Paine, H. D., and Paine, E. G.	22,634 . .	Taylor, C. H.
		23,759 . .	Nilsson, N.



INDEX

A

ABEL, C. D., 152
Absolute velocity defined, 57
Abstraction of heat at constant volume, 85
Addington, A. M., 155
Advantages of steam turbine for marine propulsion, 147, 148
Air-propeller driven by steam turbine, 19, 20, 102, 103, 125, Plate VII., 139
Aktiebolaget de Lavals Angturbin, 102, 154
Allison, H. J., 153
Alternators, effect of high rotary speed on, 55, 56, 137
Altham, G. J., 153
Amezaga, F. de, 151
Andrews, 150
Apperly, J., 151, 152
Armstrong, Whitworth and Co., Ltd., 142
Astrop, W., 151
Averseng, M. A. T., 151
Axial-flow turbine defined, 2
Axial pressure, Morton's device for balancing, 35
— thrust of turbine spindle, taking up or balancing, 39, 46, 90, 91

B

BABBITT, B. T., 151
Bachmayr, E., 154
Bäckström, C. A., 155
Bailly, P., 155
Baker, R. E., 155
Balancing axial pressure, Morton's device for, 35

Balancing axial thrust of turbine spindle, 39, 46, 90, 91
Baldwin, T., 30, 151
Barclay, 150
Bass, F., 155
Bazin, R., 152
Beaumont, W. W., 153
Beech, T. S. L., 151
Bellis, T. K., 155
Bentzen, E., 152
Benze, L., 154
Bessemer, 150
Betscher, G., 155
Billardon, A. L., 155
Binzer, J. von, 152
Blades of De Laval turbine, 2, 3, 94-96
— of Parsons turbine, 3-6, 48, 49, 68, 120, 121
— of single-disc Rateau turbine, 113
Bök, N. S., 155
Bollmann, L., 153, 154
Boorman, J. M., 151
Bourne, J., 151
Bousfield, J. E., 154
Boyd, F. A., 154
Boyman, 150, 151
—, R. B., 151
Braddock, 150
Brady, J. F., 155, 156
Brakel, 150
Branca, 7
Brookes, 150
Brooman, C. E., 151
Brown, 150, 153
—, J. W., 153
Bruder, P., 155
Brunn, G. M., 155
Brunner, A., 152
Brydges, E. A., 152
Buchmüller, C., 154

Budden, 150
 Burgum, J., 155
 Burnett, W., 151
 Burstall, 149

C

CAMBRIDGE Electric Supply Co., 42,
 127-129
 Canning, A. H., 155
 Capel, H. C., 154
 Capell, G. M., 152
 Carey, A. E., 153
 Carlier, C. F., 152
 Carnegie, A. Q., 155
 Cavitation, 137-139, 144-147
 Cazin, F. M., 154
 Centrifugal force, effect of, 64, 65, 107,
 113, 137, 146, 147
 — governors, 96-98, 123, 125, 133, 134
 — pumps driven by steam turbines,
 100-103, 125, Plate VI.
 Characteristic feature of De Laval
 turbine, 98
 Charlton, G., 152
 Charpentier, E. A., 155
 Château, 150
 Chevillard, 150
 Christophe, A., 153
 Clark, A. M., 151
 —, W., 151
 Clarke, W. H., 155
 Clarkson, T., 154
 Classification of turbines, 2
 Clearance around turbine wheel in De
 Laval turbine, 99
 — between blades in Parsons turbine,
 5
 Coard, J. B. M. A., 155
 Coffey, 150
 Coghlan, J. B., 155
 Cole, J. W., 152
 Coleman, T., 155
 Combined turbine and air-propeller,
 19, 20
 — and condenser, 116-118
 Compensating for want of balance in
 rotating mass, 91-93
 Condenser combined with turbine,
 116-118

Condenser vacuum, effect on efficiency,
 54, 55, 115, 116
 Condensing steam turbine, first
 Parsons, 42
 Consolidated Car Heating Co., 154
 Cook, 151, 154
 —, D., 154
 Cordes, 149
 Cot, J. P., 153
 Cotter, R. H., 151
 Cotton, Sir A., 151
 Cousens, R. L., 153
 Craig, 149
 Crotty, J., 155
 Curtis, C. G., 154
 —, N. W., 152, 153
 Cutler, W. H., 152

D

DANCHELL, 150
 Davidson, S. C., 154, 155
 Davies, D., 151
 —, P., 152
 Delaurier, E. J., 152
 De Laval, 2, 3, Chap. VIII., 106, 107,
 109, 152, 153
 Dennehy, P. R., 155
 Desgoffe, A., 153
 — et de Georges, Soc. des Provedes,
 154
 Desruelles, L. A. W., 152
 Distributing blades or passages of
 Rateau turbine, 110-112
 Divergent nozzles for discharge of
 steam, 2, 3, 22-24, 31, 63, 91, 93-96,
 98
 Dixon, T. H., 155
 —, T. S. E., 155
 Dominy, G., 154
 Double-ended Parsons turbine, 38-42
 Doughty, C. L., 153
 Dow, H. H., 152
 —, J. H., 152, 153
 Dryness fraction of steam, 74, 85
 Dufort, J. H., 151
 Dugard, W. H., 154
 Dumoulin, A. J. A., 152

E

- EDGE, H. T., 155
 Eduction nozzle from turbine casing, divergent, 93
 — nozzles, 7-9, 14, 22-24, 33, 34, 93
 Edwards, E. A., 153
 Efficiency of simple turbine limited by strength and weight of materials, 65
 — of steam turbine, greatest possible, 51
 Ejector for removing leaking steam, 40
 Elastic bearing for turbine spindle, 48, 91-93
 Elberfeld, 130-136
 Electrical governors, 135, 136
 Elkington, 149
 Emmanuel, C., 152
 End thrust of turbine spindle, taking up, 39, 46, 90, 91
 Engel, F. H. F., 152
 Enoch, A. G. and D., 155
 Entropy, Chaps. VI. and VII.
 Ericsson, 16, 17, 149
 Erwin, J. B., 152
 Exall, 150
 Expansion of steam in nozzle of De Laval turbine, 91, 98, 99

F

- FANS or blowers driven by steam turbines, 102, 103, 125, Plate VII., 139
 Farcot, 150, 151
 Fernihough, 29, 150
 Ferranti, S. Z. de, 154
 Ferretti, E., 156
 Fiedler, L. R., 154
 Fischer, A., 154
 Flexible shaft, 91
 — support for turbine, 40, 45, 46, 91, 92, 93, 114
 Foley, E., 155
 Franc, C., 155
 Fraser, 151
 Friction gearing for reducing speed of steam turbine, 22, 31-33, 90, 91
 — in steam turbine, losses due to, 51, 53, 88

- Frost, W., 153
 Fullagar, H. F., 156

G

- GALLOWAY, 150
 Garside, A. A., 153
 Gauthier, J. P., 154
 Gearing for Rateau turbine, 114
 Gear wheels of De Laval turbine, 94-96
 Georges, Soc. des Provedes Desgoffe et de, 154
 Gfeller, J., 152
 Giorgio, L., 153
 Goguel, E. F. A., 151
 Gommerat, J. F. and L., 155
 Gorman, 150, 151
 Governors, 96-98, 121-125, 131-136
 Grauel, H., 154
 Gray, T. M., 155
 Griffin, G. F., 151
 Grisenthwaite, 149
 Groterjam, C., 155
 Grubinski, F. von, 154
 Gunther, 150
 Gwynne, J. E. A., 152

H

- HADDAN, H. J., 153
 —, R., 152, 153, 155
 Hahn, E. J., 152
 Hakansson, L. M., 154
 Harris, 151
 —, J., 151
 Harthan, J. and E., 150
 Hayot, L., 154
 Hayward, W., 154
 Heath, 149
 Heilmann, J. J., 155
 Held, A., 154
 Helical vanes and grooves, 36, 37
 Helicoidal gearing, 30, 94-96, 114
 Hermant, 151
 Hero, 2
 Hewitt, J. T., 36, 37, 154
 Hewson, R., 154
 Heys, W. G., 154, 155
 Hickson, E., 154

Hickson, S. A. E., 154
 Hielakker, J. V., 151
 Hobday, 149
 Hodgemann, H. D., 152
 Hoehl, 150
 Hopkins, G. M., 153
 House, H. A., 153, 154
 —, I. M., 155
 Howden, J., 153
 Howell, J. A., 152
 Howson, J. T., 152
 Huber, C., 154
 Hug, D., 154
 Huggins, W., 154
 Hunt, E., 153
 Hunter, J. M., 151
 Hutchinson, W. N., 153
 Hüter, F., 155
 Hydraulic turbine compared with
 steam turbine, 50, 51

I

IMRAY, J., 152
 Induction nozzles, 2, 3, 16-21, 25, 26,
 31, 34, 91, 96, 113
 Irgens, P., 155
 Ivory, 150

J

JACKSON, J., 155
 James, 149
 Jensen, P., 152, 154
 Johnson, C. M., 155
 —, J. H., 152
 —, J. Y., 154
 Jones, 149, 152, 153
 —, J. H., 152, 153
 Jönsson, J. L., 154
 Joule's experiment, 83
 Jourdanet, A., 154
 Justice, P. M., 153

K

KABB, M., 155
 Kempelen, 8-10, 149
King Edward, steamer, 142, 143
 Kircher, 8
 Kohnberger, S., 154
 Kranich, F., 152

L

LACAVALERIE, S., 154
 Lake, H. H., 153
 —, W. R., 151, 152, 154
 Land locomotion, Pilbrow's proposal
 to use steam turbine for, 20
 Larr, A. F. S. van de, 154
 Last, W. I., 152
 Laval, C. G. P. de, 2, 3, Chap. VIII.,
 106-109, 152, 153
 Legg, R., 151
 Lemley, G. W., 151
 Lesnard, F., 151
 Leverkus, K. W. A., 152
 Limiting velocity of turbine wheel,
 64, 65, 113
 Lloyd, 150
 Locke, 149
 Lohmann, C. F. C., 154, 155
 Lombard, 150
 Louche, J. H., 151
 Lount, S., 155
 Lubricant, none required in steam
 turbine, 54
 Lumley, H. R., 152

M

McALLISTER, J., 154
 M'Callum, D., 154
 McCollum, J. H. K., 155
 McConnell, J., 152
 McIntosh, 149
 Macintosh, 150
 Mackintosh, J., 154
 Marconnet, G. A., 154
 Marine Steam Turbine Co., 137
 Martin, H. M., 154
 Martindale, M. D., 154
 Maschinenfabrik Oerlikon, 107, 109
 Mayall, J. J. E., 151
 Meade, 150
 Meldrum, R., 151
 Metropolitan Electric Supply Co., 125,
 Plate IV.
 Miles, R., 155
 Miller, 149
 Mills, B. J. B., 152
 —, C. K., 154
 Mixed-flow turbine defined, 2

Mixing products of combustion with steam to drive turbine, 29
 — steam with heavier fluid to drive turbine, 69
 Moll, J. A., 151
 Montag, G., 155
 Moore, R. T., 153
 Morton, A., 33, 36, 152, 153
 Mossop, J., 153
 Mourissey, W., 155
 Muller, J. A., 151
 Multiple expansion, 20-22, 24-30, 33-36, 65-69, Chaps. III., IX., X.
 Multiple-expansion turbine without guides, Morton's, 33

N

NAVARD, E. J., 153
 Nedden, F. zur, 152
 Neil, W., 152
 Nelson, W., 153
 Newton, 150-152
 —, H. E., 151, 152
 —, W. E., 151
 Nicholls, 150
 Niepmann, F., 155
 Nilsson, N., 156
 Niven, J. J., 153
 Nivert, E., 156
 Noble, 14, 15, 149
 Noonan, J., 155
 Nordenfelt, P., 153
 Nozzles, education, 7-9, 14, 22-24, 33, 34, 93, 94
 — for steam jets, Pilbrow's experiments on, 18
 —, induction, 2, 3, 16-21, 25, 26, 31, 34, 91, 95, 96, 113

O

O'BRIEN, J., 155
 O'Connell, M., 155
 Oil filter not required with steam turbine, 54
 Outram, J., 151
 Outward-flow turbine defined, 2
 Overend, W. J., 155

P

PACKING for spindle, 23, 41, 42, 113, 114
 Paige, J. W., 155
 Paine, H. D. and E. G., 156
 —, F. H., 152
 Parallel-flow turbine defined, 2
 — —, description of Parsons, 47, 48
 Parker, 150, 151
 —, J., 151
 Parsons, Hon. C. A., 3-6, 53, 55, 68, 88, 143-147, 152-156, Chaps. III., X., XI.
 —, C. A., and Co., 42, 89, 107, 116, 121, 125, Chap. XI.
 — Marine Steam Turbine Co. Ltd., 140-142
 Peel, 149
 Penning, G. A. de, 151
 Perkins, 17, 149
 Perrigault, 150, 151
 Petersson, F. O., 155
 Philipp, O., 154
 Phillips, W. H., 153
 Piguët and Co., 153
 Pilbrow, 18-22, 149
 Pilkington, 150
 Pitt, S., 155
 Pope, A., 151
 Poulson, 150
 Prall, W. E., 155
 Preiswerk, L., 151
 Presson, 150
 Propeller, balancing thrust of, 112, 139-141
 — boss, patent, 146, 147
 Propellers, cavitation, 137-139, 144-147
 — of *King Edward*, 142, 143
 — of *Turbinia*, 138, 139
 — of *Viper*, 140
 —, pitch of, 140, 145
 Propeller-shaft support, 143-146
 Prowett, W., 152
 Pumps, centrifugal, driven by steam turbines, 100-103, 125, Plate VI.

R

RADIAL-FLOW steam turbine, description of Parsons, 5, 6, 41, 42

M

- Radial-flow turbine defined, 2
 Rahmer, P., 155
 Ramstedt, C. W., 154
 Rateau, A. C. E., 154, 155, Chap. IX.
 Rathen, von, 22-24, 150
 Raworth, J. S., 31-33, 153, 154
 Reciprocating engine compared with
 steam turbine, 51-56
 Refern, C. F., 153
 Relative velocity defined, 57
 Reversing steam turbines, 19, 23, 24,
 112, 118-121
 Richards, R. S., 156
 Rigg, A., 152
 Ringelmann, M., 154
 Robertson, J., 151
 Robinson, M. H., 153
 Rome, L. de, 154
 Romilly, H. F. L. W. de, 151
 Rotary speed limited by strength and
 weight of materials, 64, 65, 107, 113
 Rothery, G. W., 153
 Rowe, R., 153
 Russell, E. B., 155
 Rutchet, 150
- S
- SADLER, 12-14, 149
 Sautter, Harlé and Co., 107, 109, 113,
 155
 Schmidt, J., 154
 Schroetter, J. F., 155
 Schulz, R., 155
 Scott, B. C., 151
 —, J., 155
 —, W. H., 153
 Screw turbine, 36, 37
 Seger, E., 153, 154
 Seiler, 150
 Sellier, 151
 Senior, T. E., 154
 Sharples, D. T., 153
 —, P. M., 153, 154
 Slate, 150
 Smith, I., 153
 —, J. Y., 151
 —, T. J., 151
 Sochet, 150
 Société de Laval, 94-104
 Sosnowski, paper by, 37
 Southam, 150
 Specific heat of steam, 80, 81
 Speed of rotation limited by strength
 and weight of materials, 64, 65,
 107, 113
 — — — of De Laval turbine, 96, 99,
 100
 Spence, J., 155
 Steam jet, 1 Pilbrow's experiments on
 impulsive force of, 18
 Steam-tight packing for shaft, 23, 41,
 42, 113, 114
 Stenson, 150
 Stevenson, 150
 Stolze, F., 155
 Stone, J. H., 154, 155
 Stoney, G. G., 156
 Strength of wheel or ring or disc to
 resist centrifugal force, 64, 65, 107,
 113
 Stuart, H. A., 155
 Sturme, J. H., 154
 Successive expansion of steam in
 turbine, 20-22, 24-30, 33-36, 65-69,
 Chaps. III., IX., X.
 Superheated steam for steam turbine,
 effect on efficiency, 53, 54, 88, 89,
 127
 Sutcliffe, W. W., 153
 Symon, R. R., 153, 154
- T
- TATE, W., 152
 Taylor, 150, 156
 —, C. H., 156
 Temple, G., 152
 Tests of De Laval turbines, 102, 104,
 105
 — of Parsons turbines, 89, 115, 116,
 Chap. XI.
 Tetley, 150
 Tenlon, A., 30, 31, 151
 Theta-phi diagrams, Chaps. VI., VII.
 Thévenet, J., 152
 Thompson, J. E., 153
 —, W. P., 152, 153, 155, 156
 Thomson, 150
 Thorssin, J., 155

Throttle valve, 98, 121-123
 Thrupp, E. C., 155
 Tongue, J. G., 152
 Tournaire, 29
 Tourney, 150
 Trevithick, 15, 16, 149
 Trossin, O., 154
 Tuckey, T., 152
 Turbine, definition of, 1
 Turbines, classification of, 2
Turbinia, 137-140, Plate VIII.
 Turnock, J., 151

U

ULENHUTH, E., 154
 Unresisted expansion, 83, 84

V

VACUUM in condenser, effect of, on
 efficiency, 51, 52, 115, 116, 126
 Vandel, X. C. L. G., 155
 Vanes of De Laval turbine, 2, 3, 94-
 96
 — of Parsons turbine, 3-6, 48, 49,
 68, 120, 121
 — of Rateau single-disc turbine,
 113
 Velocity of steam in steam turbine,
 50, 51
 — of vanes, Pilbrow's calculations
 on, 18
 Venzano, 150
 Verran, 150
 Victorian Railways Lighting Station,
 125, Plate V.
 Vijgh, G. van der, 155
Viper, torpedo-boat destroyer, 140-142
 Vojacek, L., 154
 Volume of steam at different pressures,
 50, 52

Von Rathen, 22-24, 150
 Vonwiller, 150

W

WALKER, W., 151
 Walther, 149
 Warburton, F. J., 155
 Wass, 143-146
 Water-packing for turbine spindle, 41,
 42
 Watkinson, W. H., 153
 Watson, 151
 Watt, 10, 149
 Weichelt, C., 154, 155
 Weights of De Laval turbines, 99
 — of marine steam turbines, 139, 141,
 143, 148
 Weihe, C. L., 155
 Wenner, 151
 West, J., 153
 Wheel, 150
 White, 151
 Whittle, W., 152
 Whyte, N. C., 154
 Willet, T., 152
 Williams, 149
 Wilson, 24, 150
 Wrench, W. G., 153
 Wright, J., 152

Y

YATES, J., 155
 Yielding bearing for Parsons turbine,
 40, 45, 46
 — — for Rateau turbine, 114

Z

ZOELLY, H., 156

THE END



A SELECT LIST OF BOOKS

IN

NATURAL AND PHYSICAL SCIENCE, MATHEMATICS AND TECHNOLOGY

PUBLISHED BY
MESSRS. LONGMANS, GREEN, & CO.

LONDON: 39 PATERNOSTER ROW, E.C.

NEW YORK: 91 & 93 FIFTH AVENUE.

BOMBAY: 32 HORNBY ROAD.

	PAGE		PAGE
<i>ADVANCED SCIENCE MANUALS</i>	- 38	MEDICINE AND SURGERY	- 25
ALGEBRA - - - -	- 9	MENSURATION - - - -	- 8
AGRICULTURE - - - -	- 35	METALLURGY - - - -	- 19
ARCHITECTURE - - - -	- 14	MINERALOGY - - - -	- 19
ASTRONOMY - - - -	- 20	MINING - - - -	- 19
BACTERIOLOGY - - - -	- 33	NATURAL HISTORY AND GENERAL	
BIOLOGY - - - -	- 32	SCIENCE - - - -	- 23
BOTANY - - - -	- 34	NAVAL ARCHITECTURE - - - -	- 19
BUILDING CONSTRUCTION - - - -	- 14	NAVIGATION - - - -	- 20
CALCULUS - - - -	- 10	OPTICS - - - -	- 12
CHEMISTRY - - - -	- 2	PHOTOGRAPHY - - - -	- 12
CONIC SECTIONS - - - -	- 9	PHYSICS - - - -	- 5
DYNAMICS - - - -	- 6	PHYSIOGRAPHY - - - -	- 22
ELECTRICITY - - - -	- 15	PHYSIOLOGY - - - -	- 32
<i>ELEMENTARY SCIENCE MANUALS</i>	- 38	<i>PRACTICAL ELEMENTARY SCIENCE</i>	
ENGINEERING - - - -	- 17	SERIES - - - -	- 40
EUCLID - - - -	- 10	<i>PROCTOR'S (R. A.) WORKS</i>	- 21
GARDENING - - - -	- 35	SOUND - - - -	- 13
GEOLOGY - - - -	- 22	STATICS - - - -	- 6
GEOMETRY - - - -	- 10	STEAM, OIL, AND GAS ENGINES	- 13
HEALTH AND HYGIENE - - - -	- 24	STRENGTH OF MATERIALS - - - -	- 17
HEAT - - - -	- 13	SURVEYING - - - -	- 8
HYDROSTATICS - - - -	- 6	TECHNOLOGY - - - -	- 23
LIGHT - - - -	- 13	TELEGRAPHY - - - -	- 16
LOGARITHMS - - - -	- 10	TELEPHONE - - - -	- 16
<i>LONDON SCIENCE CLASS-BOOKS</i>	- 40	<i>TEXT-BOOKS OF SCIENCE</i>	- 37
<i>LONGMANS' CIVIL ENGINEERING</i>		THERMODYNAMICS - - - -	- 13
SERIES - - - -	- 18	TRIGONOMETRY - - - -	- 12
MACHINE DRAWING AND DESIGN - - - -	- 18	<i>TYNDALL'S (JOHN) WORKS</i>	- 36
MAGNETISM - - - -	- 15	VETERINARY MEDICINE, ETC.	- 31
MANUFACTURES - - - -	- 23	WORKSHOP APPLIANCES - - - -	- 19
MECHANICS - - - -	- 6	ZOOLOGY - - - -	- 32

CHEMISTRY.

ARRHENIUS.—A TEXT-BOOK OF ELECTROCHEMISTRY. By SVANTE ARRHENIUS, Professor at the University of Stockholm. Translated from the German Edition by JOHN MCCRAE, Ph.D. With 58 Illustrations. 8vo., 9s. 6d. net.

CROOKES.—SELECT METHODS IN CHEMICAL ANALYSIS, chiefly Inorganic. By Sir WILLIAM CROOKES, F.R.S., etc. Third Edition, Rewritten and Enlarged. With 67 Woodcuts. 8vo., 21s. net.

FURNEAUX.—ELEMENTARY CHEMISTRY, Inorganic and Organic. By W. FURNEAUX, F.R.G.S., Lecturer on Chemistry, London School Board. With 65 Illustrations and 155 Experiments. Crown 8vo., 2s. 6d.

GARRETT AND HARDEN.—AN ELEMENTARY COURSE OF PRACTICAL ORGANIC CHEMISTRY. By F. C. GARRETT, M.Sc. (Vict. et Dunelm.), Assistant Lecturer and Demonstrator in Chemistry, the Durham College of Science, Newcastle-on-Tyne; and ARTHUR HARDEN, M.Sc. (Vict.), Ph.D., Assistant Lecturer and Demonstrator in Chemistry, the Owens College, Manchester. With 14 Illustrations. Crown 8vo., 2s.

JAGO.—Works by W. JAGO, F.C.S., F.I.C.

INORGANIC CHEMISTRY, THEORETICAL AND PRACTICAL. With an Introduction to the Principles of Chemical Analysis, Inorganic and Organic. With 63 Woodcuts and numerous Questions and Exercises. Fcp. 8vo., 2s. 6d.

AN INTRODUCTION TO PRACTICAL INORGANIC CHEMISTRY. Crown 8vo., 1s. 6d.

INORGANIC CHEMISTRY, THEORETICAL AND PRACTICAL. A Manual for Students in Advanced Classes of the Science and Art Department. With Plate of Spectra and 78 Woodcuts. Crown 8vo., 4s. 6d.

MELLOR.—HIGHER MATHEMATICS FOR STUDENTS OF CHEMISTRY AND PHYSICS. With Special Reference to Practical Work. By J. W. MELLOR, D.Sc., late Senior Scholar, and 1851 Exhibition Scholar, New Zealand University; Research Fellow, the Owens College, Manchester. With 142 Diagrams. 8vo., 12s. 6d. net.

MENDELÉEFF.—THE PRINCIPLES OF CHEMISTRY. By D. MENDELÉEFF. Translated from the Russian (Sixth Edition) by GEORGE KAMENSKY, A.R.S.M., of the Imperial Mint, St. Petersburg; and Edited by T. A. LAWSON, B.Sc., Ph.D., Fellow of the Institute of Chemistry. With 96 Diagrams and Illustrations. 2 vols. 8vo., 36s.

MEYER.—OUTLINES OF THEORETICAL CHEMISTRY. By LOTHAR MEYER, Professor of Chemistry in the University of Tübingen. Translated by Professors P. PHILLIPS BEDSON, D.Sc., and W. CARLETON WILLIAMS, B.Sc. 8vo., 9s.

MILLER.—INTRODUCTION TO THE STUDY OF INORGANIC CHEMISTRY. By W. ALLEN MILLER, M.D., LL.D. With 71 Illustrations. Fcp. 8vo., 3s. 6d.

CHEMISTRY—Continued.

MUIR.—A COURSE OF PRACTICAL CHEMISTRY. By M. M. P. MUIR, M.A., Fellow and Prælector in Chemistry of Gonville and Caius College, Cambridge. (3 Parts.)

Part I. Elementary. Crown 8vo., 4s. 6d.

Part II. Intermediate. Crown 8vo., 4s. 6d.

Part III. [In preparation.]

NEWTN.—Works by G. S. NEWTH, F.I.C. F.C.S., Demonstrator in the Royal College of Science, London.

CHEMICAL LECTURE EXPERIMENTS. With 230 Illustrations. Crown 8vo., 6s.

CHEMICAL ANALYSIS, QUANTITATIVE AND QUALITATIVE. With 100 Illustrations. Crown 8vo., 6s. 6d.

A TEXT-BOOK OF INORGANIC CHEMISTRY. With 155 Illustrations. Crown 8vo., 6s. 6d.

ELEMENTARY PRACTICAL CHEMISTRY. With 108 Illustrations and 254 Experiments. Crown 8vo., 2s. 6d.

OSTWALD.—SOLUTIONS. By W. OSTWALD, Professor of Chemistry in the University of Leipzig. Being the Fourth Book, with some additions, of the Second Edition of Oswald's 'Lehrbuch der allgemeinen Chemie'. Translated by M. M. PATTISON MUIR, Fellow and Prælector in Chemistry of Gonville and Caius College, Cambridge. 8vo., 10s. 6d.

PERKIN.—QUALITATIVE CHEMICAL ANALYSIS (ORGANIC AND INORGANIC). By F. MOLLWO PERKIN, Ph.D., Head of the Chemistry Department, Borough Polytechnic Institute, London. With 9 Illustrations and Spectrum Plate. 8vo., 3s. 6d.

REYNOLDS.—EXPERIMENTAL CHEMISTRY FOR JUNIOR STUDENTS. By J. EMERSON REYNOLDS, M.D., F.R.S., Professor of Chemistry, University of Dublin. Fcp. 8vo., with numerous Woodcuts.

Part I. Introductory. Fcp. 8vo., 1s. 6d.

Part II. Non-Metals, with an Appendix on Systematic Testing for Acids. Fcp. 8vo., 2s. 6d.

Part III. Metals, and Allied Bodies. Fcp. 8vo., 3s. 6d.

Part IV. Carbon Compounds. Fcp. 8vo., 4s.

SHENSTONE.—Works by W. A. SHENSTONE, F.R.S., Lecturer on Chemistry in Clifton College.

THE METHODS OF GLASS-BLOWING AND OF WORKING SILICA IN THE OXY-GAS FLAME. For the Use of Physical and Chemical Students. With 43 Illustrations. Crown 8vo., 2s. 6d.

A PRACTICAL INTRODUCTION TO CHEMISTRY. Intended to give a Practical acquaintance with the Elementary Facts and Principles of Chemistry. With 25 Illustrations. Crown 8vo., 2s.

CHEMISTRY—Continued.

SMITH AND HALL.—THE TEACHING OF CHEMISTRY AND PHYSICS IN THE SECONDARY SCHOOL. By ALEXANDER SMITH, B.Sc., Ph.D., Associate Professor of Chemistry in the University of Chicago, and EDWIN H. HALL, Ph.D., Professor of Physics in Harvard University. With 21 Woodcuts, Bibliographies, and Index. Crown 8vo., 6s. net.

THORNTON AND PEARSON.—NOTES ON VOLUMETRIC ANALYSIS. By ARTHUR THORNTON, M.A., and MARCHANT PEARSON, B.A., Assistant Science Master, Bradford Grammar School. Medium 8vo., 2s.

THORPE.—Works by T. E. THORPE, C.B., D.Sc. (Vict.), Ph.D., F.R.S., Principal of the Government Laboratory, London. Assisted by Eminent Contributors.

A DICTIONARY OF APPLIED CHEMISTRY. 3 vols. 8vo. Vols. I. and II., 42s. each. Vol. III., 63s.

QUANTITATIVE CHEMICAL ANALYSIS. With 88 Woodcuts. Fcp. 8vo., 4s. 6d.

THORPE AND MUIR.—QUALITATIVE CHEMICAL ANALYSIS AND LABORATORY PRACTICE. By T. E. THORPE, C.B., Ph.D., D.Sc., F.R.S., and M. M. PATTISON MUIR, M.A. With Plate of Spectra and 57 Illustrations. Fcp. 8vo., 3s. 6d.

TILDEN.—Works by WILLIAM A. TILDEN, D.Sc. London, F.R.S., Professor of Chemistry in the Royal College of Science, South Kensington.

A SHORT HISTORY OF THE PROGRESS OF SCIENTIFIC CHEMISTRY IN OUR OWN TIMES. Crown 8vo., 5s. net.

INTRODUCTION TO THE STUDY OF CHEMICAL PHILOSOPHY. The Principles of Theoretical and Systematic Chemistry. With 5 Illustrations. Fcp. 8vo., 5s. With ANSWERS to Problems. Fcp. 8vo., 5s. 6d.

PRACTICAL CHEMISTRY. The principles of Qualitative Analysis. Fcp. 8vo., 1s. 6d.

WATTS DICTIONARY OF CHEMISTRY. Revised and entirely Rewritten by H. FORSTER MORLEY, M.A., D.Sc., Fellow of, and lately Assistant Professor of Chemistry in, University College, London; and M. M. PATTISON MUIR, M.A., F.R.S.E., Fellow, and Prælector in Chemistry, of Gonville and Caius College, Cambridge. Assisted by Eminent Contributors. 4 vols. 8vo., £5 net.

WHITELEY.—Works by R. LLOYD WHITELEY, F.I.C., Principal of the Municipal Science School, West Bromwich.

CHEMICAL CALCULATIONS. With Explanatory Notes, Problems and Answers, specially adapted for use in Colleges and Science Schools. With a Preface by Professor F. CLOWES, D.Sc. (Lond.), F.I.C. Crown 8vo., 2s.

ORGANIC CHEMISTRY: the Fatty Compounds. With 45 Illustrations. Crown 8vo., 3s. 6d.

PHYSICS, ETC.

BIDGOOD.—ELEMENTARY PHYSICS AND CHEMISTRY FOR THE USE OF SCHOOLS. (In Three Books.) By JOHN BIDGOOD, B.Sc., Headmaster of the Gateshead School of Science.

Book I. Elementary Physics. With 120 Illustrations. Crown 8vo., 1s. 6d.

Book II. Physics and Chemistry. With 122 Illustrations. Crown 8vo., 1s. 6d.

BOSE.—RESPONSE IN THE LIVING AND NON-LIVING.

By JAGADIS CHUNDER BOSE, M.A. (Cantab.), D.Sc. (Lond.), Professor, Presidency College, Calcutta. With 117 Illustrations. 8vo., 10s. 6d.

** * This volume describes experimental investigations on animal, vegetable and inorganic substances regarding their response to stimulus. These researches show that the effects of fatigue, stimulants, depressants and poisons are alike in the organic and inorganic, and demonstrate that the response phenomena in the 'living' have been foreshadowed in the 'non-living'.*

GANOT.—Works by PROFESSOR GANOT. Translated and Edited by E. ATKINSON, Ph.D., F.C.S., and A. W. REINOLD, M.A., F.R.S.

ELEMENTARY TREATISE ON PHYSICS, Experimental and Applied. With 9 Coloured Plates and Maps, and 1048 Woodcuts, and Appendix of Problems and Examples with Answers. Crown 8vo., 15s.

NATURAL PHILOSOPHY FOR GENERAL READERS AND YOUNG PEOPLE. With 7 Plates, 632 Woodcuts, and an Appendix of Questions. Crown 8vo. 7s. 6d.

GLAZEBROOK AND SHAW.—PRACTICAL PHYSICS. By R. T. GLAZEBROOK, M.A., F.R.S., and W. N. SHAW, M.A. With 134 Illustrations. Fcp. 8vo., 7s. 6d.

GUTHRIE.—MOLECULAR PHYSICS AND SOUND. By F. GUTHRIE, Ph.D. With 91 Diagrams. Fcp. 8vo., 1s. 6d.

HELMHOLTZ.—POPULAR LECTURES ON SCIENTIFIC SUBJECTS. By HERMANN VON HELMHOLTZ. Translated by E. ATKINSON, Ph.D., F.C.S., formerly Professor of Experimental Science, Staff College. With 68 Illustrations. 2 vols., crown 8vo., 3s. 6d. each.

HENDERSON.—ELEMENTARY PHYSICS. By JOHN HENDERSON, D.Sc. (Edin.), A.I.E.E., Physics Department, Borough Road Polytechnic. Crown 8vo., 2s. 6d.

MACLEAN.—EXERCISES IN NATURAL PHILOSOPHY. By MAGNUS MACLEAN, D.Sc., Professor of Electrical Engineering at the Glasgow and West of Scotland Technical College. Crown 8vo., 4s. 6d.

MEYER.—THE KINETIC THEORY OF GASES. Elementary Treatise, with Mathematical Appendices. By Dr. OSKAR EMIL MEYER, Professor of Physics at the University of Breslau. Second Revised Edition. Translated by ROBERT E. BAYNES, M.A., Student of Christ Church, Oxford, and Dr. Lee's Reader in Physics. 8vo., 15s. net.

VAN 'tHOFF.—THE ARRANGEMENT OF ATOMS IN SPACE. By J. H. VAN 'tHOFF. Second, Revised, and Enlarged Edition. With a Preface by JOHANNES WISLICENUS, Professor of Chemistry at the University of Leipzig; and an Appendix 'Stereo-chemistry among Inorganic Substances,' by ALFRED WERNER, Professor of Chemistry at the University of Zürich. Translated and Edited by ARNOLD EILOART. Crown 8vo., 6s. 6d.

PHYSICS, ETC.—Continued.

WATSON.—Works by W. WATSON, A.R.C.S., F.R.S., D.Sc., Assistant Professor of Physics at the Royal College of Science, London.

ELEMENTARY PRACTICAL PHYSICS: a Laboratory Manual for Use in Organised Science Schools. With 120 Illustrations and 193 Exercises. Crown 8vo., 2s. 6d.

A TEXT-BOOK OF PHYSICS. With 564 Diagrams and Illustrations. Large crown 8vo., 10s. 6d.

WORTHINGTON.—A FIRST COURSE OF PHYSICAL LABORATORY PRACTICE. Containing 264 Experiments. By A. M. WORTHINGTON, M.A., F.R.S. With Illustrations. Crown 8vo., 4s. 6d.

WRIGHT.—ELEMENTARY PHYSICS. By MARK R. WRIGHT, M.A., Professor of Normal Education, Durham College of Science. With 242 Illustrations. Crown 8vo., 2s. 6d.

MECHANICS, DYNAMICS, STATICS, HYDRO-STATICS, ETC.

BALL.—A CLASS-BOOK OF MECHANICS. By Sir R. S. BALL, LL.D. 89 Diagrams. Fcp. 8vo., 1s. 6d.

GOODEVE.—Works by T. M. GOODEVE, M.A., formerly Professor of Mechanics at the Normal School of Science, and the Royal School of Mines.

THE ELEMENTS OF MECHANISM. With 357 Illustrations. Crown 8vo., 6s.

PRINCIPLES OF MECHANICS. With 253 Illustrations and numerous Examples. Crown 8vo., 6s.

A MANUAL OF MECHANICS: an Elementary Text-Book for Students of Applied Mechanics. With 138 Illustrations and Diagrams and 188 Examples taken from the Science Department Examination Papers, with Answers. Fcp. 8vo., 2s. 6d.

GOODMAN.—MECHANICS APPLIED TO ENGINEERING
By JOHN GOODMAN, Wh.Sch., A.M.I.C.E., M.I.M.E., Professor of Engineering in the Yorkshire College, Leeds (Victoria University). With 620 Illustrations and numerous examples. Crown 8vo., 7s. 6d. net.

GRIEVE.—LESSONS IN ELEMENTARY MECHANICS.
By W. H. GRIEVE, late Engineer, R.N., Science Demonstrator for the London School Board, etc.

Stage 1. With 165 Illustrations and a large number of Examples. Fcp. 8vo., 1s. 6d.

Stage 2. With 122 Illustrations. Fcp. 8vo., 1s. 6d.

Stage 3. With 103 Illustrations. Fcp. 8vo., 1s. 6d.

MECHANICS, DYNAMICS, STATICS, HYDROSTATICS, ETC.—

Continued.

MAGNUS.—Works by SIR PHILIP MAGNUS, B.Sc., B.A.

LESSONS IN ELEMENTARY MECHANICS. Introductory to the study of Physical Science. Designed for the Use of Schools, and of Candidates for the London Matriculation and other Examinations. With numerous Exercises, Examples, Examination Questions, and Solutions, etc., from 1870-1895. With Answers, and 131 Woodcuts. Fcp. 8vo., 3s. 6d.

Key for the use of Teachers only, price 5s. 3½d.

HYDROSTATICS AND PNEUMATICS. Fcp. 8vo., 1s. 6d.; or, with Answers, 2s. The Worked Solutions of the Problems, 2s.

PULLEN.—MECHANICS: Theoretical, Applied, and Experimental. By W. W. F. PULLEN, WH. SC. M.I.M.E., A.M.I.C.E. With 318 Diagrams and numerous Examples. Crown 8vo., 4s. 6d.

ROBINSON.—ELEMENTS OF DYNAMICS (Kinetics and Statics). With numerous Exercises. A Text-book for Junior Students. By the Rev. J. L. ROBINSON, M.A. Crown 8vo., 6s.

SMITH.—Works by J. HAMBLIN SMITH, M.A.

ELEMENTARY STATICS. Crown 8vo., 3s.

ELEMENTARY HYDROSTATICS. Crown 8vo., 3s.

KEY TO STATICS AND HYDROSTATICS. Crown 8vo., 6s.

TARLETON.—AN INTRODUCTION TO THE MATHEMATICAL THEORY OF ATTRACTION. By FRANCIS A. TARLETON, LL.D., Sc.D., Fellow of Trinity College, and Professor of Natural Philosophy in the University of Dublin. Crown 8vo., 10s. 6d.

TAYLOR.—Works by J. E. TAYLOR, M.A., B.Sc. (Lond.).

THEORETICAL MECHANICS, including Hydrostatics and Pneumatics. With 175 Diagrams and Illustrations, and 522 Examination Questions and Answers. Crown 8vo., 2s. 6d.

THEORETICAL MECHANICS—SOLIDS. With 163 Illustrations, 120 Worked Examples and over 500 Examples from Examination Papers, etc. Crown 8vo., 2s. 6d.

THEORETICAL MECHANICS.—FLUIDS. With 122 Illustrations, numerous Worked Examples, and about 500 Examples from Examination Papers, etc. Crown 8vo., 2s. 6d.

THORNTON.—THEORETICAL MECHANICS—SOLIDS. Including Kinematics, Statics and Kinetics. By ARTHUR THORNTON, M.A., F.R.A.S. With 200 Illustrations, 130 Worked Examples, and over 900 Examples from Examination Papers, etc. Crown 8vo., 4s. 6d.

MECHANICS, DYNAMICS, STATICS, HYDROSTATICS, ETC.—
Continued.

TWISDEN.—Works by the Rev. JOHN F. TWISDEN, M.A.

PRACTICAL MECHANICS; an Elementary Introduction to their Study. With 855 Exercises, and 184 Figures and Diagrams. Crown 8vo., 10s. 6d.

THEORETICAL MECHANICS. With 172 Examples, numerous Exercises, and 154 Diagrams. Crown 8vo., 8s. 6d.

WILLIAMSON.—INTRODUCTION TO THE MATHEMATICAL THEORY OF THE STRESS AND STRAIN OF ELASTIC SOLIDS. By BENJAMIN WILLIAMSON, D.Sc., F.R.S. Crown 8vo., 5s.

WILLIAMSON AND TARLETON.—AN ELEMENTARY TREATISE ON DYNAMICS. Containing Applications to Thermodynamics, with numerous Examples. By BENJAMIN WILLIAMSON, D.Sc., F.R.S., and FRANCIS A. TARLETON, LL.D. Crown 8vo., 10s. 6d.

WORTHINGTON.—DYNAMICS OF ROTATION: an Elementary Introduction to Rigid Dynamics. By A. M. WORTHINGTON, M.A., F.R.S. Crown 8vo., 4s. 6d.

MENSURATION, SURVEYING, ETC.

BRABANT.—THE ELEMENTS OF PLANE AND SOLID MENSURATION. With Copious Examples and Answers. By F. G. BRABANT, M.A. Crown 8vo., 3s. 6d.

GRIBBLE.—PRELIMINARY SURVEY AND ESTIMATES. By THEODORE GRAHAM GRIBBLE, Civil Engineer. Including Elementary Astronomy, Route Surveying, Tacheometry, Curve Ranging, Graphic Mensuration, Estimates, Hydrography and Instruments. With 133 Illustrations, Quantity Diagrams, and a Manual of the Slide-Rule. Fcp. 8vo., 7s. 6d.

LODGE.—MENSURATION FOR SENIOR STUDENTS. By ALFRED LODGE, M.A., late Fereday Fellow of St. John's College, Oxford; Professor of Pure Mathematics at the Royal Indian Engineering College, Cooper's Hill. With Answers. Crown 8vo., 4s. 6d.

LUPTON.—A PRACTICAL TREATISE ON MINE SURVEYING. By ARNOLD LUPTON, Mining Engineer, Certificated Colliery Manager, Surveyor, Member of the Institution of Civil Engineers, etc. With 216 Illustrations. Medium 8vo., 12s. net.

NESBIT.—Works by A. NESBIT.

PRACTICAL MENSURATION. Illustrated by 700 Practical Examples and 700 Woodcuts. 12mo., 3s. 6d. KEY, 5s.

PRACTICAL LAND-SURVEYING, for the Use of Schools and Private Students. Edited by W. BURNES, F.R.A.S. With 14 Plates, 221 Figures, and a Field-Book. 8vo., 12s.

SMITH.—CIRCULAR SLIDE RULE. By G. L. SMITH. Fcp. 8vo., 1s. 1¹/₂ net.

ALGEBRA, ETC.

*** For other Books, see Longmans & Co.'s Catalogue of Educational and School Books.*

ANNALS OF MATHEMATICS. (*PUBLISHED UNDER THE AUSPICES OF HARVARD UNIVERSITY.*) Issued Quarterly. 4to., 2s. net.

BURNSIDE AND PANTON.—Works by WILLIAM SNOW BURNSIDE, M.A., Fellow of Trinity College, Dublin; and ARTHUR WILLIAM PANTON, M.A., Fellow and Tutor of Trinity College, Dublin.

THE THEORY OF EQUATIONS. With an Introduction to the Theory of Binary Algebraic Forms. 2 vols. 8vo., 9s. 6d. each.

AN INTRODUCTION TO DETERMINANTS: being a Chapter from the Theory of Equations (being the First Chapter of the Second Volume of 'The Theory of Equations'). 8vo., sewed, 2s. 6d.

CRACKNELL.—PRACTICAL MATHEMATICS. By A. G. CRACKNELL, M.A., B.Sc., Sixth Wrangler, etc. With Answers to the Examples. Crown 8vo., 3s. 6d.

GRIFFIN.—Works by Rev. WILLIAM NATHANIEL GRIFFIN, B.D., sometime Fellow of St. John's College, Cambridge.

THE ELEMENTS OF ALGEBRA AND TRIGONOMETRY. Fcp. 8vo., 3s. 6d.

NOTES ON THE ELEMENTS OF ALGEBRA AND TRIGONOMETRY. With Solutions of the more Difficult Questions. Fcp. 8vo., 3s. 6d.

MELLOR.—HIGHER MATHEMATICS FOR STUDENTS OF CHEMISTRY AND PHYSICS. With special reference to Practical Work. By J. W. MELLOR, D.Sc., Research Fellow, The Owens College, Manchester. With 142 Diagrams. 8vo., 12s. 6d. net.

WELSFORD AND MAYO.—ELEMENTARY ALGEBRA. By J. W. WELSFORD, M.A., formerly Fellow of Gonville and Caius College, Cambridge, and C. H. P. MAYO, M.A., formerly Scholar of St. Peter's College, Cambridge; Assistant Masters at Harrow School. Crown 8vo., 3s. 6d., or with Answers, 4s. 6d.

CONIC SECTIONS, ETC.

CASEY.—A TREATISE ON THE ANALYTICAL GEOMETRY OF THE POINT, LINE, CIRCLE, AND CONIC SECTIONS. By JOHN CASEY, LL.D., F.R.S. Crown 8vo., 12s.

RICHARDSON.—GEOMETRICAL CONIC SECTIONS. By G. RICHARDSON, M.A. Crown 8vo., 4s. 6d.

SALMON.—A TREATISE ON CONIC SECTIONS, containing an Account of some of the most Important Modern Algebraic and Geometric Methods. By G. SALMON, D.D., F.R.S. 8vo., 12s.

SMITH.—GEOMETRICAL CONIC SECTIONS. By J. HAMBLIN SMITH, M.A. Crown 8vo., 3s. 6d.

THE CALCULUS, LOGARITHMS, ETC.

BARKER.—GRAPHICAL CALCULUS. By ARTHUR H. BARKER, B.A., B.Sc. With an Introduction by JOHN GOODMAN, A.M.I.C.E. With 61 Diagrams. Crown 8vo., 4s. 6d.

MURRAY.—AN INTRODUCTORY COURSE IN DIFFERENTIAL EQUATIONS. By DANIEL ALEXANDER MURRAY, Ph.D. Crown 8vo., 4s. 6d.

TATE.—PRINCIPLES OF THE DIFFERENTIAL AND INTEGRAL CALCULUS. Applied to the Solution of Useful Problems in Mathematics and Mechanics. By THOMAS TATE. 12mo, 4s. 6d.

TAYLOR.—Works by F. GLANVILLE TAYLOR.

AN INTRODUCTION TO THE DIFFERENTIAL AND INTEGRAL CALCULUS AND DIFFERENTIAL EQUATIONS. Crown 8vo., 9s.

AN INTRODUCTION TO THE PRACTICAL USE OF LOGARITHMS, WITH EXAMPLES IN MENSURATION. With Answers to Exercises. Crown 8vo., 1s. 6d.

WILLIAMSON.—Works by BENJAMIN WILLIAMSON, D.Sc.

AN ELEMENTARY TREATISE ON THE DIFFERENTIAL CALCULUS; containing the Theory of Plane Curves with numerous Examples. Crown 8vo., 10s. 6d.

AN ELEMENTARY TREATISE ON THE INTEGRAL CALCULUS; containing Applications to Plane Curves and Surfaces, and also a Chapter on the Calculus of Variations, with numerous Examples. Crown 8vo., 10s. 6d.

GEOMETRY AND EUCLID.

* * For other Works, see Longmans & Co.'s Catalogue of Educational and School Books.

ALLMAN.—GREEK GEOMETRY FROM THALES TO EUCLID. By G. J. ALLMAN. 8vo., 10s. 6d.

CASEY.—Works by JOHN CASEY, LL.D., F.R.S.

THE ELEMENTS OF EUCLID, BOOKS I.-VI. and Propositions, I.-XXI. of Book XI., and an Appendix of the Cylinder, Sphere, Cone, etc. With Copious Annotations and numerous Exercises. Fcp. 8vo., 4s. 6d. KEY to Exercises. Fcp. 8vo., 6s.

A SEQUEL TO THE ELEMENTS OF EUCLID. [Part I. Books I.-VI. With numerous Examples. Fcp. 8vo., 3s. 6d.

A TREATISE ON THE ANALYTICAL GEOMETRY OF THE POINT, LINE, CIRCLE AND CONIC SECTIONS. Containing an Account of its most recent Extension. Crown 8vo., 12s.

GEOMETRY AND EUCLID—Continued.

HAMILTON.—ELEMENTS OF QUATERNIONS. By the late Sir WILLIAM ROWAN HAMILTON, LL.D., M.R.I.A. Edited by CHARLES JASPER JOLY, M.A., Fellow of Trinity College, Dublin. 2 vols. 4to. 21s. net each.

HIME.—THE OUTLINES OF QUATERNIONS. By Lieut.-Colonel H. W. L. HIME, late Royal Artillery. Crown 8vo., 10s.

LOW.—TEXT-BOOK ON PRACTICAL, SOLID, AND DESCRIPTIVE GEOMETRY. By DAVID ALLAN LOW, Professor of Engineering, East London Technical College. Crown 8vo.

Part I. With 114 Figures, 2s.

Part II. With 64 Figures, 3s.

MORRIS.—Works by I. HAMMOND MORRIS.

PRACTICAL PLANE AND SOLID GEOMETRY, including Graphic Arithmetic fully Illustrated with Drawings prepared specially by the Author. Crown 8vo., 2s. 6d.

GEOMETRICAL DRAWING FOR ART STUDENTS. Embracing Plane Geometry and its Applications, the Use of Scales, and the Plans and Elevations of Solids as required in Section I. of Science Subjects. Crown 8vo., 2s.

SMITH.—ELEMENTS OF GEOMETRY. By J. HAMBLIN SMITH, M.A. Containing Books 1 to 6, and portions of Books 11 and 12, of Euclid, with Exercises and Notes. Crown 8vo., 3s. 6d. KEY, crown 8vo., 8s. 6d.

Books 1 and 2, limp cloth, 1s. 6d., may be had separately.

SPOONER.—THE ELEMENTS OF GEOMETRICAL DRAWING: an Elementary Text-book on Practical Plane Geometry, including an Introduction to Solid Geometry. Written to include the requirements of the Syllabus of the Board of Education in Geometrical Drawing and for the use of Students preparing for the Military Entrance Examinations. By HENRY J. SPOONER, C.E., M.Inst.M.E.; Director of the Polytechnic School of Engineering, etc. Crown 8vo., 3s. 6d.

WATSON.—ELEMENTS OF PLANE AND SOLID GEOMETRY. By H. W. WATSON, M.A. Fcp. 8vo., 3s. 6d.

WILSON.—GEOMETRICAL DRAWING. For the use of Candidates for Army Examinations, and as an Introduction to Mechanical Drawing. By W. N. WILSON, M.A. Parts I. and II. Crown 8vo., 4s. 6d. each.

WINTER.—ELEMENTARY GEOMETRICAL DRAWING. By S. H. WINTER.

Part I. Including Practical Plane Geometry, the Construction of Scales, the Use of the Sector, the Marquois Scales, and the Protractor. With 3 Plates and 1000 Exercises and Examination Papers. Post 8vo., 5s.

TRIGONOMETRY.

CASEY.—A TREATISE ON ELEMENTARY TRIGONOMETRY. By JOHN CASEY, LL.D., F.R.S., late Fellow of the Royal University of Ireland. With numerous Examples and Questions for Examination. 12mo, 3s.

CLARKE.—PLANE TRIGONOMETRY. Containing the more advanced Propositions, Solution of Problems and a complete Summary of Formulæ, Bookwork, etc., together with recent Examination Papers for the Army, Woolwich, etc. With Answers. By the Rev. A. DAWSON CLARKE, M.A., St. John's College, Cambridge. Crown 8vo., 5s.

GOODWIN.—Works by H. B. GOODWIN, M.A.

PLANE AND SPHERICAL TRIGONOMETRY. In Three Parts, comprising those portions of the subjects, theoretical and practical, which are required in the Final Examination for Rank of Lieutenant at Greenwich. 8vo., 8s. 6d.

ELEMENTARY PLANE TRIGONOMETRY. With numerous Examples and Examination Papers set at the Royal Naval College in recent years. With Answers. 8vo., 5s.

JONES.—THE BEGINNINGS OF TRIGONOMETRY. By A. CLEMENT JONES, M.A., Ph.D., late Open Scholar and Senior Hulme Exhibitioner of Brasenose College, Oxford; Senior Mathematical Master of Bradford Grammar School. Crown 8vo., 2s.

MURRAY.—PLANE TRIGONOMETRY FOR COLLEGES AND SECONDARY SCHOOLS. By DANIEL A. MURRAY, B.A., Ph.D., Instructor in Mathematics in Cornell University. Crown 8vo., 3s. 6d. With Logarithmic and Trigonometric Tables. Crown 8vo., 5s.

SMITH.—ELEMENTARY TRIGONOMETRY. By J. HAMBLIN SMITH, M.A. Crown 8vo., 4s. 6d. Key, 7s. 6d.

OPTICS, PHOTOGRAPHY, ETC.

ABNEY.—A TREATISE ON PHOTOGRAPHY. By Sir WILLIAM DE WIVELESIE ABNEY, K.C.B., F.R.S., Principal Assistant Secretary of the Secondary Department of the Board of Education. With 134 Illustrations. Fcp. 8vo., 5s.

DRUDE.—THE THEORY OF OPTICS. By PAUL DRUDE, Professor of Physics at the University of Giessen. Translated from the German by C. RIBORG MANN and ROBERT A. MILLIKAN, Assistant Professors of Physics at the University of Chicago. With 110 Diagrams. 8vo., 15s. net.

GLAZEBROOK.—PHYSICAL OPTICS. By R. T. GLAZEBROOK, M.A., F.R.S., Principal of University College, Liverpool. With 183 Woodcuts of Apparatus, etc. Fcp. 8vo., 6s.

VANDERPOEL.—COLOR PROBLEMS: a Practical Manual for the Lay Student of Color. By EMILY NOYES VANDERPOEL. With 117 Plates in Color. Square 8vo., 21s. net.

WRIGHT.—OPTICAL PROJECTION: a Treatise on the Use of the Lantern in Exhibition and Scientific Demonstration. By LEWIS WRIGHT, Author of 'Light: a Course of Experimental Optics'. With 232 Illustrations. Crown 8vo., 6s.

SOUND, LIGHT, HEAT, AND THERMODYNAMICS.

DEXTER.—ELEMENTARY PRACTICAL SOUND, LIGHT AND HEAT. By JOSEPH S. DEXTER, B.Sc. (Lond.), Physics Master, Technical Day School, The Polytechnic Institute, Regent Street. With 152 Illustrations. Crown 8vo., 2s. 6d.

EMTAGE.—LIGHT. By W. T. A. EMTAGE, M.A., Director of Education, Mauritius. With 232 Illustrations. Crown 8vo., 6s

HELMHOLTZ.—ON THE SENSATIONS OF TONE AS A PHYSIOLOGICAL BASIS FOR THE THEORY OF MUSIC. By HERMANN VON HELMHOLTZ. Royal 8vo., 28s.

MAXWELL.—THEORY OF HEAT. By J. CLERK MAXWELL M.A., F.R.SS., L. and E. With Corrections and Additions by Lord RAY LEIGH. With 38 Illustrations. Fcp. 8vo., 4s. 6d.

SMITH.—THE STUDY OF HEAT. By J. HAMBLIN SMITH, M.A., of Gonville and Caius College, Cambridge. Crown 8vo., 3s.

TYNDALL.—Works by JOHN TYNDALL, D.C.L., F.R.S.
See p. 36.

WORMELL.—A CLASS-BOOK OF THERMODYNAMICS. By RICHARD WORMELL, B.Sc., M.A. Fcp. 8vo., 1s. 6d.

WRIGHT.—Works by MARK R. WRIGHT, M.A.

SOUND, LIGHT, AND HEAT. With 160 Diagrams and Illustrations. Crown 8vo., 2s. 6d.

ADVANCED HEAT. With 136 Diagrams and numerous Examples and Examination Papers. Crown 8vo., 4s. 6d.

STEAM, OIL, AND GAS ENGINES.

BALE.—A HAND-BOOK FOR STEAM USERS; being Rules for Engine Drivers and Boiler Attendants, with Notes on Steam Engine and Boiler Management and Steam Boiler Explosions. By M. POWIS BALE, M.I.M.E., A.M.I.C.E. Fcp. 8vo., 2s. 6d.

CLERK.—THE GAS AND OIL ENGINE. By DUGALD CLERK, Member of the Institution of Civil Engineers, Fellow of the Chemical Society, Member of the Royal Institution, Fellow of the Institute of Patent Agents. With 228 Illustrations. 8vo., 15s.

STEAM, OIL, AND GAS ENGINES—Continued.

HOLMES.—THE STEAM ENGINE. By GEORGE C. V. HOLMES, Chairman of the Board of Works, Ireland. With 212 Illustrations. Fcp. 8vo., 6s.

NEILSON.—THE STEAM TURBINE. By ROBERT M. NEILSON, Whitworth Exhibitioner, Associate Member of the Institute of Mechanical Engineers, Lecturer on Steam and the Steam Engine at the Heginbottom Technical School, Ashton-under-Lyne. With 145 Illustrations. 8vo., 7s. 6d. net.

NORRIS.—A PRACTICAL TREATISE ON THE 'OTTO' CYCLE GAS ENGINE. By WILLIAM NORRIS, M.I.Mech.E. With 207 Illustrations. 8vo., 10s. 6d.

RIPPER.—Works by WILLIAM RIPPER, Professor of Mechanical Engineering in the Sheffield Technical School.

STEAM. With 185 Illustrations. Crown 8vo., 2s. 6d.

STEAM ENGINE THEORY AND PRACTICE. With 438 Illustrations. 8vo., 9s.

SENNETT AND ORAM.—THE MARINE STEAM ENGINE: A Treatise for Engineering Students, Young Engineers and Officers of the Royal Navy and Mercantile Marine. By the late RICHARD SENNETT, Engineer-in-Chief of the Navy, etc.; and HENRY J. ORAM, Senior Engineer Inspector at the Admiralty, Inspector of Machinery in H.M. Fleet, etc. With 414 Diagrams. 8vo., 21s.

STROMEYER.—MARINE BOILER MANAGEMENT AND CONSTRUCTION. Being a Treatise on Boiler Troubles and Repairs, Corrosion, Fuels, and Heat, on the properties of Iron and Steel, on Boiler Mechanics, Workshop Practices, and Boiler Design. By C. E. STROMEYER, Chief Engineer of the Manchester Steam Users' Association, Member of Council of the Institution of Naval Architects, etc. With 452 Diagrams, etc. 8vo., 12s. net.

ARCHITECTURE, BUILDING CONSTRUCTION, ETC.

ADVANCED BUILDING CONSTRUCTION. By the Author of 'Rivingtons' Notes on Building Construction'. With 385 Illustrations. Crown 8vo., 4s. 6d.

BURRELL.—BUILDING CONSTRUCTION. By EDWARD J. BURRELL, Second Master of the People's Palace Technical School, London. With 303 Working Drawings. Crown 8vo., 2s. 6d.

GWILT.—AN ENCYCLOPÆDIA OF ARCHITECTURE. By JOSEPH GWILT, F.S.A. Revised (1888), with Alterations and Considerable Additions by WYATT PAPWORTH. With 1700 Engravings. 8vo., 21s. net.

PARKER AND UNWIN.—THE ART OF BUILDING A HOME: A Collection of Lectures and Illustrations. By BARRY PARKER and RAYMOND UNWIN. With 68 Full-page Plates. 8vo., 10s. 6d. net.

RICHARDS.—BRICKLAYING AND BRICKCUTTING. By H. W. RICHARDS, Examiner in Brickwork and Masonry to the City and Guilds of London Institute, Head of Building Trades Department, Northern Polytechnic Institute, London, N. With over 200 Illustrations. 8vo., 3s. 6d.

ARCHITECTURE, BUILDING CONSTRUCTION, ETC.—Continued.

SEDDON.—**BUILDER'S WORK AND THE BUILDING TRADES.** By Col. H. C. SEDDON, R.E., late Superintending Engineer, H.M.'s Dockyard, Portsmouth; Examiner in Building Construction, Science and Art Department, South Kensington. With numerous Illustrations. Medium 8vo., 16s.

VALDER.—**BOOK OF TABLES**, giving the Cubic Contents of from One to Thirty Pieces Deals, Battens and Scantlings of the Sizes usually imported or used in the Building Trades, together with an Appendix showing a large number of sizes, the Contents of which may be found by referring to the aforesaid Tables. By THOMAS VALDER. Oblong 4to., 6s. net.

RIVINGTONS' COURSE OF BUILDING CONSTRUCTION.

NOTES ON BUILDING CONSTRUCTION. Arranged to meet the requirements of the syllabus of the Board of Education. Medium 8vo.

Part I. Elementary Stage. With 552 Illustrations, 9s. net.

Part II. Advanced Stage. With 479 Illustrations, 9s. net.

Part III. Materials. Course for Honours. With 188 Illustrations, 18s. net.

Part IV. Calculations for Building Structures. Course for Honours. With 551 Illustrations, 13s. net.

ELECTRICITY AND MAGNETISM.

ARRHENIUS.—**A TEXT-BOOK OF ELECTROCHEMISTRY.** By SVANTE ARRHENIUS, Professor at the University of Stockholm. Translated from the German Edition by JOHN MCCRAE, Ph.D. With 58 Illustrations. 8vo., 9s. 6d. net.

CARUS-WILSON.—**ELECTRO-DYNAMICS:** the Direct-Current Motor. By CHARLES ASHLEY CARUS-WILSON, M.A. Cantab. With 71 Diagrams, and a Series of Problems, with Answers. Crown 8vo., 7s. 6d.

CUMMING.—**ELECTRICITY TREATED EXPERIMENTALLY.** By LINNÆUS CUMMING, M.A. With 242 Illustrations. Cr. 8vo., 4s. 6d.

DAY.—**EXERCISES IN ELECTRICAL AND MAGNETIC MEASUREMENTS**, with Answers. By R. E. DAY. 12mo., 3s. 6d.

FITZGERALD.—**THE SCIENTIFIC WRITINGS OF THE LATE GEORGE FRANCIS FITZGERALD**, Sc.D., F.R.S., F.R.S.E., Fellow of Trinity College, Dublin. Collected and Edited, with an Historical Introduction, by JOSEPH LARMOR, Sec.R.S., Fellow of St. John's College, Cambridge. With Portrait. 8vo., 15s.

GORE.—**THE ART OF ELECTRO-METALLURGY**, including all known Processes of Electro-Deposition. By G. GORE, LL.D., F.R.S. With 56 Illustrations. Fcp. 8vo., 6s.

HENDERSON.—**Works by JOHN HENDERSON**, D.Sc., F.R.S.E. **PRACTICAL ELECTRICITY AND MAGNETISM.** With 159 Illustrations and Diagrams. Crown 8vo., 6s. 6d.

PRELIMINARY PRACTICAL MAGNETISM AND ELECTRICITY. Crown 8vo., 1s.

ELECTRICITY AND MAGNETISM—Continued.

JENKIN.—ELECTRICITY AND MAGNETISM. By FLEEMING JENKIN, F.R.S., M.I.C.E. With 177 Illustrations. Fcp. 8vo., 3s. 6d.

JOUBERT.—ELEMENTARY TREATISE ON ELECTRICITY AND MAGNETISM. Founded on JOUBERT'S 'Traité Élémentaire d'Électricité'. By G. C. FOSTER, F.R.S., and E. ATKINSON, Ph.D. With Illustrations. Crown 8vo. [New Edition in the Press.]

JOYCE.—EXAMPLES IN ELECTRICAL ENGINEERING. By SAMUEL JOYCE, A.I.E.E. Crown 8vo., 5s.

MACLEAN AND MARCHANT.—ELEMENTARY QUESTIONS IN ELECTRICITY AND MAGNETISM. With Answers. Compiled by MAGNUS MACLEAN, D.Sc., M.I.E.E., and E. W. MARCHANT, D.Sc., A.I.E.E. Crown 8vo., 1s.

MERRIFIELD.—MAGNETISM AND DEVIATION OF THE COMPASS. By JOHN MERRIFIELD, LL.D., F.R.A.S., 18mo., 2s. 6d.

PARR.—PRACTICAL ELECTRICAL TESTING IN PHYSICS AND ELECTRICAL ENGINEERING. By G. D. ASPINALL PARR, Assoc. M.I.E.E. With 231 Illustrations. 8vo., 8s. 6d.

POYSER.—Works by A. W. POYSER, M.A.

MAGNETISM AND ELECTRICITY. With 235 Illustrations. Crown 8vo., 2s. 6d.

ADVANCED ELECTRICITY AND MAGNETISM. With 317 Illustrations. Crown 8vo., 4s. 6d.

RHODES.—AN ELEMENTARY TREATISE ON ALTERING CURRENTS. By W. G. RHODES, M.Sc. (Vict.), Consulting Engineer. With 80 Diagrams 8vo., 7s. 6d. net.

SLINGO AND BROOKER.—Works by W. SLINGO and A. BROOKER.

ELECTRICAL ENGINEERING FOR ELECTRIC LIGHT ARTISANS AND STUDENTS. With 371 Illustrations. Crown 8vo., 12s.

PROBLEMS AND SOLUTIONS IN ELEMENTARY ELECTRICITY AND MAGNETISM. With 98 Illustrations. Cr. 8vo., 2s.

TYNDALL.—Works by JOHN TYNDALL, D.C.L., F.R.S. See p. 36.

TELEGRAPHY AND THE TELEPHONE.

HOPKINS.—TELEPHONE LINES AND THEIR PROPERTIES. By WILLIAM J. HOPKINS, Professor of Physics in the Drexel Institute, Philadelphia. Crown 8vo., 6s.

PREECE AND SIVEWRIGHT.—TELEGRAPHY. By Sir W. H. PREECE, K.C.B., F.R.S., V.P.Inst., C.E., etc., Consulting Engineer and Electrician, Post Office Telegraphs; and Sir J. SIVEWRIGHT, K.C.M.G., General Manager, South African Telegraphs. With 267 Illustrations. Fcp. 8vo., 6s.

ENGINEERING, STRENGTH OF MATERIALS, ETC.

ANDERSON.—THE STRENGTH OF MATERIALS AND STRUCTURES: the Strength of Materials as depending on their Quality and as ascertained by Testing Apparatus. By Sir J. ANDERSON, C.E., LL.D., F.R.S.E. With 66 Illustrations. Fcp. 8vo., 3s. 6d.

BARRY.—RAILWAY APPLIANCES: a Description of Details of Railway Construction subsequent to the completion of the Earthworks and Structures. By Sir JOHN WOLFE BARRY, K.C.B., F.R.S., M.I.C.E. With 218 Illustrations. Fcp. 8vo., 4s. 6d.

DIPLOCK.—A NEW SYSTEM OF HEAVY GOODS TRANSPORT ON COMMON ROADS. By BRAHAM JOSEPH DIPLOCK. With 27 Illustrations. 8vo.

GOODMAN.—MECHANICS APPLIED TO ENGINEERING. By JOHN GOODMAN, Wh.Sch., A.M.I.C.E., M.I.M.E., Professor of Engineering in the Yorkshire College, Leeds (Victoria University). With 620 Illustrations and numerous Examples. Crown 8vo., 7s. 6d. net.

LOW.—A POCKET-BOOK FOR MECHANICAL ENGINEERS. By DAVID ALLAN LOW (Whitworth Scholar), M.I.Mech.E., Professor of Engineering, East London Technical College (People's Palace), London. With over 1000 specially prepared Illustrations. Fcp. 8vo., gilt edges, rounded corners, 7s. 6d.

PARKINSON.—LIGHT RAILWAY CONSTRUCTION. By RICHARD MARION PARKINSON, Assoc.M.Inst.C.E. With 85 Diagrams. 8vo., 10s. 6d. net.

SMITH.—GRAPHICS, or the Art of Calculation by Drawing Lines, applied especially to Mechanical Engineering. By ROBERT H. SMITH, Professor of Engineering, Mason College, Birmingham. Part I. With separate Atlas of 29 Plates containing 97 Diagrams. 8vo., 15s.

STONE Y.—THE THEORY OF STRESSES IN GIRDERS AND SIMILAR STRUCTURES; with Practical Observations on the Strength and other Properties of Materials. By BINDON B. STONEY, LL.D., F.R.S., M.I.C.E. With 5 Plates and 143 Illust. in the Text. Royal 8vo., 36s.

UNWIN.—Works by W. CAWTHORNE UNWIN, F.R.S., B.Sc.
THE TESTING OF MATERIALS OF CONSTRUCTION.
A Text-book for the Engineering Laboratory and a Collection of the Results of Experiment. With 5 Plates and 188 Illustrations and Diagrams. 8vo., 16s. net.

ON THE DEVELOPMENT AND TRANSMISSION OF POWER FROM CENTRAL STATIONS: being the Howard Lectures delivered at the Society of Arts in 1893. With 81 Diagrams. 8vo., 10s. net.

WARREN.—ENGINEERING CONSTRUCTION IN IRON, STEEL, AND TIMBER. By WILLIAM HENRY WARREN, Challis Professor of Civil and Mechanical Engineering, University of Sydney. With 13 Folding Plates and 375 Diagrams. Royal 8vo., 16s. net.

WHEELER.—THE SEA COAST: Destruction, Littoral Drift, Protection. By W. H. WHEELER, M.Inst. C.E. With 38 Illustrations and Diagram. Medium 8vo., 10s. 6d. net.

LONGMANS' CIVIL ENGINEERING SERIES.

CIVIL ENGINEERING AS APPLIED TO CONSTRUCTION.

By LEVESON FRANCIS VERNON-HARCOURT, M.A., M.Inst.C.E. With 368 Illustrations. Medium 8vo., 14s. net.

CONTENTS.—Materials, Preliminary Works, Foundations and Roads—Railway Bridge and Tunnel Engineering—River and Canal Engineering—Irrigation Works—Dock Works and Maritime Engineering—Sanitary Engineering.

NOTES ON DOCKS AND DOCK CONSTRUCTION. By C.

COLSON, C.B., M.Inst.C.E. With 365 Illustrations. Medium 8vo., 21s. net.

CALCULATIONS IN HYDRAULIC ENGINEERING: a

Practical Text-Book for the use of Students, Draughtsmen and Engineers. By T. CLAXTON FIDLER, M.Inst.C.E.

Part I. Fluid Pressure and the Calculation of its Effects in Engineering Structures. With numerous Illustns. and Examples. 8vo., 6s. 6d. net.

Part II. Calculations in Hydro-Kinetics. With numerous Illustrations and Examples. 8vo., 7s. 6d. net.

RAILWAY CONSTRUCTION. By W. H. MILLS, M.I.C.E.,

Engineer-in-Chief of the Great Northern Railway of Ireland. With 516 Illustrations and Diagrams. 8vo., 18s. net.

PRINCIPLES AND PRACTICE OF HARBOUR CONSTRUCTION. By WILLIAM SHIELD, F.R.S.E., M.Inst.C.E. With 97 Illustrations. Medium 8vo., 15s. net.

TIDAL RIVERS: their (1) Hydraulics, (2) Improvement, (3)

Navigation. By W. H. WHEELER, M.Inst.C.E. With 75 Illustrations. Medium 8vo., 16s. net.

MACHINE DRAWING AND DESIGN.

LOW.—Works by DAVID ALLAN LOW, Professor of Engineering, East London Technical College (People's Palace).

IMPROVED DRAWING SCALES. 6d. in case.

AN INTRODUCTION TO MACHINE DRAWING AND DESIGN. With 153 Illustrations and Diagrams. Crown 8vo., 2s. 6d.

LOW AND BEVIS.—A MANUAL OF MACHINE DRAWING AND DESIGN. By DAVID ALLAN LOW and ALFRED WILLIAM BEVIS, M.I.Mech.E. With 700 Illustrations. 8vo., 7s. 6d.

UNWIN.—THE ELEMENTS OF MACHINE DESIGN. By W. CAWTHORNE UNWIN, F.R.S.

Part I. General Principles, Fastenings, and Transmissive Machinery. With 345 Diagrams, etc. Fcp. 8vo., 7s. 6d.

Part II. Chiefly on Engine Details. With 259 Illustrations, Fcp. 8vo., 6s.

NAVAL ARCHITECTURE.

ATTWOOD.—TEXT-BOOK OF THEORETICAL NAVAL ARCHITECTURE: a Manual for Students of Science Classes and Draughtsmen Engaged in Shipbuilders' and Naval Architects' Drawing Offices. By EDWARD LEWIS ATTWOOD, Assistant Constructor, Royal Navy. With 114 Diagrams. Crown 8vo., 7s. 6d.

WATSON.—NAVAL ARCHITECTURE: A Manual of Laying-off Iron, Steel and Composite Vessels. By THOMAS H. WATSON, Lecturer on Naval Architecture at the Durham College of Science, Newcastle-upon-Tyne. With numerous Illustrations. Royal 8vo., 15s. net.

WORKSHOP APPLIANCES, ETC.

NORTHCOTT.—LATHES AND TURNING, Simple, Mechanical and Ornamental. By W. H. NORTHCOTT. With 338 Illustrations. 8vo., 18s.

SHELLEY.—WORKSHOP APPLIANCES, including Descriptions of some of the Gauging and Measuring Instruments, Hand-cutting Tools, Lathes, Drilling, Planeing, and other Machine Tools used by Engineers. By C. P. B. SHELLEY, M.I.C.E. With an additional Chapter on Milling by R. R. LISTER. With 323 Illustrations. Fcp. 8vo., 5s.

MINERALOGY, MINING, METALLURGY, ETC.

BAUERMAN.—Works by HILARY BAUERMAN, F.G.S.
SYSTEMATIC MINERALOGY. With 373 Illustrations.
Fcp. 8vo., 6s.

DESCRIPTIVE MINERALOGY. With 236 Illustrations.
Fcp. 8vo., 6s.

BREARLEY AND IBBOTSON.—THE ANALYSIS OF STEEL-WORKS MATERIALS. By HARRY BREARLEY and FRED IBBOTSON, B.Sc. (Lond.), Demonstrator of Micrographic Analysis, University College, Sheffield. With 85 Illustrations. 8vo., 14s. net.

GORE.—THE ART OF ELECTRO-METALLURGY. By G. GORE, LL.D., F.R.S. With 56 Illustrations. Fcp. 8vo., 6s.

HUNTINGTON AND M'MILLAN.—METALS: their Properties and Treatment. By A. K. HUNTINGTON, Professor of Metallurgy in King's College, London, and W. G. M'MILLAN, Lecturer on Metallurgy in Mason's College, Birmingham. With 122 Illustrations. Fcp. 8vo., 7s. 6d.

LUPTON.—Works by ARNOLD LUPTON, M.I.C.E., F.G.S., etc.
MINING. An Elementary Treatise on the Getting of Minerals.
With 596 Diagrams and Illustrations. Crown 8vo., 9s. net.

A PRACTICAL TREATISE ON MINE SURVEYING.
With 209 Illustrations. 8vo., 12s. net.

RHEAD.—METALLURGY. By E. L. RHEAD, Lecturer on Metallurgy at the Municipal Technical School, Manchester. With 94 Illustrations. Fcp. 8vo., 3s. 6d.

RHEAD AND SEXTON.—ASSAYING AND METALLURGICAL ANALYSIS for the use of Students, Chemists and Assayers. By E. L. RHEAD, Lecturer on Metallurgy, Municipal School of Technology, Manchester; and A. HUMBOLDT SEXTON, F.I.C., F.C.S., Professor of Metallurgy, Glasgow and West of Scotland Technical College. 8vo., 10s. 6d. net.

RUTLEY.—THE STUDY OF ROCKS: an Elementary Text-book of Petrology. By F. RUTLEY, F.G.S. With 6 Plates and 88 other Illustrations. Fcp. 8vo., 4s. 6d.

ASTRONOMY, NAVIGATION, ETC.

ABBOTT.—ELEMENTARY THEORY OF THE TIDES : the Fundamental Theorems Demonstrated without Mathematics and the Influence on the Length of the Day Discussed. By T. K. ABBOTT, B.D., Fellow and Tutor, Trinity College, Dublin. Crown 8vo., 2s.

BALL.—Works by Sir ROBERT S. BALL, LL.D., F.R.S.

ELEMENTS OF ASTRONOMY. With 130 Figures and Diagrams. Fcp. 8vo., 6s. 6d.

A CLASS-BOOK OF ASTRONOMY. With 41 Diagrams. Fcp. 8vo., 1s. 6d.

GILL.—TEXT-BOOK ON NAVIGATION AND NAUTICAL ASTRONOMY. By J. GILL, F.R.A.S., late Head Master of the Liverpool Corporation Nautical College. 8vo., 10s. 6d.

GOODWIN.—AZIMUTH TABLES FOR THE HIGHER DECLINATIONS. (Limits of Declination 24° to 30° , both inclusive.) Between the Parallels of Latitude 0° and 60° . With Examples of the Use of the Tables in English and French. By H. B. GOODWIN, Naval Instructor, Royal Navy. Royal 8vo., 7s. 6d.

HERSCHEL.—OUTLINES OF ASTRONOMY. By Sir JOHN F. W. HERSCHEL, Bart., K.H., etc. With 9 Plates and numerous Diagrams. 8vo., 12s.

LAUGHTON.—AN INTRODUCTION TO THE PRACTICAL AND THEORETICAL STUDY OF NAUTICAL SURVEYING. By JOHN KNOX LAUGHTON, M.A., F.R.A.S. With 35 Diagrams. Crown 8vo., 6s.

LOWELL.—MARS. By PERCIVAL LOWELL, Fellow American Academy, Member Royal Asiatic Society, Great Britain and Ireland, etc. With 24 Plates. 8vo., 12s. 6d.

MARTIN.—NAVIGATION AND NAUTICAL ASTRONOMY. Compiled by Staff Commander W. R. MARTIN, R.N. Royal 8vo., 18s.

MERRIFIELD.—A TREATISE ON NAVIGATION. For the Use of Students. By J. MERRIFIELD, LL.D., F.R.A.S., F.M.S. With Charts and Diagrams. Crown 8vo., 5s.

PARKER.—ELEMENTS OF ASTRONOMY. With Numerous Examples and Examination Papers. By GEORGE W. PARKER, M.A., of Trinity College, Dublin. With 84 Diagrams. 8vo., 5s. 6d. net.

WEBB.—CELESTIAL OBJECTS FOR COMMON TELESCOPES. By the Rev. T. W. WEBB, M.A., F.R.A.S. Fifth Edition, Revised and greatly Enlarged by the Rev. T. E. ESPIN, M.A., F.R.A.S. (Two Volumes.) Vol. I., with Portrait and a Reminiscence of the Author, 2 Plates, and numerous Illustrations. Crown 8vo., 6s. Vol. II., with numerous Illustrations. Crown 8vo., 6s. 6d.

WORKS BY RICHARD A. PROCTOR.

THE MOON: Her Motions, Aspect, Scenery, and Physical Condition. With many Plates and Charts, Wood Engravings, and 2 Lunar Photographs. Crown 8vo., 3s. 6d.

OTHER WORLDS THAN OURS: the Plurality of Worlds Studied Under the Light of Recent Scientific Researches. With 14 Illustrations; Map, Charts, etc. Crown 8vo., 3s. 6d.

OUR PLACE AMONG INFINITIES: a Series of Essays contrasting our Little Abode in Space and Time with the Infinities around us. Crown 8vo., 3s. 6d.

MYTHS AND MARVELS OF ASTRONOMY. Crown 8vo., 3s. 6d.

LIGHT SCIENCE FOR LEISURE HOURS: Familiar Essays on Scientific Subjects, Natural Phenomena, etc. Crown 8vo., 3s. 6d.

THE ORBS AROUND US; Essays on the Moon and Planets, Meteors and Comets, the Sun and Coloured Pairs of Suns. Crown 8vo., 3s. 6d.

THE EXPANSE OF HEAVEN: Essays on the Wonders of the Firmament. Crown 8vo., 3s. 6d.

OTHER SUNS THAN OURS: a Series of Essays on Suns—Old, Young, and Dead. With other Science Gleanings. Two Essays on Whist, and Correspondence with Sir John Herschel. With 9 Star-Maps and Diagrams. Crown 8vo., 3s. 6d.

HALF-HOURS WITH THE TELESCOPE: a Popular Guide to the Use of the Telescope as a means of Amusement and Instruction. With 7 Plates. Fcp. 8vo., 2s. 6d.

NEW STAR ATLAS FOR THE LIBRARY, the School, and the Observatory, in Twelve Circular Maps (with Two Index-Plates). With an Introduction on the Study of the Stars. Illustrated by 9 Diagrams. Cr. 8vo., 5s.

THE SOUTHERN SKIES: a Plain and Easy Guide to the Constellations of the Southern Hemisphere. Showing in 12 Maps the position of the principal Star-Groups night after night throughout the year. With an Introduction and a separate Explanation of each Map. True for every Year. 4to., 5s.

HALF-HOURS WITH THE STARS: a Plain and Easy Guide to the Knowledge of the Constellations. Showing in 12 Maps the position of the principal Star-Groups night after night throughout the year. With Introduction and a separate Explanation of each Map. True for every Year. 4to., 3s. net.

LARGER STAR ATLAS FOR OBSERVERS AND STUDENTS. In Twelve Circular Maps, showing 6000 Stars, 1500 Double Stars, Nebulæ, etc. With 2 Index-Plates. Folio, 15s.

OVER.

WORKS BY RICHARD A. PROCTOR—Continued.

THE STARS IN THEIR SEASONS: an Easy Guide to a Knowledge of the Star-Groups. In 12 Large Maps. Imperial 8vo., 5s.

ROUGH WAYS MADE SMOOTH. Familiar Essays on Scientific Subjects. Crown 8vo., 3s. 6d.

PLEASANT WAYS IN SCIENCE. Crown 8vo., 3s. 6d.

NATURE STUDIES. By R. A. PROCTOR, GRANT ALLEN, A. WILSON, T. FOSTER, and E. CLODD. Crown 8vo., 3s. 6d.

LEISURE READINGS. By R. A. PROCTOR, E. CLODD, A. WILSON, T. FOSTER, and A. C. RANYARD. Crown 8vo., 3s. 6d.

PHYSIOGRAPHY AND GEOLOGY.

BIRD.—Works by CHARLES BIRD, B.A.

ELEMENTARY GEOLOGY. With Geological Map of the British Isles, and 247 Illustrations. Crown 8vo., 2s. 6d.

ADVANCED GEOLOGY. A Manual for Students in Advanced Classes and for General Readers. With over 300 Illustrations, a Geological Map of the British Isles (coloured), and a set of Questions for Examination. Crown 8vo., 7s. 6d.

GREEN.—**PHYSICAL GEOLOGY FOR STUDENTS AND GENERAL READERS.** By A. H. GREEN, M.A., F.G.S. With 236 Illustrations. 8vo., 21s.

MORGAN.—Works by ALEX. MORGAN, M.A., D.Sc., F.R.S.E.

ELEMENTARY PHYSIOGRAPHY. Treated Experimentally. With 4 Maps and 243 Diagrams. Crown 8vo., 2s. 6d.

ADVANCED PHYSIOGRAPHY. With 215 Illustrations. Crown 8vo., 4s. 6d.

THORNTON.—Works by J. THORNTON, M.A.

ELEMENTARY PRACTICAL PHYSIOGRAPHY.

Part I. With 215 Illustrations. Crown 8vo., 2s. 6d.

Part II. With 98 Illustrations. Crown 8vo., 2s. 6d.

ELEMENTARY PHYSIOGRAPHY: an Introduction to the Study of Nature. With 13 Maps and 295 Illustrations. With Appendix on Astronomical Instruments and Measurements. Crown 8vo., 2s. 6d.

ADVANCED PHYSIOGRAPHY. With 11 Maps and 255 Illustrations. Crown 8vo., 4s. 6d.

NATURAL HISTORY AND GENERAL SCIENCE.

BEDDARD.—THE STRUCTURE AND CLASSIFICATION OF BIRDS. By FRANK E. BEDDARD, M.A., F.R.S., Prosecutor and Vice-Secretary of the Zoological Society of London. With 252 Illus. 8vo., 21s. net.

FURNEAUX.—Works by WILLIAM FURNEAUX, F.R.G.S.

THE OUTDOOR WORLD; or, The Young Collector's Handbook. With 18 Plates, 16 of which are coloured, and 549 Illustrations in the Text. Crown 8vo., 6s. net.

LIFE IN PONDS AND STREAMS. With 8 Coloured Plates and 331 Illustrations in the Text. Crown 8vo., 6s. net.

BUTTERFLIES AND MOTHS (British). With 12 Coloured Plates and 241 Illustrations in the Text. Crown 8vo., 6s. net.

HUDSON.—BRITISH BIRDS. By W. H. HUDSON, C.M.Z.S. With 8 Coloured Plates from Original Drawings by A. THORBURN, and 8 Plates and 100 Figures by C. E. LODGE, and 3 Illustrations from Photographs. Crown 8vo., 6s. net.

MILLAIS.—THE NATURAL HISTORY OF THE BRITISH SURFACE-FEEDING DUCKS. By JOHN GUILLE MILLAIS, F.Z.S., etc. With 6 Photogravures and 66 Plates (41 in colours) from Drawings by the Author ARCHIBALD THORBURN, and from Photographs. Royal 4to., £6 6s. net.

NANSEN.—THE NORWEGIAN NORTH POLAR EXPEDITION, 1893-1896: Scientific Results. Edited by FRIDTJOF NANSEN. Volume I. With 44 Plates and numerous Illustrations in the Text. Demy 4to., 40s. net.

CONTENTS: The *Fram*—The Jurassic Fauna of Cape Flora. With a Geological Sketch of Cape Flora and its Neighbourhood—Fossil Plants from Franz Josef Land—An Account of the Birds—Crustacea.

Volume II. With 2 Charts and 17 Plates. Demy 4to., 30s. net.

CONTENTS: Astronomical Observations—Terrestrial Magnetism—Results of the Pendulum—Observations and some Remarks on the Constitution of the Earth's Crust.

Volume III. With 33 Plates. Demy 4to., 32s. net.

CONTENTS: The Oceanography of the North Polar Basin—On Hydrometers and the Surface Tension of Liquids.

STANLEY.—A FAMILIAR HISTORY OF BIRDS. By E. STANLEY, D.D., formerly Bishop of Norwich. With 160 Illustrations. Crown 8vo., 3s. 6d

MANUFACTURES, TECHNOLOGY, ETC.

BELL.—JACQUARD WEAVING AND DESIGNING. By F. T. BELL. With 199 Diagrams. 8vo., 12s. net.

CROSS AND BEVAN.—Works by C. F. CROSS and E. J. BEVAN.

CELLULOSE: an Outline of the Chemistry of the Structural Elements of Plants. With reference to their Natural History and Industrial Uses. (C. F. CROSS, E. J. BEVAN and C. BEADLE.) With 14 Plates. Crown 8vo., 12s. net.

RESEARCHES ON CELLULOSE, 1895-1900. Crown 8vo., 6s. net.

MANUFACTURES, TECHNOLOGY, ETC.—Continued.

MORRIS AND WILKINSON.—THE ELEMENTS OF COTTON SPINNING. By JOHN MORRIS and F. WILKINSON. With a Preface by Sir B. A. DOBSON, C.E., M.I.M.E. With 169 Diagrams and Illustrations. Crown 8vo., 7s. 6d. net.

RICHARDS.—BRICKLAYING AND BRICK-CUTTING. By H. W. RICHARDS, Examiner in Brickwork and Masonry to the City and Guilds of London Institute, Head of Building Trades Department, Northern Polytechnic Institute, London, N. With over 200 Illustrations. Med. 8vo., 3s. 6d.

TAYLOR.—COTTON WEAVING AND DESIGNING. By JOHN T. TAYLOR. With 373 Diagrams. Crown 8vo., 7s. 6d. net.

WATTS.—AN INTRODUCTORY MANUAL FOR SUGAR GROWERS. By FRANCIS WATTS, F.C.S., F.I.C. With 20 Illustrations. Crown 8vo., 6s.

HEALTH AND HYGIENE.

ASHBY.—HEALTH IN THE NURSERY. By HENRY ASHBY, M.D., F.R.C.P. With 25 Illustrations. Crown 8vo., 3s. net.

BUCKTON.—HEALTH IN THE HOUSE. By Mrs. C. M. BUCKTON. With 41 Woodcuts and Diagrams. Crown 8vo., 2s.

CORFIELD.—THE LAWS OF HEALTH. By W. H. CORFIELD, M.A., M.D. Fcp. 8vo., 1s. 6d.

FURNEAUX.—ELEMENTARY PRACTICAL HYGIENE.—Section I. By WILLIAM S. FURNEAUX. With 146 Illustrations. Cr. 8vo., 2s. 6d.

NOTTER AND FIRTH.—Works by J. L. NOTTER, M.A., M.D., and R. H. FIRTH, F.R.C.S.

HYGIENE. With 95 Illustrations. Crown 8vo., 3s. 6d.

PRACTICAL DOMESTIC HYGIENE. With 83 Illustrations. Crown 8vo., 2s. 6d.

POORE.—Works by GEORGE VIVIAN POORE, M.D.

ESSAYS ON RURAL HYGIENE. Crown 8vo., 6s. 6d.

THE DWELLING-HOUSE. With 36 Illustrations. Crown 8vo., 3s. 6d.

THE EARTH IN RELATION TO THE PRESERVATION AND DESTRUCTION OF CONTAGIA: being the Milroy Lectures delivered at the Royal College of Physicians in 1899, together with other Papers on Sanitation. With 13 Illustrations. Crown 8vo., 5s.

WILSON.—A MANUAL OF HEALTH-SCIENCE. By ANDREW WILSON, F.R.S.E., F.L.S., etc. With 74 Illustrations. Crown 8vo., 2s. 6d.

MEDICINE AND SURGERY.

ASHBY AND WRIGHT.—THE DISEASES OF CHILDREN, MEDICAL AND SURGICAL. By HENRY ASHBY, M.D., Lond., F.R.C.P., Physician to the General Hospital for Sick Children, Manchester; and G. A. WRIGHT, B.A., M.B. Oxon., F.R.C.S., Eng., Assistant-Surgeon to the Manchester Royal Infirmary, and Surgeon to the Children's Hospital. Enlarged and Improved Edition. With 192 Illustrations. 8vo., 25s.

BENNETT.—Works by SIR WILLIAM BENNETT, K.C.V.O., F.R.C.S., Surgeon to St. George's Hospital; Member of the Board of Examiners, Royal College of Surgeons of England.

CLINICAL LECTURES ON VARICOSE VEINS OF THE LOWER EXTREMITIES. With 3 Plates. 8vo., 6s.

ON VARICOCELE; A PRACTICAL TREATISE. With 4 Tables and a Diagram. 8vo., 5s.

CLINICAL LECTURES ON ABDOMINAL HERNIA: chiefly in relation to Treatment, including the Radical Cure. With 12 Diagrams in the Text. 8vo., 8s. 6d.

ON VARIX, ITS CAUSES AND TREATMENT, WITH ESPECIAL REFERENCE TO THROMBOSIS. 8vo., 3s. 6d.

THE PRESENT POSITION OF THE TREATMENT OF SIMPLE FRACTURES OF THE LIMBS. 8vo., 2s. 6d.

LECTURES ON THE USE OF MASSAGE AND EARLY PASSIVE MOVEMENTS IN RECENT FRACTURES AND OTHER COMMON SURGICAL INJURIES: The Treatment of Internal Derangements of the Knee Joint and Management of Stiff Joints. With 17 Illustrations. 8vo., 6s.

BENTLEY.—A TEXT-BOOK OF ORGANIC MATERIA MEDICA. Comprising a Description of the Vegetable and Animal Drugs of the British Pharmacopœia, with some others in common use. Arranged Systematically, and Especially Designed for Students. By ROBERT BENTLEY, M.R.C.S. Eng., F.L.S. With 62 Illustrations on Wood. Crown 8vo., 7s. 6d.

CABOT.—A GUIDE TO THE CLINICAL EXAMINATION OF THE BLOOD FOR DIAGNOSTIC PURPOSES. By RICHARD C. CABOT, M.D., Physician to Out-patients, Massachusetts General Hospital. With 3 Coloured Plates and 28 Illustrations in the Text. 8vo., 16s.

CARR, PICK, DORAN, AND DUNCAN.—THE PRACTITIONER'S GUIDE. By J. WALTER CARR, M.D. (Lond.), F.R.C.P.; T. PICKERING PICK, F.R.C.S.; ALBAN H. G. DORAN, F.R.C.S.; ANDREW DUNCAN, M.D., B.Sc. (Lond.), F.R.C.S., M.R.C.P. 8vo., 21s. net.

CELLI.—MALARIA, ACCORDING TO THE NEW RESEARCHES. By Prof. ANGELO CELLI, Director of the Institute of Hygiene, University of Rome. Translated from the Second Italian Edition by JOHN JOSEPH EYRE, M.R.C.P., L.R.C.S. Ireland, D.P.H. Cambridge. With an Introduction by Dr. PATRICK MANSON, Medical Adviser to the Colonial Office. 8vo., 10s. 6d.

MEDICINE AND SURGERY—Continued.

CHEYNE AND BURGHARD.—A MANUAL OF SURGICAL TREATMENT. By W. WATSON CHEYNE, C.B., M.B., F.R.C.S., F.R.S., Professor of Surgery in King's College, London, Surgeon to King's College Hospital, etc.; and F. F. BURGHARD, M.D. and M.S., F.R.C.S., Teacher of Practical Surgery in King's College, London, Surgeon to King's College, Hospital (Lond.), etc.

Part I. The Treatment of General Surgical Diseases, including Inflammation, Suppuration, Ulceration, Gangrene, Wounds and their Complications, Infective Diseases and Tumours; the Administration of Anæsthetics. With 66 Illustrations. Royal 8vo., 10s. 6d.

Part II. The Treatment of the Surgical Affections of the Tissues, including the Skin and Subcutaneous Tissues, the Nails, the Lymphatic Vessels and Glands, the Fasciæ, Bursæ, Muscles, Tendons and Tendon-sheaths, Nerves, Arteries and Veins. Deformities. With 141 Illustrations. Royal 8vo., 14s.

Part III. The Treatment of the Surgical Affections of the Bones. Amputations. With 100 Illustrations. Royal 8vo., 12s.

Part IV. The Treatment of the Surgical Affections of the Joints (including Excisions) and the Spine. With 138 Illustrations. Royal 8vo., 14s.

Part V. The Treatment of the Surgical Affections of the Head, Face, Jaws, Lips, Larynx and Trachea; and the Intrinsic Diseases of the Nose, Ear and Larynx, by H. LAMBERT LACK, M.D. (Lond.), F.R.C.S., Surgeon to the Hospital for Diseases of the Throat, Golden Square, and to the Throat and Ear Department, The Children's Hospital, Paddington Green. With 145 Illustrations. Royal 8vo., 18s.

Part VI. Section I. The Treatment of the Surgical Affections of the Tongue and Floor of the Mouth, the Pharynx, Neck, Oesophagus, Stomach and Intestines. With 124 Illustrations. Royal 8vo., 18s.

Section II. The Treatment of the Surgical Affections of the Rectum, Liver, Spleen, Pancreas, Throat, Breast and Genito-urinary Organs. With Illustrations. *[In preparation.]*

CLARKE.—POST-MORTEM EXAMINATIONS IN MEDICO-LEGAL AND ORDINARY CASES. With Special Chapters on the Legal Aspects of Post-mortems, and on Certificates of Death. By J. JACKSON CLARKE, M.B. Lond., F.R.C.S., Assistant Surgeon at the North-west London and City Orthopædic Hospitals, etc. Fcp. 8vo., 2s. 6d.

COATS.—A MANUAL OF PATHOLOGY. By JOSEPH COATS, M.D., late Professor of Pathology in the University of Glasgow. Fourth Edition. Revised throughout and Edited by LEWIS R. SUTHERLAND, M.D., Professor of Pathology, University of St. Andrews. With 490 Illustrations. 8vo., 31s. 6d.

COOKE.—Works by THOMAS COOKE, F.R.C.S. Eng., B.A., B.Sc., M.D., Paris.

TABLETS OF ANATOMY. Being a Synopsis of Demonstrations given in the Westminster Hospital Medical School. Eleventh Edition in Three Parts, thoroughly brought up to date, and with over 700 Illustrations from all the best Sources, British and Foreign. Post 4to.

Part I. The Bones. 7s. 6d. net.

Part II. Limbs, Abdomen, Pelvis. 10s. 6d. net.

Part III. Head and Neck, Thorax, Brain. 10s. 6d. net.

MEDICINE AND SURGERY—Continued.

COOKE.—Works by THOMAS COOKE (*continued*).

APHORISMS IN APPLIED ANATOMY AND OPERATIVE SURGERY. Including 100 Typical *vivæ voce* Questions on Surface Marking, etc. Crown 8vo., 3s. 6d.

DAKIN.—A HANDBOOK OF MIDWIFERY. By WILLIAM RADFORD DAKIN, M.D., F.R.C.P., Obstetric Physician and Lecturer on Midwifery at St. George's Hospital, etc. With 394 Illustrations. Large crown 8vo., 18s.

DICKINSON.—Works by W. HOWSHIP DICKINSON, M.D. Cantab., F.R.C.P.

ON RENAL AND URINARY AFFECTIONS. With 12 Plates and 122 Woodcuts. Three Parts. 8vo., £3 4s. 6d.

THE TONGUE AS AN INDICATION OF DISEASE: being the Lumleian Lectures delivered March, 1888 8vo., 7s. 6d.

OCCASIONAL PAPERS ON MEDICAL SUBJECTS, 1855-1896. 8vo., 12s.

MEDICINE OLD AND NEW. An Address Delivered on the Occasion of the Opening of the Winter Session, 1899-1900, at St. George's Hospital Medical School, on 2nd October, 1899. Crown 8vo., 2s. 6d.

DUCKWORTH.—Works by SIR DYCE DUCKWORTH, M.D., LL.D., Fellow and Treasurer of the Royal College of Physicians, etc.

THE SEQUELS OF DISEASE: being the Lumleian Lectures, 1896. 8vo., 10s. 6d.

THE INFLUENCE OF CHARACTER AND RIGHT JUDGMENT IN MEDICINE: the Harveian Oration, 1898. Post 4to. 2s. 6d.

ERICHSEN.—THE SCIENCE AND ART OF SURGERY; a Treatise on Surgical Injuries, Diseases, and Operations. By Sir JOHN ERIC ERICHSEN, Bart., F.R.S., LL.D. Edin., Hon. M.Ch. and F.R.C.S. Ireland. Illustrated by nearly 1000 Engravings on Wood. 2 vols. Royal 8vo., 48s.

FOWLER AND GODLEE.—THE DISEASES OF THE LUNGS. By JAMES KINGSTON FOWLER, M.A., M.D., F.R.C.P., Physician to the Middlesex Hospital and to the Hospital for Consumption and Diseases of the Chest, Brompton, etc.; and RICKMAN JOHN GODLEE, Honorary Surgeon in Ordinary to His Majesty, M.S., F.R.C.S., Fellow and Professor of Clinical Surgery, University College, London, etc. With 160 Illustrations. 8vo., 25s.

MEDICINE AND SURGERY—Continued.

GARROD.—Works by SIR ALFRED BARING GARROD, M.D., F.R.S., etc.

A TREATISE ON GOUT AND RHEUMATIC GOUT (RHEUMATOID ARTHRITIS). With 6 Plates, comprising 21 Figures (14 Coloured), and 27 Illustrations engraved on Wood. 8vo., 21s.

THE ESSENTIALS OF MATERIA MEDICA AND THERAPEUTICS. Crown 8vo., 12s. 6d.

GOADBY.—THE MYCOLOGY OF THE MOUTH : a Text-Book of Oral Bacteria. By KENNETH W. GOADBY, L.D.S. (Eng.), D.P.H. (Camb.), L.R.C.P., M.R.C.S., Bacteriologist and Lecturer on Bacteriology, National Dental Hospital, etc. With numerous Illustrations. 8vo.

GOODSALL AND MILES.—DISEASES OF THE ANUS AND RECTUM. By D. H. GOODSALL, F.R.C.S., Senior Surgeon, Metropolitan Hospital; Senior Surgeon, St. Mark's Hospital; and W. ERNEST MILES, F.R.C.S., Assistant Surgeon to the Cancer Hospital, Surgeon (out-patients), to the Gordon Hospital, etc. (In Two Parts.) Part I. With 91 Illustrations. 8vo., 7s. 6d. net.

GRAY.—ANATOMY, DESCRIPTIVE AND SURGICAL. By HENRY GRAY, F.R.S., late Lecturer on Anatomy at St. George's Hospital Medical School. The Fifteenth Edition Enlarged, edited by T. PICKERING PICK, F.R.C.S., Consulting Surgeon to St. George's Hospital, etc., and by ROBERT HOWDEN, M.A., M.B., C.M., Professor of Anatomy in the University of Durham, etc. With 772 Illustrations, a large proportion of which are Coloured, the Arteries being coloured red, the Veins blue, and the Nerves yellow. The attachments of the muscles to the bones, in the section on Osteology, are also shown in coloured outline. Royal 8vo., 32s. net.

HALLIBURTON.—Works by W. D. HALLIBURTON, M.D., F.R.S., Professor of Physiology in King's College, London.

A TEXT-BOOK OF CHEMICAL PHYSIOLOGY AND PATHOLOGY. With 104 Illustrations. 8vo., 28s.

ESSENTIALS OF CHEMICAL PHYSIOLOGY. With 77 Illustrations. 8vo., 5s.

LANG.—THE METHODICAL EXAMINATION OF THE EYE. Being Part I. of a Guide to the Practice of Ophthalmology for Students and Practitioners. By WILLIAM LANG, F.R.C.S. Eng., Surgeon to the Royal London Ophthalmic Hospital, Moorfields, etc. With 15 Illustrations. Crown 8vo., 3s. 6d.

LUFF.—TEXT-BOOK OF FORENSIC MEDICINE AND TOXICOLOGY. By ARTHUR P. LUFF, M.D., B.Sc. (Lond.), Physician in Charge of Out-Patients and Lecturer on Medical Jurisprudence and Toxicology in St. Mary's Hospital. With 13 full-page Plates (1 in colours) and 33 Illustrations in the Text. 2 vols. Crown 8vo., 24s.

MEDICINE AND SURGERY—Continued.

LIVERPOOL UNIVERSITY PRESS PUBLICATIONS, THE.

The Thomson Yates Laboratories Reports. Physiology; Pathology; Bacteriology; Tropical Medicine; Hygiene. Edited by RUPERT BOYCE and C. S. SHERRINGTON. With Plates and Illustrations in the text. Demy 4to. Vol I., 1898-9, 10s. 6d.; Vol. II., 1898-9, 25s.; Vol. III., Part I., 1900, 7s. 6d.; Vol. III., Part II., 1901, 12s. 6d.; Vol. IV., Part I., 1901, 20s.; Vol. IV., Part II., 1902, 21s.

THE LIVERPOOL SCHOOL OF TROPICAL MEDICINE MEMOIRS.

With Plates and Illustrations in the text. Demy 4to.

- I. Malarial Fever: Its Cause, Prevention and Treatment. Containing full details for the use of Travellers, Sportsmen, Soldiers, and Residents in Malarious Places. By RONALD ROSS, C.B., F.R.S., F.R.C.S. Ninth Edition, Revised and Enlarged. With Frontispiece. 8vo., 2s. 6d.
- II. Report of the Malaria Expedition to West Africa, August, 1899. By RONALD ROSS, C.B., F.R.S., F.R.C.S., H. E. ANNETT, M.D., D.P.H. and E. E. AUSTEN. With Supplementary Reports by Major G. M. GILES, M.B. and R. FIELDING-OULD, M.B. 21s.
- III. Report of the Malaria Expedition to Nigeria. Part I. Malarial Fever, etc. By H. E. ANNETT, M.D., J. EVERETT DUTTON, M.B. and J. H. ELLIOTT, M.D. 10s. 6d.
- IV. Report of the Malaria Expedition to Nigeria. Part II. Filariasis. By H. E. ANNETT, M.D., J. EVERETT DUTTON, M.B. and J. H. ELLIOTT, M.D. 15s.
- V. Part I. First Progress Report of the Campaign against Mosquitoes in Sierra Leone (1901). By RONALD ROSS, C.B., F.R.C.S., F.R.S. 8vo., 1s.
- VII. Report of the Yellow Fever Expedition to Pará (1900). By H. E. DURHAM, M.B., F.R.C.S., and the late WALTER MYERS, M.B. 4to., 7s. 6d.


MISCELLANEOUS.

Notes on Sanitary Conditions obtaining in Pará. By the MEMBERS OF THE YELLOW FEVER EXPEDITION. 8vo., 1s.

PAGET.—Edited by STEPHEN PAGET.

SELECTED ESSAYS AND ADDRESSES. By Sir JAMES PAGET. 8vo., 12s. 6d. net.

MEMOIRS AND LETTERS OF SIR JAMES PAGET, BART.,

 F.R.S., D.C.L., late Sergeant-Surgeon to Her Majesty Queen Victoria. With 6 Portraits (3 Photogravures) and 4 other Illustrations. 8vo., 12s. 6d. net.

PICK.—**SURGERY:** a Treatise for Students and Practitioners.

By T. PICKERING PICK, Consulting Surgeon to St. George's Hospital; Senior Surgeon to the Victoria Hospital for Children; H.M. Inspector of Anatomy in England and Wales. With 441 Illustrations. Medium 8vo., 25s.

POOLE.—**COOKERY FOR THE DIABETIC.** By W. H. and

Mrs. POOLE. With Preface by Dr. PAVY. Fcap. 8vo., 2s. 6d.

PROBYN-WILLIAMS.—**A PRACTICAL GUIDE TO THE**

ADMINISTRATION OF ANÆSTHETICS. By R. J. PROBYN-WILLIAMS, M.D., Anæsthetist and Instructor in Anæsthetics at the London Hospital; Lecturer in Anæsthetics at the London Hospital Medical College, etc. With 34 Illustrations. Crown 8vo., 4s. 6d. net.

MEDICINE AND SURGERY—Continued.

QUAIN.—**QUAIN'S (SIR RICHARD) DICTIONARY OF MEDICINE.** By Various Writers. Third Edition. Edited by H. MONTAGUE MURRAY, M.D., F.R.C.P., Joint Lecturer on Medicine, Charing Cross Medical School, and Physician to Out-Patients, Charing Cross Hospital; assisted by JOHN HAROLD, M.B., B.Ch., B.A.O., Physician to St. John's and St. Elizabeth's Hospital; and W. CECIL BOSANQUET, M.A., M.D., M.R.C.P., Physician to Out-Patients, Victoria Hospital for Children, Chelsea. With 21 Plates (14 in Colour) and numerous Illustrations in the Text. 8vo., 21s. net, buckram; or 30s. net, half-morocco.

QUAIN.—**QUAIN'S (JONES) ELEMENTS OF ANATOMY.** The Tenth Edition. Edited by EDWARD ALBERT SCHÄFER, F.R.S., Professor of Physiology in the University of Edinburgh; and GEORGE DANCER THANE, Professor of Anatomy in University College, London.

VOL. I., PART I. EMBRYOLOGY. By E. A. SCHÄFER, F.R.S. With 200 Illustrations. Royal 8vo., 9s.

VOL. I., PART II. GENERAL ANATOMY OR HISTOLOGY. By E. A. SCHÄFER, F.R.S. With 291 Illustrations. Royal 8vo., 12s. 6d.

VOL. II., PART I. OSTEOLOGY—ARTHROLOGY. By G. D. THANE. With 224 Illus. Royal 8vo., 11s.

VOL. II., PART II. MYOLOGY—ANGEIOLOGY. By G. D. THANE. With 199 Illustrations. Royal 8vo., 16s.

VOL. III., PART I. THE SPINAL CORD AND BRAIN. By E. A. SCHÄFER, F.R.S. With 139 Illustrations. Royal 8vo., 12s. 6d.

VOL. III., PART II. THE NERVES. By G. D. THANE. With 102 Illustrations. Royal 8vo., 9s.

VOL. III., PART III. THE ORGANS OF THE SENSES. By E. A. SCHÄFER, F.R.S. With 178 Illustrations. Royal 8vo., 9s.

VOL. III., PART IV. SPLANCHNOLOGY. By E. A. SCHÄFER, F.R.S., and JOHNSON SYMINGTON, M.D. With 337 Illustrations. Royal 8vo., 16s.

APPENDIX. SUPERFICIAL AND SURGICAL ANATOMY. By Professor G. D. THANE and Professor R. J. GODLEE, M.S. With 29 Illustrations. Royal 8vo., 6s. 6d.

SCHÄFER.—Works by E. A. SCHÄFER, F.R.S., Professor of Physiology in the University of Edinburgh.

THE ESSENTIALS OF HISTOLOGY. Descriptive and Practical. For the Use of Students. With 463 Illustrations. 8vo., 9s. net.

DIRECTIONS FOR CLASS WORK IN PRACTICAL PHYSIOLOGY: Elementary Physiology of Muscle and Nerve and of the Vascular and Nervous Systems. With 48 Diagrams and 24 pages of plain paper at end for Notes. 8vo., 3s. net.

SMALE AND COLYER.—**DISEASES AND INJURIES OF THE TEETH,** including Pathology and Treatment. By MORTON SMALE, M.R.C.S., L.S.A., L.D.S., Dental Surgeon to St. Mary's Hospital, Dean of the School, Dental Hospital of London, etc.; and J. F. COLYER, L.R.C.P., M.R.C.S., L.D.S., Dental Surgeon to Charing Cross Hospital and to the Dental Hospital of London. Second Edition Revised and Enlarged by J. F. COLYER. With 640 Illustrations. Large crown 8vo., 21s. net.

MEDICINE AND SURGERY—Continued.

SMITH (H. F.).—THE HANDBOOK FOR MIDWIVES. By HENRY FLY SMITH, B.A., M.B. Oxon., M.R.C.S. 41 Woodcuts. Cr. 8vo., 5s.

STEVENSON.—WOUNDS IN WAR: the Mechanism of their Production and their Treatment. By Surgeon-Colonel W. F. STEVENSON (Army Medical Staff), A.B., M.B., M.Ch. Dublin University, Professor of Military Surgery, Army Medical School, Netley. With 86 Illustrations. 8vo., 18s.

TAPPEINER. — INTRODUCTION TO CHEMICAL METHODS OF CLINICAL DIAGNOSIS. By Dr. H. TAPPEINER, Professor of Pharmacology and Principal of the Pharmacological Institute of the University of Munich. Translated by EDMOND J. MCWEENEY, M.A., M.D. (Royal Univ. of Ireland), L.R.C.P.I., etc. Crown 8vo., 3s. 6d.

WALLER.—Works by AUGUSTUS D. WALLER, M.D., Lecturer on Physiology at St. Mary's Hospital Medical School, London; late External Examiner at the Victorian University.

AN INTRODUCTION TO HUMAN PHYSIOLOGY. Third Edition, Revised. With 314 Illustrations. 8vo., 18s.

LECTURES ON PHYSIOLOGY. First Series. On Animal Electricity. 8vo., 5s. net.

VETERINARY MEDICINE, ETC.

FITZWYGRAM.—HORSES AND STABLES. By Lieut.-General Sir F. FITZWYGRAM, Bart. With 56 pages of Illustrations. 8vo., 3s. net.

STEEL.—Works by JOHN HENRY STEEL, F.R.C.V.S., F.Z.S., A.V.D., late Professor of Veterinary Science and Principal of Bombay Veterinary College.

A TREATISE ON THE DISEASES OF THE DOG; being a Manual of Canine Pathology. Especially adapted for the use of Veterinary Practitioners and Students. With 88 Illustrations. 8vo., 10s 6d.

A TREATISE ON THE DISEASES OF THE OX; being a Manual of Bovine Pathology. Especially adapted for the use of Veterinary Practitioners and Students. With 2 Plates and 117 Woodcuts. 8vo. 15s.

A TREATISE ON THE DISEASES OF THE SHEEP; being a Manual of Ovine Pathology for the use of Veterinary Practitioners and Students. With Coloured Plate and 99 Woodcuts. 8vo., 12s.

YOUATT.—Works by WILLIAM YOUATT.

THE HORSE. With 52 Wood Engravings. 8vo., 7s. 6d.

THE DOG. With 33 Wood Engravings. 8vo., 6s.

PHYSIOLOGY, BIOLOGY, ZOOLOGY, ETC.

(And see *MEDICINE AND SURGERY*, page 25.)

ASHBY.—NOTES ON PHYSIOLOGY FOR THE USE OF STUDENTS PREPARING FOR EXAMINATION. By HENRY ASHBY, M.D. Lond., F.R.C.P., Physician to the General Hospital for Sick Children, Manchester; formerly Demonstrator of Physiology, Liverpool School of Medicine. With 148 Illustrations. 18mo., 5s.

BARNETT.—THE MAKING OF THE BODY: a Children's Book on Anatomy and Physiology. By Mrs. S. A. BARNETT. With 113 Illustrations. Crown 8vo., 1s. 9d.

BEDDARD.—Works by FRANK E. BEDDARD, M.A. Oxon.
ELEMENTARY PRACTICAL ZOOLOGY. With 93 Illustrations. Crown 8vo., 2s. 6d.

THE STRUCTURE AND CLASSIFICATION OF BIRDS.
With 252 Illustrations. 8vo., 21s. net.

BIDGOOD.—A COURSE OF PRACTICAL ELEMENTARY BIOLOGY. By JOHN BIDGOOD, B.Sc., F.L.S. With 226 Illustrations. Crown 8vo., 4s. 6d.

BOSE.—RESPONSE IN THE LIVING AND NON-LIVING.
By JAGADIS CHUNDER BOSE, M.A. (Cantab.), D.Sc. (Lond.), Professor, Presidency College, Calcutta. With 117 Illustrations. 8vo., 10s. 6d.

*** This volume describes experimental investigations on animal, vegetable and inorganic substances regarding their response to stimulus. These researches show that the effects of fatigue, stimulants, depressants and poisons are alike in the organic and inorganic, and demonstrate that the response phenomena in the 'living' have been foreshadowed in the 'non-living'.*

BRODIE.—THE ESSENTIALS OF EXPERIMENTAL PHYSIOLOGY. For the Use of Students. By T. G. BRODIE, M.D., Lecturer on Physiology, St. Thomas's Hospital Medical School. With 2 Plates and 177 Illustrations in the Text. 8vo., 6s. 6d.

CHAPMAN.—THE FORAMINIFERA: An Introduction to the Study of the Protozoa. By FREDERICK CHAPMAN, A.L.S., F.R.M.S. With 14 Plates and 42 Illustrations in the Text. 8vo., 9s. net.

FURNEAUX.—HUMAN PHYSIOLOGY. By W. FURNEAUX, F.R.G.S. With 218 Illustrations. Crown 8vo., 2s. 6d.

HUDSON AND GOSSE.—THE ROTIFERA, or 'WHEEL-ANIMACULES'. By C. T. HUDSON, LL.D., and P. H. GOSSE, F.R.S. With 30 Coloured and 4 Uncoloured Plates. In 6 Parts. 4to., 10s. 6d. each. Supplement 12s. 6d. Complete in 2 vols., with Supplement, 4to., £4 4s.

MACALISTER.—Works by ALEXANDER MACALISTER, M.D.

AN INTRODUCTION TO THE SYSTEMATIC ZOOLOGY AND MORPHOLOGY OF VERTEBRATE ANIMALS. With 41 Diagrams. 8vo., 10s. 6d.

ZOOLOGY OF THE INVERTEBRATE ANIMALS. With 59 Diagrams. Fcp. 8vo., 1s. 6d.

ZOOLOGY OF THE VERTEBRATE ANIMALS. With 77 Diagrams. Fcp. 8vo., 1s. 6d.

PHYSIOLOGY, BIOLOGY, ZOOLOGY, ETC.—Continued.

MACDOUGAL.—Works by DANIEL TREMBLY MACDOUGALL, Ph.D., Director of the Laboratories of the New York Botanical Garden.

PRACTICAL TEXT-BOOK OF PLANT PHYSIOLOGY.
With 159 Illustrations. 8vo., 7s. 6d. net.

ELEMENTARY PLANT PHYSIOLOGY. With 108 Illustrations. Crown 8vo., 3s.

MOORE.—**ELEMENTARY PHYSIOLOGY.** By BENJAMIN MOORE, M.A., Lecturer on Physiology at the Charing Cross Hospital Medical School. With 125 Illustrations. Crown 8vo., 3s. 6d.

MORGAN.—**ANIMAL BIOLOGY:** an Elementary Text-Book. By C. LLOYD MORGAN, F.R.S., Principal of University College, Bristol. With 103 Illustrations. Crown 8vo., 8s. 6d.

SCHÄFER.—**DIRECTIONS FOR CLASS WORK IN PRACTICAL PHYSIOLOGY:** Elementary Physiology of Muscle and Nerve and of the Vascular and Nervous Systems. By E. A. SCHÄFER, LL.D., F.R.S., Professor of Physiology in the University of Edinburgh. With 48 Diagrams. 8vo., 3s. net.

THORNTON.—Works by JOHN THORNTON, M.A.
HUMAN PHYSIOLOGY. With 267 Illustrations, some Coloured. Crown 8vo., 6s.

ELEMENTARY BIOLOGY, Descriptive and Experimental. With numerous Illustrations. Crown 8vo., 3s. 6d.

BACTERIOLOGY.

CURTIS.—**THE ESSENTIALS OF PRACTICAL BACTERIOLOGY:** An Elementary Laboratory Book for Students and Practitioners. By H. J. CURTIS, B.S. and M.D. (Lond.), F.R.C.S. With 133 Illustrations. 8vo., 9s.

DHINGRA.—**AN INTRODUCTION TO BACTERIOLOGY.** (Specially designed for Indian Medical Students.) By M. L. DHINGRA, M.D.D.P.H.

FRANKLAND.—**MICRO-ORGANISMS IN WATER.** Together with an Account of the Bacteriological Methods involved in their Investigation. Specially designed for the use of those connected with the Sanitary Aspects of Water-Supply. By PERCY FRANKLAND, Ph.D., B.Sc. (Lond.), F.R.S., and Mrs. PERCY FRANKLAND. With 2 Plates and Numerous Diagrams. 8vo., 16s. net.

FRANKLAND.—**BACTERIA IN DAILY LIFE.** By Mrs. PERCY FRANKLAND, F.R.M.S. Crown 8vo.

GOADBY.—**THE MYCOLOGY OF THE MOUTH:** A Text-Book of Oral Bacteria. By KENNETH W. GOADBY, L.D.S. Eng., etc.; Bacteriologist and Lecturer on Bacteriology, National Dental Hospital, etc. With numerous Illustrations. 8vo.

BACTERIOLOGY—Continued.

KLÖCKER. — FERMENTATION ORGANISMS IN THE THEORY AND PRACTICE OF THE ALCOHOLIC FERMENTATION INDUSTRY, with special reference to the Construction and Work of Laboratories for the Physiology and Technology of Fermentation. By ALB. KLÖCKER. Translated by G. E. ALLAN, B.Sc., and J. H. MILLAR, F.I.C. With 146 Illustrations in the text. 8vo.

BOTANY.

AITKEN. — ELEMENTARY TEXT-BOOK OF BOTANY. By EDITH AITKEN, late Scholar of Girton College. With 400 Diagrams. Crown 8vo., 4s. 6d.

BENNETT AND MURRAY.—HANDBOOK OF CRYPTOGAMIC BOTANY. By ALFRED W. BENNETT, M.A., B.Sc., F.L.S., Lecturer on Botany at St. Thomas's Hospital; and GEORGE MURRAY, F.L.S., Keeper of Botany, British Museum. With 378 Illustrations. 8vo., 16s.

CROSS AND BEVAN.—Works by C. F. CROSS, E. J. BEVAN and C. BEADLE.

CELLULOSE: an Outline of the Chemistry of the Structural Elements of Plants. With Reference to their Natural History and Industrial Uses. With 14 Plates. Crown 8vo., 12s. net.

RESEARCHES ON CELLULOSE, 1895-1900. Cr. 8vo., 6s. net.

EDMONDS.—Works by HENRY EDMONDS, B.Sc., London.

ELEMENTARY BOTANY. With 342 Illustrations. Cr. 8vo., 2s. 6d.

BOTANY FOR BEGINNERS. With 85 Illustrations. Fcp. 8vo., 1s. 6d.

FARMER.—A PRACTICAL INTRODUCTION TO THE STUDY OF BOTANY: Flowering Plants. By J. BRETLAND FARMER, F.R.S., M.A., Professor of Botany in the Royal College of Science, London. With 121 Illustrations. Crown 8vo., 2s. 6d.

KITCHENER.—A YEAR'S BOTANY. Adapted to Home and School Use. By FRANCES A. KITCHENER. With 195 Illustrations. Cr. 8vo., 5s.

LINDLEY AND MOORE.—THE TREASURY OF BOTANY. Edited by J. LINDLEY, M.D., F.R.S., and T. MOORE, F.L.S. With 20 Steel Plates and numerous Woodcuts. Two parts. Fcp. 8vo., 12s.

McNAB.—CLASS-BOOK OF BOTANY. By W. R. McNAB. MORPHOLOGY AND PHYSIOLOGY. With 42 Diagrams. CLASSIFICATION OF PLANTS. With 118 Diagrams. Fcp. 8vo., 1s. 6d.

SORAUER.—A POPULAR TREATISE ON THE PHYSIOLOGY OF PLANTS. By Dr. PAUL SORAUER. Translated by F. E. WEISS, B.Sc., F.L.S. With 33 Illustrations. 8vo., 9s. net.

BOTANY—Continued.

THOMÉ AND BENNETT.—STRUCTURAL AND PHYSIOLOGICAL BOTANY. By OTTO WILHELM THOMÉ and by ALFRED W. BENNETT, B.Sc., F.L.S. With Coloured Map and 600 Woodcuts. Fcp. 8vo., 6s.

TUBEUF.—DISEASES OF PLANTS INDUCED BY CRYPTOGRAMIC PARASITES. Introduction to the Study of Pathogenic Fungi, Slime Fungi, Bacteria and Algæ. By Dr. KARL FREIHERR VON TUBEUF, Privatdozent in the University of Munich. English Edition by WILLIAM G. SMITH, B.Sc., Ph.D., Lecturer on Plant Physiology, University of Edinburgh. With 330 Illustrations. Royal 8vo., 18s. net.

WATTS.—A SCHOOL FLORA. For the use of Elementary Botanical Classes. By W. MARSHALL WATTS, D.Sc. Lond. Cr, 8vo., 2s. 6d.

AGRICULTURE AND GARDENING.

ADDYMAN.—AGRICULTURAL ANALYSIS. A Manual of Quantitative Analysis for Students of Agriculture. By FRANK T. ADDYMAN, B.Sc. (Lond.), F.I.C. With 49 Illustrations. Crown 8vo., 5s. net.

COLEMAN AND ADDYMAN.—PRACTICAL AGRICULTURAL CHEMISTRY. By J. BERNARD COLEMAN, A.R.C.Sc., F.I.C., and FRANK T. ADDYMAN, B.Sc. (Lond.), F.I.C. With 24 Illustrations. Crown 8vo., 1s 6d. net.

HAGGARD.—Works by H. RIDER HAGGARD.

A FARMER'S YEAR: being his Commonplace Book for 1898. With 36 Illustrations by G. LEON LITTLE and three others. Crown 8vo., 7s. 6d. net.

RURAL ENGLAND. With Agricultural Maps and numerous Illustrations from Photographs. 2 vols. 8vo.

WEATHERS.—A PRACTICAL GUIDE TO GARDEN PLANTS. Containing Descriptions of the Hardest and most Beautiful Annuals and Biennials, Hardy Herbaceous and Bulbous Perennials, Hardy Water and Bog Plants, Flowering and Ornamental Trees and Shrubs, Conifers, Hardy Ferns, Hardy Bamboos and other Ornamental Grasses; and also the best kinds of Fruit and Vegetables that may be grown in the Open Air in the British Islands, with Full and Practical Instructions as to Culture and Propagation. By JOHN WEATHERS, F.R.H.S., late Assistant Secretary to the Royal Horticultural Society, formerly of the Royal Gardens, Kew, etc. With 163 Diagrams. 8vo., 21s. net.

WEBB.—Works by HENRY J. WEBB, Ph.D., B.Sc. (Lond.).

ELEMENTARY AGRICULTURE. A Text-Book specially adapted to the requirements of the Board of Education, the Junior Examination of the Royal Agricultural Society, and other Elementary Examinations. With 34 Illustrations. Crown 8vo., 2s. 6d.

AGRICULTURE. A Manual for Advanced Science Students. With 100 Illustrations. Crown 8vo., 7s. 6d. net.

WORKS BY JOHN TYNDALL, D.C.L., LL.D., F.R.S.

LECTURES ON SOUND. With Frontispiece of Fog-Syren, and 203 other Woodcuts and Diagrams in the Text. Crown 8vo., 10s. 6d.

HEAT, A MODE OF MOTION. With 125 Woodcuts and Diagrams. Crown 8vo., 12s.

LECTURES ON LIGHT DELIVERED IN THE UNITED STATES IN 1872 AND 1873. With Portrait, Lithographic Plate, and 59 Diagrams. Crown 8vo., 5s.

FRAGMENTS OF SCIENCE: a Series of Detached Essays, Addresses, and Reviews. 2 vols. Crown 8vo., 16s.

Vol. I.—The Constitution of Nature—Radiation—On Radiant Heat in Relation to the Colour and Chemical Constitution of Bodies—New Chemical Reactions produced by Light—On Dust and Disease—Voyage to Algeria to observe the Eclipse—Niagara—The Parallel Roads of Glen Roy—Alpine Sculpture—Recent Experiments on Fog—Signals—On the Study of Physics—On Crystalline and Slaty Cleavage—On Paramagnetic and Diamagnetic Forces—Physical Basis of Solar Chemistry—Elementary Magnetism—On Force—Contributions to Molecular Physics—Life and Letters of FARADAY—The Copley Medallist of 187c—The Copley Medallist of 1871—Death by Lightning—Science and the Spirits.

Vol. II.—Reflections on Prayer and Natural Law—Miracles and Special Providences—On Prayer as a Form of Physical Energy—Vitality—Matter and Force—Scientific Materialism—An Address to Students—Scientific Use of the Imagination—The Belfast Address—Apology for the Belfast Address—The Rev. JAMES MARTINEAU and the Belfast Address—Fermentation, and its Bearings on Surgery and Medicine—Spontaneous Generation—Science and Man—Professor VIRCHOW and Evolution—The Electric Light.

NEW FRAGMENTS. Crown 8vo., 10s. 6d.

CONTENTS.—The Sabbath—Goethe's 'Farbenlehre'—Atoms, Molecules, and Ether Waves—Count Rumford—Louis Pasteur, his Life and Labours—The Rainbow and its Congeners—Address delivered at the Birkbeck Institution on October 22, 1884—Thomas Young—Life in the Alps—About Common Water—Personal Recollections of Thomas Carlyle—On Unveiling the Statue of Thomas Carlyle—On the Origin, Propagation, and Prevention of Phthisis—Old Alpine Jottings—A Morning on Alp Lusen.

ESSAYS ON THE FLOATING MATTER OF THE AIR IN RELATION TO PUTREFACTION AND INFECTION. With 24 Woodcuts. Crown 8vo., 7s. 6d.

RESEARCHES ON DIAMAGNETISM AND MAGNECRYSTALLIC ACTION; including the Question of Diamagnetic Polarity. Crown 8vo., 12s.

NOTES OF A COURSE OF NINE LECTURES ON LIGHT, delivered at the Royal Institution of Great Britain, 1869. Crown 8vo., 1s. 6d.

NOTES OF A COURSE OF SEVEN LECTURES ON ELECTRICAL PHENOMENA AND THEORIES, delivered at the Royal Institution of Great Britain, 1870. Crown 8vo., 1s. 6d.

LESSONS IN ELECTRICITY AT THE ROYAL INSTITUTION 1875-1876. With 58 Woodcuts and Diagrams. Crown 8vo., 2s. 6d.

THE GLACIERS OF THE ALPS: being a Narrative of Excursions and Ascents. An Account of the Origin and Phenomena of Glaciers, and an Exposition of the Physical Principles to which they are related. With 7 Illustrations. Crown 8vo., 6s. 6d. net.

HOURS OF EXERCISE IN THE ALPS. With 7 Illustrations. Crown 8vo., 6s. 6d. net.

FARADAY AS A DISCOVERER. Crown 8vo., 3s. 6d.

TEXT-BOOKS OF SCIENCE.

- PHOTOGRAPHY.** By Sir WILLIAM DE WIVELESIE ABNEY, K.C.B., F.R.S. With 134 Illustrations. Fcp. 8vo., 5s.
- THE STRENGTH OF MATERIAL AND STRUCTURES.** By Sir J. ANDERSON, C.E. With 66 Illustrations. Fcp. 8vo., 3s. 6d.
- RAILWAY APPLIANCES.** By Sir JOHN WOLFE BARRY, K.C.B., F.R.S., M.I.C.E. With 218 Illustrations. Fcp. 8vo., 4s. 6d.
- INTRODUCTION TO THE STUDY OF INORGANIC CHEMISTRY.** By WILLIAM ALLEN MILLER, M.D., LL.D., F.R.S. With 72 Illustrations. 3s. 6d.
- QUANTITATIVE CHEMICAL ANALYSIS.** By T. E. THORPE, C.B., F.R.S., Ph.D. With 88 Illustrations. Fcp. 8vo., 4s. 6d.
- QUALITATIVE ANALYSIS AND LABORATORY PRACTICE.** By T. E. THORPE, C.B., Ph.D., F.R.S., and M. M. PATTISON MUIR, M.A. and F.R.S.E. With Plate of Spectra and 57 Illustrations. Fcp. 8vo., 3s. 6d.
- INTRODUCTION TO THE STUDY OF CHEMICAL PHILOSOPHY.** By WILLIAM A. TILDEN, D.Sc., London, F.R.S. With Illustrations. Fcp. 8vo., 5s. With Answers to Problems. Fcp. 8vo., 5s. 6d.
- ELEMENTS OF ASTRONOMY.** By Sir R. S. BALL, LL.D., F.R.S. With 130 Illustrations. Fcp. 8vo., 6s. 6d.
- SYSTEMATIC MINERALOGY.** By HILARY BAUERMAN, F.G.S. With 373 Illustrations. Fcp. 8vo., 6s.
- DESCRIPTIVE MINERALOGY.** By HILARY BAUERMAN, F.G.S., etc. With 236 Illustrations. Fcp. 8vo., 6s.
- METALS: THEIR PROPERTIES AND TREATMENT.** By A. K. HUNTINGTON and W. G. McMILLAN. With 122 Illustrations. Fcp. 8vo., 7s. 6d.
- THEORY OF HEAT.** By J. CLERK MAXWELL, M.A., LL.D., Edin., F.R.S.S., L. & E. With 38 Illustrations. Fcp. 8vo., 4s. 6d.
- PRACTICAL PHYSICS.** By R. T. GLAZEBROOK, M.A., F.R.S., and W. N. SHAW, M.A. With 134 Illustrations. Fcp. 8vo., 7s. 6d.
- PRELIMINARY SURVEY AND ESTIMATES.** By THEODORE GRAHAM GRIBBLE, Civil Engineer. Including Elementary Astronomy, Route Surveying, Tacheometry, Curve-ranging, Graphic Mensuration, Estimates, Hydrography and Instruments. With 133 Illustrations. Fcp. 8vo., 7s. 6d.
- ALGEBRA AND TRIGONOMETRY.** By WILLIAM NATHANIEL GRIFFIN, B.D. 3s. 6d. Notes on, with Solutions of the more difficult Questions. Fcp. 8vo., 3s. 6d.
- THE STEAM ENGINE.** By GEORGE C. V. HOLMES, Secretary of the Institution of Naval Architects. With 212 Illustrations. Fcp. 8vo., 6s.
- ELECTRICITY AND MAGNETISM.** By FLEEMING JENKIN, F.R.S.S., L. & E. With 177 Illustrations. Fcp. 8vo., 3s. 6d.
- THE ART OF ELECTRO-METALLURGY.** By G. GORE, LL.D., F.R.S. With 56 Illus. Fcp. 8vo., 6s.
- TELEGRAPHY.** By Sir W. H. PREECE, K.C.B., F.R.S., M.I.C.E., and Sir J. SIVEWRIGHT, M.A., K.C.M.G. With 267 Illustrations. Fcp. 8vo., 6s.
- PHYSICAL OPTICS.** By R. T. GLAZEBROOK, M.A., F.R.S. With 183 Illustrations. Fcp. 8vo., 6s.
- TECHNICAL ARITHMETIC AND MENSURATION.** By CHARLES W. MERRIFIELD, F.R.S. 3s. 6d. Key, by the Rev. JOHN HUNTER, M.A. Fcp. 8vo., 3s. 6d.
- THE STUDY OF ROCKS.** By FRANK RUTLEY, F.G.S. With 6 Plates and 88 Illustrations. Fcp. 8vo., 4s. 6d.
- WORKSHOP APPLIANCES,** including Descriptions of some of the Machine Tools used by Engineers. By C. P. B. SHELLEY, M.I.C.E. With 323 Illustrations. Fcp. 8vo., 5s.
- ELEMENTS OF MACHINE DESIGN.** By W. CAWTHORNE UNWIN, F.R.S., B.Sc., M.I.C.E.
- PART I.** General Principles, Fastenings and Transmissive Machinery. With 345 Illustrations. Fcp. 8vo., 7s. 6d.
- PART II.** Chiefly on Engine Details. With 259 Illustrations. Fcp. 8vo., 6s.
- STRUCTURAL AND PHYSIOLOGICAL BOTANY.** By OTTO WILHELM THOMÉ, and A. W. BENNETT, M.A., B.Sc., F.L.S. With 600 Illustrations. Fcp. 8vo., 6s.
- PLANE AND SOLID GEOMETRY.** By H. W. WATSON, M.A. Fcp. 8vo., 3s. 6d.

ADVANCED SCIENCE MANUALS.

- BUILDING CONSTRUCTION.** By the Author of 'Rivington's Notes on Building Construction'. With 385 Illustrations and an Appendix of Examination Questions. Crown 8vo., 4s. 6d.
- THEORETICAL MECHANICS.** Solids, including Kinematics, Statics, and Kinetics. By A. THORNTON, M.A., F.R.A.S. With 220 Illustrations, 130 Worked Examples, and over 900 Examples from Examination Papers, etc. Crown 8vo., 4s. 6d.
- HEAT.** By MARK R. WRIGHT, Hon. Inter. B.Sc. (Lond.). With 136 Illustrations and numerous Examples and Examination Papers. Crown 8vo., 4s. 6d.
- LIGHT.** By W. J. A. EMTAGE, M.A. With 232 Illustrations. Cr. 8vo., 6s.
- MAGNETISM AND ELECTRICITY.** By ARTHUR WILLIAM POYSER, M.A. With 317 Illustrations. Crown 8vo., 4s. 6d.
- INORGANIC CHEMISTRY, THEORETICAL AND PRACTICAL.** By WILLIAM JAGO, F.C.S., F.I.C. With Plate of Spectra and 78 Woodcuts. Crown 8vo., 4s. 6d.
- GEOLOGY :** a Manual for Students in Advanced Classes and for General Readers. By CHARLES BIRD, B.A. (Lond.), F.G.S. With over 300 Illustrations, a Geological Map of the British Isles (coloured), and a set of Questions for Examination. Crown 8vo., 7s. 6d.
- HUMAN PHYSIOLOGY :** a Manual for Students in advanced Classes of the Science and Art Department. By JOHN THORNTON, M.A. With 268 Illustrations, some of which are Coloured, and a set of Questions for Examination. Crown 8vo., 6s.
- PHYSIOGRAPHY.** By JOHN THORNTON, M.A. With 11 Maps, 255 Illustrations, and Coloured Map of Ocean Deposits. Crown 8vo., 4s. 6d.
- AGRICULTURE.** By HENRY J. WEBB, Ph.D., B.Sc. With 100 Illustrations. Crown 8vo., 7s. 6d. net.
- HYGIENE.** By J. LANE NOTTER, M.A., M.D., Professor of Hygiene in the Army Medical School, Netley, Colonel, Royal Army Medical Corps; and R. H. FIRTH, F.R.C.S., late Assistant Professor of Hygiene in the Army Medical School, Netley, Major, Royal Army Medical Corps. With 95 Illustrations. Crown 8vo., 3s. 6d.

ELEMENTARY SCIENCE MANUALS.

** * Written specially to meet the requirements of the ELEMENTARY STAGE OF SCIENCE SUBJECTS as laid down in the Syllabus of the Directorate of the BOARD OF EDUCATION.*

- PRACTICAL, PLANE, AND SOLID GEOMETRY,** including Graphic Arithmetic. By I. H. MORRIS. Fully Illustrated with Drawings. Crown 8vo., 2s. 6d.
- GEOMETRICAL DRAWING FOR ART STUDENTS.** Embracing Plane Geometry and its Applications, the Use of Scales, and the Plans and Elevations of Solids. By I. H. MORRIS. Crown 8vo., 2s.
- TEXT-BOOK ON PRACTICAL, SOLID, OR DESCRIPTIVE GEOMETRY.** By DAVID ALLAN LOW (Whitworth Scholar). Part I. Crown 8vo., 2s. Part II. Crown 8vo., 3s.
- AN INTRODUCTION TO MACHINE DRAWING AND DESIGN.** By DAVID ALLAN LOW. With 153 Illustrations. Crown 8vo., 2s. 6d.

ELEMENTARY SCIENCE MANUALS—Continued.

- BUILDING CONSTRUCTION AND DRAWING.** By EDWARD J. BURRELL. With 308 Illustrations and Working Drawings. Crown 8vo., 2s. 6d.
- AN ELEMENTARY COURSE OF MATHEMATICS.** Containing Arithmetic; Euclid (Book I., with Deductions and Exercises); and Algebra. Crown 8vo., 2s. 6d.
- THEORETICAL MECHANICS.** Including Hydrostatics and Pneumatics. By J. E. TAYLOR, M.A., B.Sc. With numerous Examples and Answers, and 175 Diagrams and Illustrations. Crown 8vo., 2s. 6d.
- THEORETICAL MECHANICS—SOLIDS.** By J. E. TAYLOR, M.A., B.Sc. (Lond.). With 163 Illustrations, 120 Worked Examples, and over 500 Examples from Examination Papers, etc. Crown 8vo., 2s. 6d.
- THEORETICAL MECHANICS—FLUIDS.** By J. E. TAYLOR, M.A., B.Sc. (Lond.). With 122 Illustrations, numerous Worked Examples, and about 500 Examples from Examination Papers, etc. Crown 8vo., 2s. 6d.
- A MANUAL OF MECHANICS.** With 138 Illustrations and Diagrams, and 188 Examples taken from Examination Papers, with Answers. By T. M. GOODEVE, M.A. Crown 8vo., 2s. 6d.
- SOUND, LIGHT, AND HEAT.** By MARK R. WRIGHT, M.A. With 160 Diagrams and Illustrations. Crown 8vo., 2s. 6d.
- METALLURGY:** an Elementary Text-Book. By E. L. RHEAD. With 94 Illustrations. Crown 8vo., 3s. 6d.
- PHYSICS.** Alternative Course. By MARK R. WRIGHT, M.A. With 242 Illustrations. Crown 8vo., 2s. 6d.
- MAGNETISM AND ELECTRICITY.** By A. W. POYSER, M.A. With 235 Illustrations. Crown 8vo., 2s. 6d.
- PROBLEMS AND SOLUTIONS IN ELEMENTARY ELECTRICITY AND MAGNETISM.** By W. SLINGO and A. BROOKER. Embracing a Complete Set of Answers to the South Kensington Papers for the years 1885-1899, and a Series of Original Questions. With 67 Original Illustrations. Crown 8vo., 2s.
- ORGANIC CHEMISTRY:** the Fatty Compounds. By R. LLOYD WHITELEY, F.I.C., F.C.S. With 45 Illustrations. Crown 8vo., 3s. 6d.
- INORGANIC CHEMISTRY, THEORETICAL AND PRACTICAL.** By WILLIAM JAGO, F.C.S., F.I.C. With 63 Illustrations and numerous Questions and Exercises. Fcp. 8vo. 2s. 6d.
- AN INTRODUCTION TO PRACTICAL INORGANIC CHEMISTRY.** By WILLIAM JAGO, F.C.S., F.I.C. Crown 8vo., 1s. 6d.
- PRACTICAL CHEMISTRY:** the Principles of Qualitative Analysis. By WILLIAM A. TILDEN, D.Sc. Fcp. 8vo., 1s. 6d.
- ELEMENTARY INORGANIC CHEMISTRY.** By WILLIAM FURNEAUX, F.R.G.S. Crown 8vo., 2s. 6d.
- ELEMENTARY GEOLOGY.** By CHARLES BIRD, B.A., F.G.S. With Coloured Geological Map of the British Islands, and 247 Illustrations. Crown 8vo., 2s. 6d.
- HUMAN PHYSIOLOGY.** By WILLIAM FURNEAUX, F.R.G.S. With 218 Illustrations. Crown 8vo., 2s. 6d.
- A COURSE OF PRACTICAL ELEMENTARY BIOLOGY.** By J. BIDGOOD, B.Sc. With 226 Illustrations. Crown 8vo., 4s. 6d.
- ELEMENTARY BOTANY, THEORETICAL AND PRACTICAL.** By HENRY EDMONDS, B.Sc. With 342 Illustrations. Crown 8vo., 2s. 6d.
- STEAM.** By WILLIAM RIPPER, Member of the Institution of Mechanical Engineers. With 185 Illustrations. Crown 8vo., 2s. 6d.
- ELEMENTARY PHYSIOGRAPHY.** By J. THORNTON, M.A. With 13 Maps and 295 Illustrations. With Appendix on Astronomical Instruments and Measurements. Crown 8vo., 2s. 6d.
- AGRICULTURE.** By HENRY J. WEBB, Ph.D. With 34 Illustrations. Crown 8vo., 2s. 6d.

THE LONDON SCIENCE CLASS-BOOKS.


Edited by G. CAREY FOSTER, F.R.S., and by Sir PHILIP MAGNUS, B.Sc., B.A.,
of the City and Guilds of London Institute.

- ASTRONOMY. By Sir ROBERT STAWELL BALL, LL.D., F.R.S. With 41 Diagrams. Fcp. 8vo., 1s. 6d.
- MECHANICS. By Sir ROBERT STAWELL BALL, LL.D., F.R.S. With 89 Diagrams. Fcp. 8vo., 1s. 6d.
- THE LAWS OF HEALTH. By W. H. CORFIELD, M.A., M.D., F.R.C.P. With 22 Illustrations. Fcp. 8vo., 1s. 6d.
- MOLECULAR PHYSICS AND SOUND. By FREDERICK GUTHRIE, F.R.S. With 91 Diagrams. Fcp. 8vo., 1s. 6d.
- GEOMETRY, CONGRUENT FIGURES. By O. HENRICI, Ph.D., F.R.S. With 141 Diagrams. Fcp. 8vo., 1s. 6d.
- ZOOLOGY OF THE INVERTEBRATE ANIMALS. By ALEXANDER MACALISTER, M.D. With 59 Diagrams. Fcp. 8vo., 1s. 6d.
- ZOOLOGY OF THE VERTEBRATE ANIMALS. By ALEXANDER MACALISTER, M.D. With 77 Diagrams. Fcp. 8vo., 1s. 6d.
- HYDROSTATICS AND PNEUMATICS. By Sir PHILIP MAGNUS, B.Sc., B.A. With 79 Diagrams. Fcp. 8vo., 1s. 6d. (To be had also *with Answers*, 2s.) The Worked Solutions of the Problems. 2s.
- BOTANY. Outlines of the Classification of Plants. By W. R. MCNAB, M.D. With 118 Diagrams. Fcp. 8vo., 1s. 6d.
- BOTANY. Outlines of Morphology and Physiology. By W. R. MCNAB, M.D. With 42 Diagrams. Fcp. 8vo., 1s. 6d.
- THERMODYNAMICS. By RICHARD WORMELL, M.A., D.Sc. With 41 Diagrams. Fcp. 8vo., 1s. 6d.

PRACTICAL ELEMENTARY SCIENCE SERIES.

- ELEMENTARY PRACTICAL PHYSIOGRAPHY. (Section I.) By JOHN THORNTON, M.A. With 215 Illustrations and a Coloured Spectrum. Crown 8vo., 2s. 6d.
- ELEMENTARY PRACTICAL PHYSIOGRAPHY. (Section II.). A Course of Lessons and Experiments in Elementary Science for the Queen's Scholarship Examination. By JOHN THORNTON, M.A. With 98 Illustrations and a Series of Questions. Crown 8vo., 2s. 6d.
- PRACTICAL DOMESTIC HYGIENE. By J. LANE NOTTER, M.A., M.D., and R. H. FIRTH, F.R.C.S. With 83 Illustrations. Crown 8vo., 2s. 6d.
- A PRACTICAL INTRODUCTION TO THE STUDY OF BOTANY: Flowering Plants. By J. BRETLAND FARMER, F.R.S., M.A. With 121 Illustrations. Crown 8vo., 2s. 6d.
- ELEMENTARY PRACTICAL HYGIENE. Section I. By WILLIAM S. FURNEAUX. With 146 Illustrations. Crown 8vo., 2s. 6d.
- ELEMENTARY PRACTICAL SOUND, LIGHT, AND HEAT. By JOSEPH S. DEXTER. With 152 Illustrations. Crown 8vo., 2s. 6d.
- PRACTICAL MATHEMATICS. By A. G. CRACKNELL, M.A., B.Sc. Crown 8vo., 3s. 6d.
- ELEMENTARY PRACTICAL CHEMISTRY. By G. S. NEWTH, F.I.C., F.C.S. With 108 Illustrations and 254 Experiments. Crown 8vo., 2s. 6d.
- ELEMENTARY PRACTICAL PHYSICS. By W. WATSON, B.Sc. With 120 Illustrations and 193 Exercises. Crown 8vo., 2s. 6d.
- ELEMENTARY PRACTICAL ZOOLOGY. By FRANK E. BEDDARD, M.A. Oxon., F.R.S. With 93 Illustrations. Crown 8vo., 2s. 6d.
- ELEMENTARY BIOLOGY. By JOHN THORNTON, M.A. With 108 Illustrations. Crown 8vo., 3s. 6d.
- THE ELEMENTS OF GEOMETRICAL DRAWING: an Elementary Text-book on Practical Plane Geometry, including an Introduction to Solid Geometry. By HENRY J. SPOONER, C.E., M.Inst.M.E. Crown 8vo., 3s. 6d.





UNIVERSITY OF CALIFORNIA LIBRARY,
BERKELEY

**THIS BOOK IS DUE ON THE LAST DATE
STAMPED BELOW**

Books not returned on time are subject to a fine of 50c per volume after the third day overdue, increasing to \$1.00 per volume after the sixth day. Books not in demand may be renewed if application is made before expiration of loan period.

50m-3,'26

YC 12681

109259

T-4735

74

